




The installation of the glass wall is made by a subcontractor.

The horizontal structure is going to be fixed to the foundation, like the splicing channels, those are the supports for the mullions who will be put after. For the perfect fixation of the glass wall structure, it will have a fixation on the vertical face of the foundation, with the appropriate waterproofing sheet for preventing damages to that.

For the best thermal conditioning, the glass will have 3 layers, 2 of dobleglass (4+4 mm.) and an air chamber between them (16 mm.).




FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT	ADDRESS		
Sint-Barbara College - SITE PARKING	Savaanstraat 98-100 B-9000 Gent		
PLAN			
STUDENT		TUTOR	
Devís Sanjuan, Carlos		Peter Dantle	
SCHOOL	DATE	TUTOR	
KAHO Sint-Lieven - Aalst	22/06/2012	Lieve Weymeis	
IV DE PLAN	SCALE		
6	1 / 10		





On the upper part of the glass wall, it will be fixed to the perimetral beam. The anchor will be made by a "L" profile attached to the mullion and to the beam. At the height of 3.10 m. there's another horizontal profile, the mid frame. On the last part of the glass wall, from the mud frame to the upper frame, the glasses will be the same, but the inside glass is going to be an opaque glass to hide the concrete structure.

For the roof of the classes we are going to put a false ceiling made by plaster boards hanging from the alveolar slabs thanks to the hang pieces screwed to those.

The rail on the top of the perimetral beam is made with 3 pieces, the first one is embedded on the concrete and it is the support for the posts for the rail. The last piece is the screw to attach the other 2 pieces in to one, it has a doble female screw to be well fixed.



FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT: Sint-Barbara College - SITE PARKING		ADDRESS: Savaanstraat 98-100 B-9000 Gent	
PLAN: Detail 2 - Glass wall and terrace			
	STUDENT Devís Sanjuán, Carlos		
	SCHOOL KAHO Sint-Lieven - Aalst		DATE 22/06/2012
	Nº DE PLAN: 6	SCALE 1 / 20	TUTORS Peter Denie Lieve Weymeis



On the encounter of the terrace with the door hole we need to have a continuity of the insulation and the waterproof membrane. For the insulation we put 5 cm. of insulation in vertical, until the end of the threshold, made with brick on the bottom of the door.

The EPDM will need to be continuous until the end of the threshold and 15 cm. on the doorjamb. Over the EPDM in the threshold we put a stone gutter for preventing the wear and tear it could be exposed without the gutter.

For preventing the breaking of the EPDM we make a small slope for the encounter with the vertical parament so it don't have to be folded 90° cause it can break.

The anchor of the EPDM is made by a screw to the vertical parament, and for preventing water penetration another EPDM is overlapping the screw and fixed with blowtorch.

FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT		ADDRESS	
Sint-Barbara College - SITE PARKING		Savaanstraat 98-100 B-9000 Gent	
PLAN			
Detail 3 - Encounter terrace with door			
STUDENT		Devís Sanjuán, Carlos	
SCHOOL		DATE	
KAHO Sint-Lieven - Aalst		22/06/2012	
N° DE PLAN		TUTORS	
6		Peter Denie Lieve Weymeis	
SCALE			
1 / 20			

SPECIAL PIECE


DRIPCAP


WINDOW

GLASS (4+4 mm.)
AIR CHAMBER (16 mm.)
GLASS (4+4 mm.)

INSULATION

2.5

FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT: Sint-Barbara College - SITE PARKING		ADRESS: Savaanstraat 98-100 B-9000 Gent	
PLAN: Detail 5 - Theater window			
	STUDENT Devis Sanjuán, Carlos		
	SCHOOL KAHO Sint-Lieven - Aalst		DATE 22/06/2012
	N° DE PLAN: 6	SCALE 1 / 10	TUTORS Peter Denie Lieke Weumels




The roof of the theater is made with prefabricated alveolar slabs who rest in the walls. On the perimeter of the non-transitable roof there's a small beam like in the terrace.

Over the slabs there's a polyethylene plastic sheet as vapour barrier along all the roof, the next layers are the slope formation, made with lean concrete, the insulation (polystyrene rigid panels), the EPDM waterproofing membrane and on the last layer we place gravel. The gravel is too heavy and that's why we don't need to fix the insulation with screws.

On the edge of the beam there's a wood board to fix with struts the aluminum drip, this board is fixed to the beam with some screws too, fixing also the vapour barrier. To prevent water penetration, we overlap the EPDM over the screw head.

Inside the building, for the acoustical conditioning for the theater, there are rock wool panels installed, glued to the wall ans to the floor, and over them, a piramidal acoustic foam is placed to perform the acoustic of the place.





For the fixation of the insulation we use a screw with a dowel, and for the finishing of the external face of the wall, a reinforcement fiberglass grid is placed over the insulation and the fixation screws.

At last a layer of plaster is placed to finish the wall.

FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT		ADDRESS	
Sint-Barbara College - SITE PARKING		Savaanstraat 98-100 B-9000 Gent	
PLAN			
STUDENT		Detail 4 - Wall and theater roof	
STUDENT		Devís Sanjuán, Carlos	
SCHOOL		DATE	
KAHO Sint-Lieven - Aalst		22/06/2012	
Nº DE PLAN		TUTORS	
6		Peter Denie Lieve Weymeis	
SCALE			
1 / 10			

After the demolition and the debris transport to the dump we have the ground cleared to start with the foundation excavation in height ±0.00m.

First of all we start with an excavation until -0.46m. for the entire slab. On the last 2 m. to the perimeter, we excavate until -0.52m. and on the perimeter until -1.12m. leaving a 45° of batter on the inside, and 60° on the outside for prevention for landslides.




When we reach the -1.12m. we place a 10cm. of lean concrete at the bottom at the trench of the slab perimeter and after the installation of the insulation and the armor for the slab perimeter we fill the holes with the land we excavate and put a 10cm. of lean concrete in the rest of the slab taking care of making the step in the last 2m. of the perimeter.


FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT:		ADDRESS:	
Sint-Barbara College - SITE PARKING		Savaanstraat 98-100 B-9000 Gent	
PLAN:			
STUDENT		Details of foundation in classes - Part 1	
Devis Sanjuán, Carlos			
SCHOOL:		DATE:	
KAHO Sint-Lieven - Aalst		22/06/2012	
TYPE PLAN:		TUTORS:	
2		Peter Denie Lieve Weymeis	
SCALE:			
1 / 50			



When the lean concrete is dry enough, we proceed to the placement of the insulation, on the entire slab we put 6 cm. of that, but on the last 2 meters on the perimeter of the slab, we put 12 cm. for safety. When the insulation is being installed, we proceed to place the rest of the slab armor on the places where the insulation is already installed. The quantity of armor is 75 kg/m³ of iron B-500S , and after the placement of those, we proceed with the pouring of concrete, taking care and vibrating it correctly. When all the slab is concreted, we wait, at least, for 7 days before starting another work on the top of it.





FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT: Sint-Barbara College - SITE PARKING		ADDRESS: Savaanstraat 98-100 B-9000 Gent	
PLAN: Details of foundation in classes - Part 2			
STUDENT Dev's Sanjuán, Carlos		DATE 22/06/2012	
SCHOOL: KAHO Sint-Lieven - Aalst		TUTORS Peter Dantle Lieve Weymeis	
Nº DE PLAN: 3		SCALE 1 / 50	




After 7 days of pouring the concrete, we start with the brick walls for the delimitation of the classes, those walls will be made with perforated bricks, and they will support the slabs of the terrace on top of them. As a delimitation, we will create a beam along the perimeter, for the construction of it we will use at least 1 strut every 2 meters and the convenient formwork for it.


The walls will reach the 3.50 metres and it will be made by 2 different brick walls separated by 2 cm. of fiber glass for the insulation of them.



FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT: Sint-Barbara College - SITE PARKING		ADDRESS: Savaanstraat 98-100 B-9000 Gent	
PLAN:			
STUDENT Davis SanJuan, Carlos		Construction of brick walls and perimetral beam	
SCHOOL KAHO Sint-Lieven - Aalst		DATE 22/06/2012	
IN DE PLAN 4		SCALE 1 / 50	
		TUTORS Peter Denie Lieve Weymeis	









When the brick walls are finished and the perimetral beam has his formwork removed, we proceed to the placement of the alveolar slabs. Those slabs are 1 meter wide and they rest on the top of the brick walls, on a plaster mortar of 2 cm. for preventing the breaking of the bricks. The rest will have a minimum of 10 cm. and the slabs will rest in the middle of the span on a timber plank supported by struts. The joints between slabs are going to be filled with reinforced concrete with iron B500-S for the negative moments of the structure in the resting places, connecting the slabs and making it like a bigger one.

The glass wall structure will be installated at the same time, anchoring it to the perimetral beam on the top, and to the foundation on the bottom. This structure is the "*Courtain wall: MX Structural VEE*" of TECHNICAL.



FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT:	Sint-Barbara College - SITE PARKING	ADDRESS:	Savaanstraat 98-100 B-9000 Gent
PLANT:	Placement of alveolar slabs and glass wall structure		
STUDENT	Devis Sanjuán, Carlos		
SCHOOL:	KAHO Sint-Lieven - Aalst	DATE:	22/06/2012
TYPE PLAN:	5	SCALE:	1 / 50
		TUTOR:	Peter Denie Lieve Weymeis






For the construction of the terrace, we start with the vapour barrier, a polyethylene plastic sheet placed in contact with the slabs, on top of it we will place a layer of lean concrete to make the slope for water evacuation, not more than 1-5%. Over the slope formation we will place the insulation, 20 cm. of expanded polystyrene rigid panels, they will be not fixed because the weight of the coming tiles will be enough to keep them on place in the worst case. The next layer is the EPDM, the waterproofing membrane.

Both the EPDM and the vapour barrier are going to continue along the parimetral beam and they are going to be fixed on the top of it with a screw.

The glass wall and the floor of the classes will be installed when the terrace is done. On the floor, after the placement of the PUR, placed by projection for preventing the joint and have a better thermal insulation. Over the PUR we place the “*Grupo Cecatherm*” floor heating system, based on a pipe net on the floor between the PUR and the tiles, embedded on concrete. At last, we place the tiles, glued to the concrete.

FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT: Sint-Barbara College - SITE PARKING		ADDRESS: Savaanstraat 98-100 B-9000 Gent	
PLAN: Finishing of terrace and glass wall installation			
STUDENT Dev's Sanjuán, Carlos		DATE 22/06/2012	
SCHOOL KAHO Sint-Lieven - Aalst		TUTORS Peter Dente Lieve Weymeis	
N° DE PLAN: 6		SCALE 1 / 50	





FINAL PROJECT OF BUILDING ENGINEERING			
PROJECT: Sint-Barbara College - SITE PARKING		ADDRESS: Savaanstraat 98-100 B-9000 Gent	
PLAN: Section			
STUDENT Devís Sanjuán, Carlos			
SCHOOL: KAHO Sint-Lieven - Aalst		DATE 22/06/2012	
Nº DE PLAN: 1	SCALE 1 / 200	TUTORS Peter Denie Lieve Weymeis	
