

Company: VIAConstruction Ltd

Handbook
For project and construction management

PROCESCONTROLPLAN:

Case: SVANEKØKKENET AARHUS

Nr.:

Rev.: Concrete works

Aktivitet	Controlled by	Control	Controlmethod	Accepting criteria	Dokumentation of control	Remarks
Reinforcement (Steel)	Foreman	Reinforcement works must be controlled before each pour.	Visual, measurement and physical test	± 2 mm	Journal	
Formworks	Foreman	Formwork must be controlled before each pour is implemented.	Visual + Measure + Physical test	/	Journal	

Company: VIAConstruction Ltd

*Handbook
For project and construction management*

Concrete	Foreman	Casting is controlled at minimum: - first pour and per 10th repetition. - critical activities, e.g., at rebates close to reinforcement and complicated geometry - substantial alteration, e.g., for alteration of method and design.	Visual and Measurement	/	Journal	
-----------------	---------	---	------------------------	---	---------	--

Skema 3.