


FINAL PROJECT PRESENTED AT:  
KAHO SINT LIEVEN  
OPLEIDING PROFESSIONELE BACHELOR BOUW.

BACHELOR FINAL PROJECT  
EINDWERK-STAGE (LIVE IT)

SHELTERED AND DAY CARE FLATS THE MOUWERIJ



ANA SUCH FUSTER  
UNIVERSITAT POLITÈCNICA DE VALÈNCIA  
KAHO SINT LIEVEN

## INDEX:

### PART 0: PRESENTATION OF THE BUILDING SITE.

<b>N.PLANE TOTAL</b>	<b>PLANE NAME</b>	<b>N.PLANE PART</b>
1/28	SITUATION PLAN	1/1

### PART 1: SITE INSTALLATION PLAN.

<b>N.PLANE TOTAL</b>	<b>PLANE NAME</b>	<b>N.PLANE PART</b>
2/28	GENERAL PLAN	1/3
3/28	CRANE-ORGANIZATION SITE	2/3
4/28	ACCESS-UTILITIES-TO KEEP	3/3

### PART 2: PRINCIPAL CROSS/LONGITUDINAL SECTION

<b>N.PLANE TOTAL</b>	<b>PLANE NAME</b>	<b>N.PLANE PART</b>
5/28	COMPLET SECTION 1/150	1/2
6/28	DETAILED PLAN 1/20	2/2

### PART 3: ADITTIONAL DETAILED DRAWINGS

<b>N.PLANE TOTAL</b>	<b>PLANE NAME</b>	<b>N.PLANE PART</b>
7/28	DETAIL 1 2	1/7
8/28	DETAIL 3 4	2/7
9/28	DETAIL 5 6 7	3/7
10/28	DETAIL 8 9	4/7
11/28	DETAIL 10.1, 10.2, 11.1, 11.2	5/7
12/28	DETAIL 12 13	6/7
13/28	DETAIL 14 15	7/7

### PART 4: TECHNICAL STUDY

<b>N.PLANE TOTAL</b>	<b>PLANE NAME</b>	<b>N.PLANE PART</b>
14/28	STEP 1 2 3	1/14
15/28	STEP 4 5	2/14
16/28	STEP 6 7	3/14
17/28	STEP 8 9	4/14
18/28	STEP 10 11	5/14
19/28	STEP 12 13	6/14
20/28	STEP 14 15	7/14
21/28	STEP 16 17	8/14
22/28	STEP 18 19	9/14
23/28	STEP 20 21	10/14
24/28	STEP 22 23	11/14
25/28	STEP 24 25 26 27	12/14

26/28	STEP 28 29 30 31	13/14
27/28	STEP 32 33 34	14/14

**PART 5: COMPARATIVE STUDY.**

<b>N.PLANE TOTAL</b>	<b>PLANE NAME</b>	<b>N.PLANE PART</b>
28/28	SITUATION PLAN	1/1

**PART 6: SCHEDULING AND PRICING.**

6.1. BASE CALENDAR

6.2. RESOURCE USAGE

6.3. GANT

6.4. TASK USAGE

6.5. WHO DOES WHAT

6.6. CASH FLOW

**PART 7: TECHNICAL DOCUMENTS**

7.1. TOWER CRANE LIEBHERR (154 EC H6 LITRONIC)

7.2. STREMAFORM WATERPROOF (TYPE 3077)

7.3. PREDAL GSS (GILBERT STEEL SOLUTIONS)

7.4. STABOX (TYPE S)

7.5. QUEMICAL ANCHOR HILTI (HIT-HY 200-A)

7.6. VANDERSANDEN MORVAN (ZWART)/ RIJSWAARD ENGELS BONT (ROOD)

**INTRODUCTION:**

THIS PROJECT IS ABOUT THE CONSTRUCTION OF SHELTERED AND DAY CARE FLATS THE MOUWERIJ, LOCATED IN THE CORNER OF ARBEIDSTRAAT AND NIJWBEEKSTRAAT, 9300, AALST.

THE BUILDING HAVE GROUND FLOOR WHERE WILL BE THE RESTAURANT AND COMMON AREAS, AND 7 FLOORS, WITH FLATS, WITH A SURFACE IN PLANT=756 M2, AND IN TOTAL 5943M2.



AS A STARTING POINT WE FIND THAT THE BUILDING WILL BE BUILD ABOVE THE FOUNDATION OF AN OLD BUILDING DEMOLISHED LAST YEAR. WE FIND ALSO THE FACADES OF BOTH STREETS, WHICH HAS TO BE PROTECTED.

THE WORKS WAS STARTED ON 3-DECEMBER-2012. ONLY SIX MONTHS HAVE PASSED, AND NOW THEY ARE BUILDING THE STRUCTURE OF FLOOR 5, THEY HAVE ALREADY STARTED THE FACADE OF THE FIRST FLOOR, AND THE PARTITIONING AND FACILITIES.

THAT IS POSSIBLE BECAUSE PRACTICALLY ALL THE SITE IS PREFABRICATED, AND ALSO THERE ARE 15 PEOPLE WORKING AT THE SAME MOMENT.



SITUATION PLAN\_S:1/1500



COMMISSONER :  
SILVERSTONE NV, WOLUWEDAL 58, 1200 BRUSSEL

KAHO TUTOR:  
FRANK VERPLANKEN


CONTRACTOR'S PROJECT MANAGER:  
STEVEN SCHYVYNCK , BARREZ IGMAR

CONTRACTOR:  
JAN DE NUL NV  
TRAGEL 60, 9308 HOFSTADE-AALST  
BELGIUM



KaHoSl. - Campus Dirk Martens,  
Kwalestraat 154  
9320 Aalst-Belgium  
Academic schoolyear 2012-2013







LOCATION OF THE CONSTRUCTION CRANE ON SITE

THE TOWER CRANE IS PLACED INSIDE THE FUTURE BUILDING, USING ONE OF THE ELEVATOR SHAFTS.

SINCE THE BUILDING HAS THREE ELEVATOR SHAFTS, WE HAS CHOSEN TO PLACE IT IN THE MOST CENTRED OF THE THREE.


IN THIS WAY WE NEED A RADIUS OF 40 METERS TO REACH THE STOCKPILE AREA AND THE DEBRIS AREA.

SECONDLY, WE NEED AT LEAST 34,20 M HIGHT, BECAUSE OUR BUILDING HAVE 30,20 M. SINCE THE FOUNDATION OF THE CRANE, TO THE MOST ELEVATED PONT OF THE BUILDING.


WE CHOOSE THE MODEL: LIEBHERR 1 54 EC-HS LITRONIC

FINALLY, WE NEED TO KNOW THE LIFTING CAPACITY AND THE LIFT CAPACITY, AS WE WORK WITH PRECAST ELEMENTS. SO LM1=4.000 KG. LM2=4.500 KG. IS ENOUGH FOR US.

ABOUT THE ADJACENT BUILDINGS AND THEIR PROTECTION, THERE AREN'T ANY PROBLEM, BECAUSE THIS BUILDINGS HAVE AT MOST 5 FLOORS, AND OUR BUILDINS HAVE 8 FLOORS.



<b>LIEBHERR</b>	<b>154 EC-H6 Litronic</b>
Wn :	47806
HH	36,3 m
Gieklenkte:	40 m
Uitvoering :	betonsokkel





		154 EC-H6																		
m	r	m/kg	22,0	24,0	26,0	28,0	30,0	32,0	34,0	36,0	38,0	40,0	42,0	45,0	48,0	50,0	52,0	55,0	58,0	60,0
60,0	(r = 61,4)	2,2-20,8 600	5570	5050	4610	4230	3910	3620	3370	3150	2950	2780	2610	2400	2210	2100	2000	1850	1730	1650
50,0	(r = 56,4)	2,2-22,8 600	6000	5620	5130	4720	4360	4050	3770	3530	3310	3120	2940	2700	2490	2370	2290	2100		
50,0	(r = 51,4)	2,2-25,1 600	6000	6000	5770	5310	4920	4570	4260	3990	3750	3530	3330	3070	2840	2700				
45,0	(r = 46,4)	2,2-26,3 600	6000	6000	6000	5610	5190	4830	4500	4220	3960	3730	3530	3250						
40,0	(r = 41,4)	2,2-28,0 600	6000	6000	6000	5990	5550	5160	4820	4510	4240	4000								

		LM1	
kg	m	LM1	LM2
6000	40,0	4000	4500
5000	45,0	3700	4200
4000	50,0	3300	3800
3000	55,0	2900	3400
2000	60,0	2500	3000

LOCATION FOR TEMPORARY STORAGE OF MATERIAL AND CONSUMER GOODS



THE TEMPORARY STORAGE OF MATERIAL AND CONSUMER GOODS ARE LOCATED NEAR THE TRUKS ENTRY AND INSIDE THE CRANE'S RADIO.



LOCATION OF SITE OFFICES AND BUILDING SUPERVISOR'S OFFICES

THE SITE OFFICES AND BUILDING SUPERVISOR'S OFFICES ARE LOCATED NEXT TO THE BUILDING TO BE CONSTRUCTED, AND AN EXISTING STRUCTURE OF THE OLD BUILDING WHICH SERVES TO STABILIZE THE PROTECTED FACADE.

IN TOTAL WE HAVE 5 PROVISIONALS HOUSES.






**TEMPORARY SITE ACCESS ROADS, FENCED AND SIGNALING**

WE HAVE 2 DIFFERENT ACCESS, ONE FOR WORKER'S CARS TO PARK INSIDE THE SITE, SITUATED IN NIEUWBEEKSTRAAT, AND THE OTHER ONE, SITUATED IN ARBEIDSTRAAT, IS THE TRUCKS ENTRY. HERE THERE ARE MORE SPACE FOR MANEUVERING. HOWEVER WE HAVE TO CHANGE THE DIRECTION OF THE STREET AND WE HAVE TO PUT MORE SIGNALING.

WE HAVE OCCUPIED THE SIDEWALK AND PART OF THE ROAD IN AREAS WHERE ARE LOCATED FRONT STABILIZERS, THEREFORE, WE HAD TO ILLUMINATE THE ROAD WITH EMERGENCY LIGHTS FLASHING.



**AVAILABLES UTILITIES**

**WATER:** DISCONTINUOUS BLUE MARKING ON THE GENERAL PLAN, IS LOCATED ON ARBEIDSTRAAT, ENTERING TO THE SITE, NEXT TO THE SITE OFFICES. (PICTURE 1)

**ELECTRICITY:** WE USE AN ELECTRIC GENERATOR FOR THE SITE.

**SANITATION:** WE HAVE TOILETS CABINS WITH THEM OWN EVACUATION SYSTEM. THE REST OF EVACUATION FLOWS DIRECTLY TO THE GROUND.



**MEANS OF CONNECTION FOR THE LATTER (UNDERGROUND, AIR SUPPORTED,...): EXISTING FOUNDATIONS**


OUR BUILDING WILL BE CONSTRUCTED ABOVE THE FOUNDATIONS OF AN ANCIENT BUILDING.

AFTER CHECKING ITS RESISTENCE, WE REINFORCE, WHERE WILL BE NECESSARY, WITH ADDITIONAL FOUNDATION.

WE WILL NEED MORE DEPTH FOR THE FOUNDATIONS OF THE LIFT SHAFTS AND THE TOWER CRANE FOUNDATION. SO HERE, WE WILL PROCEED WITH THE DEMOLITION AND POSTERIOR EXCAVATION.

IN PART 4: TECHNICAL STUDY, WE DESCRIBE, STEP BY STEP, HOW TO PERFORM THIS PROCESS. THE EXISTING FOUNDATION WAS EXPOSED TO THE WEATHER MORE THAN A YEAR, SO WE HAD TO ELIMINATE THE CUMULATIVE WATER OF THE INSIDE, USING A DRAIN PUMPS.


AFTER THAT WE WOULD PROCEED TO THE CLEANING FOUNDATIONS.



**LOCATION OF UTILITIES THAT REQUIRES SPECIAL ATTENTION DURING CONSTRUCTION: PROTECTED WALL TO KEEP**

IS IMPORTANT TO KEEP THIS IN MIND FROM THE BEGINNING OF THE ORGANIZATION OF THE WORK, UNTIL THE COMPLETION OF THE STRUCTURE, FACADE AND FINISHES.

BY HAVING DIFFERENT HEIGHT AND FINISHES ON THE WALLS TO MAINTAIN, THEY USED TWO DIFFERENT SYSTEMS FOR THE FRONT STABILIZERS, PLACED BEFORE WE START THE WORK.






PICTURES FIRST VISIT



PICTURES LAST VISIT



PRINCIPAL CROSS SECTION COMPLET BUILDING\_ S:1/150




HORIZONTAL STRUCTURE CROSS, FIRST FLOOR\_E:1/300



-  SAND BROKEN CONCRETE
-  STRUCTURE
-  GROUND
-  PRE-EXISTING FOUNDATIONS





D.8= COMPLET STAIR  
D.15= PREFABRICATED BALCONY


- GROUND
- SAND BROKEN CONCRETE
- PREFABRICATED CONCRETE
- "YTONG" AERATED CONCRETE
- PRE-EXISTING FOUNDATIONS
- "IN SITU" CONCRETE
- "UTHERM" INSULATION
- CELLULAR CONCRETE

BACHELOR FINAL PROJECT/EINDWERK-STAGE (LIVE IT)


FINAL PROJECT PRESENTED AT:  
KAHO SINT LIEVEN  
OPLEIDING PROFESSIONELE BACHELOR BOUW.




DETAIL 1: FACADE STARTING-WALL S:1/10




DETAIL 1: FACADE STARTING-WINDOW S:1/5



DETAIL 2: FACADE STARTING-WINDOW S:1/10




DETAIL 1: FACADE STARTING-WALL S:1/5







DETAIL 3: FACADE-WINDOW \_ S:1/10




DETAIL 4: UNION COLUMN-BEAM-FLOOR \_ S:1/10



DETAIL 3: FACADE-WINDOW \_ S:1/5




DETAIL 4: UNION COLUMN-BEAM-FLOOR \_ S:1/5







DETAIL 5: UNION FOUNDATION-COLUMN \_ S:1/10




DETAIL 6: UNION WALL - FLOOR \_ S:1/10



DETAIL 7: UNION FOUNDATION - WALL \_ S:1/10




DETAIL 7: UNION FOUNDATION-COLUMN \_ S:1/7.5







DETAIL 8: PREFABRICATED STAIR \_ S:1/25



DETAIL 8: UNION STAIR-FOUNDATION \_ S:1/5




DETAIL 9: UNION STAIR-FOUNDATION \_ S:1/10







DETAIL 11.1: UNION PREFABRICATED STAIR-IN SITU FLOOR \_S:1/10




DETAIL 11.2: UNION PREFABRICATED STAIR-IN SITU FLOOR \_S:1/10




DETAIL 10.1: UNION PREFABRICATED STAIR-IN SITU WALL \_S:1/10





DETAIL 10.2: UNION PREFABRICATED STAIR-IN SITU WALL \_S:1/10




Compressed air cleaning (all diameter and length of hole)




DETAIL 12: UNION TERRACE-TERRACE\_KITCHEN\_S: 1/5




DETAIL 13: BOTTOM WALL - FLOOR \_ S:1/5



DETAIL 12: UNION TERRACE-TERRACE\_KITCHEN\_S: 1/10




DETAIL 13: UNION TERRACE-TERRACE-FACADE\_S: 1/10







DETAIL 13: UNION TERRACE-RESTAURANT\_FACADE\_S: 1/10




DETAIL 14: UNION BALCONY-FACADE\_S: 1/5



DETAIL 14: UNION BALCONY-FACADE\_S: 1/10



DETAIL 13: UNION WINDOW - RESTAURANT\_S: 1/5







PREVIOUS STEP: STARTING SITUATION




STEP 1: TAKE OUT THE WATER OF THE FOUNDATION+CLEANING FOUNDATIONS\_S: 1/40



STEP 2: STAKEOUT AREA TO DEMOLISH AND DEMOLITION OF EXISTING FOUNDATION\_S: 1/40




STEP 3: EXCAVATION UNTIL COTE -3,00 M / OTHER TWO LIFT-CASE COTE -1,90 M\_S: 1/40




MACHINES




NEXT STEP: 4 \_ S: 1/80




PREVIOUS: STEP 3 \_ S:1/80



STEP 4: PUT THE CLEANING CONCRET (10 cm) + VERTICAL PLASTIC \_ S:1/40




DETAIL STEP 4 \_ S:1/20





- PROTECTOR PLASTIC: TO AVOID THE POSSIBLE LANDSLIDE WHILE THE CONCRETE IS BEING POURED.
- CLEANING CONCRET: TO GET A SMOOTH SURFACE WORK AND PROTECT THE STEEL AND THE CONCRET.


STEP 5 \_ S:1/40




DETAIL STEP: 5 \_ S:1/20




NEXT STEP: 6 \_ S:1/80




PREVIOUS: STEP 5 \_ S:1/80




STEP 6 \_ S:1/40




DETAIL STEP 6 \_ S:1/20




STEP 7 \_ S:1/40



DETAIL STEP 7 \_ S:1/20




NEXT: STEP 8 \_ S:1/80







PREVIOUS STEP 7 \_ S:1/80




DETAIL STEP 8 \_ S:1/20




STEP 8: COLOCATE ARMOR Ø20S15 \_ S:1/40




STEP 9: COLOCATE FIRS PARTO OF TOWER CRANE \_ S:1/40



DETAIL STEP 9 \_ S:1/20




NEXT STEP: 8 \_ S:1/80







PREVIOUS STEP 9 \_ S:1/80




DETAIL STEP 10 \_ S:1/20




STEP 11: COLOCATE STREMAFORM \_ S:1/40




STEP 10: COLOCATE SUPERIOR ARMOR Ø20S15 \_ S:1/40




DETAIL STEP 11 \_ S:1/20




NEXT STEP: 12 \_ S:1/80




PREVIOUS STEP 11 \_ S:1/80




DETAIL STEP 12 \_ S:1/20




STEP 12: STEEL WORKING WALLS Ø12S10 \_ S:1/40




STEP 13: CONCRET WORKING \_ S:1/40




DETAIL STEP 13 \_ S:1/20




NEXT STEP: 14 \_ S:1/80




PREVIOUS STEP 13 \_ S:1/80




STEP 14: FORMWORK ADDITIONAL FOUNDATION(ONE SIDE) \_ S:1/40




DETAIL STEP 14 \_ S:1/20




STEP 15: FORMWORK WALLS (TWO SIDES) \_ S:1/40



DETAIL STEP 15 \_ S:1/20




NEXT STEP: 16 \_ S:1/80







PREVIOUS STEP 15 \_ S:1/80




STEP 16: STEEL WORKING REFORCE, Ø16+Ø12S15 \_ S:1/40




DETAIL STEP 16 \_ S:1/20




STEP 17: CHEMICAL ANCHOR, Ø12S30 \_ S:1/40



DETAIL STEP 17 \_ S:1/20




NEXT STEP: 18 \_ S:1/90







PREVIOUS STEP 17\_ S:1/90




STEP 18: STEEL WORKING WALLS, 150x150, 8x8 \_ S:1/40




DETAIL STEP 18 \_ S:1/20




STEP 19: STEEL WORKING, Ø12S15 \_ S:1/40




DETAIL STEP 19 \_ S:1/20




NEXT STEP: 20 \_ S:1/90




PREVIOUS STEP 19 \_ S:1/90




DETAIL STEP 18 \_ S:1/20




STEP 20: STEEL WORKING WALLS, Ø12s15 \_ S:1/40




STEP 21: STEEL WORKING CONNECTION WALLS, Ø8S15 \_ S:1/40



DETAIL STEP 21 \_ S:1/20




NEXT STEP: 22 \_ S:1/90







PREVIOUS STEP 21 \_ S:1/90




DETAIL STEP 22 \_ S:1/20




STEP 22: CONCRET WORKING (-0'28M) \_ S:1/40




STEP 23: FORMWORK ZONE OTHER WALLS-COLUMNS \_ S:1/40




DETAIL STEP 23 \_ S:1/20




NEXT STEP: 24 \_ S:1/90




PREVIOUS STEP 23\_ S:1/90




STEP 24: STEEL WORKING  $\varnothing 16 + \varnothing 12 \text{ S}15$  \_ S:1/20




STEP 25: QUEMICAL ANCHOR,  $\varnothing 12 \text{ S}30$




STEP 27 \_ REMOVE FORMWORK S:1/40




STEP 26: CONCRET WORKING



DETAIL STEP: 27 \_ S:1/20




NEXT STEP: 28 \_ S:1/90







PREVIOUS STEP 27\_ S:1/90




STEP 28:FILL THE SPACES WITH SAND(RECICLED FROM BROKEN CONCRETE) \_ S:1/40




STEP 29:CONSOLIDATION+PE FOIL \_ S:1/20




DETAIL STEP 28 \_ S:1/20




STEP 30: STEEL WORKING FLOOR, 150x150x8x8 \_ S:1/40




STEP 31:CONECTION WALL, Ø8S15 \_ S:1/20



FINAL STEP: STEP 32





STEP 32: CONCRET WORKING UNTIL - 0,16 M. \_ S:1/40












STEP 33: FORMWORK WALLS \_ S:1/40

STEP 34: STEEL WORKING WALLS. \_ S:1/40





M2	VUKSTENEN BETOM FLOOR	PREDALLEN PREFABRICATED FLOOR																																																																																																																																																																																																																																																																																																																											
	EDGE=22+5 CM 35 N/MM2 4-6M. DISTANCE BETWEEN BEAMS	EDGE=20 CM 35 N/MM2 4-6M. DISTANCE BETWEEN BEAMS																																																																																																																																																																																																																																																																																																																											
MATERIALS	 	 																																																																																																																																																																																																																																																																																																																											
	<table border="1"> <thead> <tr> <th rowspan="2">QNT</th> <th rowspan="2">UT</th> <th rowspan="2">DESCRIPTION</th> <th colspan="2">SPAIN</th> <th colspan="2">BELGIUM</th> </tr> <tr> <th>€/UT</th> <th>€</th> <th>€/UT</th> <th>€</th> </tr> </thead> <tbody> <tr> <td>0,207</td> <td>h</td> <td>CAT IV</td> <td>22,91</td> <td>4,742</td> <td>32,84</td> <td>6,798</td> </tr> <tr> <td>0,207</td> <td>h</td> <td>CAT III</td> <td>22,53</td> <td>4,664</td> <td>30,3</td> <td>6,272</td> </tr> <tr> <td>0,104</td> <td>h</td> <td>CAT II</td> <td>21,9</td> <td>2,278</td> <td>28,49</td> <td>2,963</td> </tr> <tr> <td>0,099</td> <td>h</td> <td>MEESTERGAST</td> <td>23,91</td> <td>2,367</td> <td>39,45</td> <td>3,906</td> </tr> <tr> <td>0,099</td> <td>h</td> <td>CAT IV STEEL</td> <td>21,31</td> <td>2,110</td> <td>32,84</td> <td>3,251</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td>16,160</td> <td></td> <td>23,190</td> </tr> <tr> <td>0,009</td> <td>h</td> <td>CONCRETE PLUMP</td> <td>112,9</td> <td>1,016</td> <td>129,83</td> <td>1,168</td> </tr> <tr> <td>0,1</td> <td>h</td> <td>VIBRATOR GASOIL 30-50 mm</td> <td>1,42</td> <td>0,142</td> <td>1,652</td> <td>0,165</td> </tr> <tr> <td>1,15</td> <td>kg</td> <td>B 500 S D6-25</td> <td>0,61</td> <td>0,702</td> <td>0,701</td> <td>0,806</td> </tr> <tr> <td>5,4</td> <td>kg</td> <td>ELABORATED B 500 S</td> <td>0,9</td> <td>4,860</td> <td>1,035</td> <td>5,589</td> </tr> <tr> <td>0,07</td> <td>m3</td> <td>CONCRET 35n/mm2- soft-20.IIa</td> <td>78,08</td> <td>5,466</td> <td>89,79</td> <td>6,285</td> </tr> <tr> <td>1,465</td> <td>m</td> <td>beam h18</td> <td>5,63</td> <td>8,248</td> <td>6,474</td> <td>9,484</td> </tr> <tr> <td>0,1</td> <td>m3</td> <td>WATER</td> <td>1,89</td> <td>0,189</td> <td>2,173</td> <td>0,217</td> </tr> <tr> <td>7,1</td> <td>U</td> <td>VULSTENEN BETOM 70 59x22cm</td> <td>0,79</td> <td>5,609</td> <td>0,908</td> <td>6,447</td> </tr> <tr> <td>1,05</td> <td>m2</td> <td>500T 15x30 d5-5</td> <td>1,25</td> <td>1,313</td> <td>1,437</td> <td>1,509</td> </tr> <tr> <td>1,05</td> <td>m2</td> <td>FORMWORK BEAM</td> <td>13,39</td> <td>14,060</td> <td>15,42</td> <td>16,191</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td>41,603</td> <td></td> <td>47,862</td> </tr> <tr> <td colspan="3"><b>TOTAL</b></td> <td colspan="2">57,764</td> <td colspan="2">71,052</td> </tr> <tr> <td colspan="3">TOTAL % SUPERIOR</td> <td colspan="2"></td> <td colspan="2">23,01</td> </tr> <tr> <td colspan="3">WORKERS % SUPERIOR</td> <td colspan="2"></td> <td colspan="2">43,496</td> </tr> <tr> <td colspan="3">MATERIAL % SUPERIOR</td> <td colspan="2"></td> <td colspan="2">15,045</td> </tr> <tr> <td colspan="3">TOTAL HOUR/M2</td> <td colspan="2">0,306</td> <td colspan="2"></td> </tr> </tbody> </table>	QNT	UT	DESCRIPTION	SPAIN		BELGIUM		€/UT	€	€/UT	€	0,207	h	CAT IV	22,91	4,742	32,84	6,798	0,207	h	CAT III	22,53	4,664	30,3	6,272	0,104	h	CAT II	21,9	2,278	28,49	2,963	0,099	h	MEESTERGAST	23,91	2,367	39,45	3,906	0,099	h	CAT IV STEEL	21,31	2,110	32,84	3,251					16,160		23,190	0,009	h	CONCRETE PLUMP	112,9	1,016	129,83	1,168	0,1	h	VIBRATOR GASOIL 30-50 mm	1,42	0,142	1,652	0,165	1,15	kg	B 500 S D6-25	0,61	0,702	0,701	0,806	5,4	kg	ELABORATED B 500 S	0,9	4,860	1,035	5,589	0,07	m3	CONCRET 35n/mm2- soft-20.IIa	78,08	5,466	89,79	6,285	1,465	m	beam h18	5,63	8,248	6,474	9,484	0,1	m3	WATER	1,89	0,189	2,173	0,217	7,1	U	VULSTENEN BETOM 70 59x22cm	0,79	5,609	0,908	6,447	1,05	m2	500T 15x30 d5-5	1,25	1,313	1,437	1,509	1,05	m2	FORMWORK BEAM	13,39	14,060	15,42	16,191					41,603		47,862	<b>TOTAL</b>			57,764		71,052		TOTAL % SUPERIOR					23,01		WORKERS % SUPERIOR					43,496		MATERIAL % SUPERIOR					15,045		TOTAL HOUR/M2			0,306				<table border="1"> <thead> <tr> <th rowspan="2">QNT</th> <th rowspan="2">UT</th> <th rowspan="2">DESCRIPTION</th> <th colspan="2">SPAIN</th> <th colspan="2">BELGIUM</th> </tr> <tr> <th>€/UT</th> <th>€</th> <th>€/UT</th> <th>€</th> </tr> </thead> <tbody> <tr> <td>0,09</td> <td>h</td> <td>CAT IV</td> <td>22,91</td> <td>2,062</td> <td>32,84</td> <td>2,956</td> </tr> <tr> <td>0,09</td> <td>h</td> <td>CAT III</td> <td>22,53</td> <td>2,028</td> <td>30,3</td> <td>2,727</td> </tr> <tr> <td>0,045</td> <td>h</td> <td>CAT II</td> <td>21,9</td> <td>0,986</td> <td>28,49</td> <td>1,282</td> </tr> <tr> <td>0,122</td> <td>h</td> <td>MEESTERGAST</td> <td>23,91</td> <td>2,917</td> <td>39,45</td> <td>4,813</td> </tr> <tr> <td>0,122</td> <td>h</td> <td>CAT IV STEEL</td> <td>21,31</td> <td>2,600</td> <td>32,84</td> <td>4,006</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td>10,592</td> <td></td> <td>15,784</td> </tr> <tr> <td>0,009</td> <td>h</td> <td>CONCRETE PLUMP</td> <td>112,9</td> <td>1,016</td> <td>129,83</td> <td>1,168</td> </tr> <tr> <td>0,162</td> <td>h</td> <td>VIBRATOR GASOIL 30-50 mm</td> <td>1,42</td> <td>0,230</td> <td>1,652</td> <td>0,268</td> </tr> <tr> <td>10,82</td> <td>kg</td> <td>ELABORATED B 500 S</td> <td>0,9</td> <td>9,738</td> <td>1,035</td> <td>11,199</td> </tr> <tr> <td>0,13</td> <td>m3</td> <td>CONCRET 35n/mm2- soft-20.IIa</td> <td>78,08</td> <td>10,150</td> <td>89,79</td> <td>11,673</td> </tr> <tr> <td>0,1</td> <td>m3</td> <td>WATER</td> <td>1,89</td> <td>0,189</td> <td>2,173</td> <td>0,217</td> </tr> <tr> <td>1</td> <td>m2</td> <td>PREDALLEN</td> <td>24,5</td> <td>24,500</td> <td>28,25</td> <td>28,250</td> </tr> <tr> <td>1,05</td> <td>m2</td> <td>500T 15x30 d5-5</td> <td>1,25</td> <td>1,313</td> <td>1,437</td> <td>1,509</td> </tr> <tr> <td>0,5</td> <td>m</td> <td>STRAINING</td> <td>5,55</td> <td>2,775</td> <td>7,49</td> <td>3,745</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td>49,911</td> <td></td> <td>58,029</td> </tr> <tr> <td colspan="3"><b>TOTAL</b></td> <td colspan="2">60,503</td> <td colspan="2">73,813</td> </tr> <tr> <td colspan="3">TOTAL % SUPERIOR</td> <td colspan="2"></td> <td colspan="2">22,00</td> </tr> <tr> <td colspan="3">WORKERS % SUPERIOR</td> <td colspan="2"></td> <td colspan="2">49,019</td> </tr> <tr> <td colspan="3">MATERIAL % SUPERIOR</td> <td colspan="2"></td> <td colspan="2">16,264</td> </tr> <tr> <td colspan="3">TOTAL HOUR/M2</td> <td colspan="2">0,212</td> <td colspan="2"></td> </tr> </tbody> </table>	QNT	UT	DESCRIPTION	SPAIN		BELGIUM		€/UT	€	€/UT	€	0,09	h	CAT IV	22,91	2,062	32,84	2,956	0,09	h	CAT III	22,53	2,028	30,3	2,727	0,045	h	CAT II	21,9	0,986	28,49	1,282	0,122	h	MEESTERGAST	23,91	2,917	39,45	4,813	0,122	h	CAT IV STEEL	21,31	2,600	32,84	4,006					10,592		15,784	0,009	h	CONCRETE PLUMP	112,9	1,016	129,83	1,168	0,162	h	VIBRATOR GASOIL 30-50 mm	1,42	0,230	1,652	0,268	10,82	kg	ELABORATED B 500 S	0,9	9,738	1,035	11,199	0,13	m3	CONCRET 35n/mm2- soft-20.IIa	78,08	10,150	89,79	11,673	0,1	m3	WATER	1,89	0,189	2,173	0,217	1	m2	PREDALLEN	24,5	24,500	28,25	28,250	1,05	m2	500T 15x30 d5-5	1,25	1,313	1,437	1,509	0,5	m	STRAINING	5,55	2,775	7,49	3,745					49,911		58,029	<b>TOTAL</b>			60,503		73,813		TOTAL % SUPERIOR					22,00		WORKERS % SUPERIOR					49,019		MATERIAL % SUPERIOR					16,264		TOTAL HOUR/M2			0,212		
QNT	UT				DESCRIPTION	SPAIN		BELGIUM																																																																																																																																																																																																																																																																																																																					
		€/UT	€	€/UT		€																																																																																																																																																																																																																																																																																																																							
0,207	h	CAT IV	22,91	4,742	32,84	6,798																																																																																																																																																																																																																																																																																																																							
0,207	h	CAT III	22,53	4,664	30,3	6,272																																																																																																																																																																																																																																																																																																																							
0,104	h	CAT II	21,9	2,278	28,49	2,963																																																																																																																																																																																																																																																																																																																							
0,099	h	MEESTERGAST	23,91	2,367	39,45	3,906																																																																																																																																																																																																																																																																																																																							
0,099	h	CAT IV STEEL	21,31	2,110	32,84	3,251																																																																																																																																																																																																																																																																																																																							
				16,160		23,190																																																																																																																																																																																																																																																																																																																							
0,009	h	CONCRETE PLUMP	112,9	1,016	129,83	1,168																																																																																																																																																																																																																																																																																																																							
0,1	h	VIBRATOR GASOIL 30-50 mm	1,42	0,142	1,652	0,165																																																																																																																																																																																																																																																																																																																							
1,15	kg	B 500 S D6-25	0,61	0,702	0,701	0,806																																																																																																																																																																																																																																																																																																																							
5,4	kg	ELABORATED B 500 S	0,9	4,860	1,035	5,589																																																																																																																																																																																																																																																																																																																							
0,07	m3	CONCRET 35n/mm2- soft-20.IIa	78,08	5,466	89,79	6,285																																																																																																																																																																																																																																																																																																																							
1,465	m	beam h18	5,63	8,248	6,474	9,484																																																																																																																																																																																																																																																																																																																							
0,1	m3	WATER	1,89	0,189	2,173	0,217																																																																																																																																																																																																																																																																																																																							
7,1	U	VULSTENEN BETOM 70 59x22cm	0,79	5,609	0,908	6,447																																																																																																																																																																																																																																																																																																																							
1,05	m2	500T 15x30 d5-5	1,25	1,313	1,437	1,509																																																																																																																																																																																																																																																																																																																							
1,05	m2	FORMWORK BEAM	13,39	14,060	15,42	16,191																																																																																																																																																																																																																																																																																																																							
				41,603		47,862																																																																																																																																																																																																																																																																																																																							
<b>TOTAL</b>			57,764		71,052																																																																																																																																																																																																																																																																																																																								
TOTAL % SUPERIOR					23,01																																																																																																																																																																																																																																																																																																																								
WORKERS % SUPERIOR					43,496																																																																																																																																																																																																																																																																																																																								
MATERIAL % SUPERIOR					15,045																																																																																																																																																																																																																																																																																																																								
TOTAL HOUR/M2			0,306																																																																																																																																																																																																																																																																																																																										
QNT	UT	DESCRIPTION	SPAIN		BELGIUM																																																																																																																																																																																																																																																																																																																								
			€/UT	€	€/UT	€																																																																																																																																																																																																																																																																																																																							
0,09	h	CAT IV	22,91	2,062	32,84	2,956																																																																																																																																																																																																																																																																																																																							
0,09	h	CAT III	22,53	2,028	30,3	2,727																																																																																																																																																																																																																																																																																																																							
0,045	h	CAT II	21,9	0,986	28,49	1,282																																																																																																																																																																																																																																																																																																																							
0,122	h	MEESTERGAST	23,91	2,917	39,45	4,813																																																																																																																																																																																																																																																																																																																							
0,122	h	CAT IV STEEL	21,31	2,600	32,84	4,006																																																																																																																																																																																																																																																																																																																							
				10,592		15,784																																																																																																																																																																																																																																																																																																																							
0,009	h	CONCRETE PLUMP	112,9	1,016	129,83	1,168																																																																																																																																																																																																																																																																																																																							
0,162	h	VIBRATOR GASOIL 30-50 mm	1,42	0,230	1,652	0,268																																																																																																																																																																																																																																																																																																																							
10,82	kg	ELABORATED B 500 S	0,9	9,738	1,035	11,199																																																																																																																																																																																																																																																																																																																							
0,13	m3	CONCRET 35n/mm2- soft-20.IIa	78,08	10,150	89,79	11,673																																																																																																																																																																																																																																																																																																																							
0,1	m3	WATER	1,89	0,189	2,173	0,217																																																																																																																																																																																																																																																																																																																							
1	m2	PREDALLEN	24,5	24,500	28,25	28,250																																																																																																																																																																																																																																																																																																																							
1,05	m2	500T 15x30 d5-5	1,25	1,313	1,437	1,509																																																																																																																																																																																																																																																																																																																							
0,5	m	STRAINING	5,55	2,775	7,49	3,745																																																																																																																																																																																																																																																																																																																							
				49,911		58,029																																																																																																																																																																																																																																																																																																																							
<b>TOTAL</b>			60,503		73,813																																																																																																																																																																																																																																																																																																																								
TOTAL % SUPERIOR					22,00																																																																																																																																																																																																																																																																																																																								
WORKERS % SUPERIOR					49,019																																																																																																																																																																																																																																																																																																																								
MATERIAL % SUPERIOR					16,264																																																																																																																																																																																																																																																																																																																								
TOTAL HOUR/M2			0,212																																																																																																																																																																																																																																																																																																																										
PRICE STUDY	  	 																																																																																																																																																																																																																																																																																																																											
CONCLUSION	<p>THE "VUKSTENEN BETOM FLOOR" IS 23,01% MORE EXPENSIVE IN BELGIUM THAN IN SPAIN, BEING THE WORKERS PRICE 43,50% MORE EXPENSIVE AND THE MATERIAL PRICE 15,05%. THE TOTAL TIME FOR 1M2 IS 0,306 HOURS. IN CONCLUSION THIS FLOOR IS BETTER IN SPAIN BECAUSE IT NEEDS MORE TIME THAN THE PREDALLEN, AND THE % OF WORK HOUR IS CHEAPER IN SPAIN.</p>	<p>THE PREDALLEN FLOOR IS 22,00% MORE EXPENSIVE IN BELGIUM THAN IN SPAIN, BEING THE WORKERS PRICE 49,02% MORE EXPENSIVE AND THE MATERIAL PRICE 16,26%. THE TOTAL TIME FOR 1M2 IS 0,212 HOURS. THIS FLOOR IS BETTER IN BELGIUM BECAUSE IT NEEDS LESS TIME TO BUID 1M2, AND THE MEN HOURS/M2 FLOOR ARE MORE EXPENSIVE IN BELGIUM.</p>																																																																																																																																																																																																																																																																																																																											

**PART 6: SCHEDULING AND PRICING.**





**De Mouterij**  
**Jan de Nul NV**  
**Steven Schyvynck**  
as of 20/06/13 8:00

**Dates**

Start:	03/12/12 7:00	Finish:	23/04/13 10:16
Baseline Start:	NA	Baseline Finish:	NA
Actual Start:	NA	Actual Finish:	NA
Start Variance:	0 d	Finish Variance:	0 d

**Duration**

Scheduled:	94,41 d	Remaining:	94,41 d
Baseline:	0 d	Actual:	0 d
Variance:	94,41 d	Percent Complete:	0%

**Work**

Scheduled:	1.991,7 h	Remaining:	1.991,7 h
Baseline:	0 h	Actual:	0 h
Variance:	1.991,7 h	Percent Complete:	0%

**Costs**

Scheduled:	139.191,95 €	Remaining:	139.191,95 €
Baseline:	0,00 €	Actual:	0,00 €
Variance:	139.191,95 €		

**Task Status**

Tasks not yet started:	65
Tasks in progress:	0
Tasks completed:	0
<b>Total Tasks:</b>	<b>65</b>

**Resource Status**

Work Resources:	16
Overallocated Work Resources:	6
Material Resources:	3
<b>Total Resources:</b>	<b>25</b>



Base Calendar as of 20/06/13 17:01  
 De Mouterij  
 Steven Schyvynck

BASE CALENDAR: JAN DE NUL	
Day	Hours
Monday	7:00 - 11:30, 12:00 - 15:30
Tuesday	7:00 - 11:30, 12:00 - 15:30
Wednesday	7:00 - 11:30, 12:00 - 15:30
Thursday	7:00 - 11:30, 12:00 - 15:30
Friday	7:00 - 11:30, 12:00 - 15:30
Saturday	Nonworking
Sunday	Nonworking
Exceptions:	
Date	Hours
02/01/12 0:00	Nonworking
25/12/12 0:00	Nonworking
01/01/13 0:00	Nonworking
01/04/13 0:00 - 05/04/13 0:00	Nonworking
01/05/13 0:00	Nonworking
09/05/13 0:00 - 10/05/13 0:00	Nonworking
20/05/13 0:00	Nonworking
08/07/13 0:00 - 26/07/13 0:00	Nonworking
15/08/13 0:00	Nonworking
01/11/13 0:00	Nonworking
11/11/13 0:00	Nonworking
25/12/13 0:00	Nonworking

Resource Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13
Steve	18,75 h	40,33 h	11,25 h	9,3 h	1,27 h	15,05 h	24,68 h		11,75 h								
Cleaning and clearin	2,25 h																
Topography foundation	3 h																
Foundation demolition(lifts and stairs cases)	1 h																
Steel working for the tower crane	9,5 h	34,83 h															
Put the first part of the tower crane		0,5 h															
Formwork(walls+connection existing foundation)			11,25 h														
Concret workin until -0,28 m.				9,3 h													
Stremaform+steel link walls		2 h															
Formwork(zone columns)	3 h																
Mounting manholes		3 h															
Topography+Formwork perimetres					1 h												
Stell working floor (+conecction with walls and columns)					0,27 h	5,23 h											
Inside Formwork walls lift cases							10,5 h										
Prop up for the pedallen						9,82 h	14,18 h										
Concret working floor									11,75 h								
Paul	49,5 h	60,08 h	16,87 h	8,38 h	10,77 h	27,62 h	17,37 h		11,75 h								
Fenced and signaling	5 h																
Provisional houses	2,5 h																
Water, electricity and sanitar Phase2	3 h																
Take out the water of the foundation	11 h																
Cleaning foundations	14,5 h	19,75 h															
Steel working for the tower crane	9,5 h	34,83 h															
Put the first part of the tower crane		0,5 h															
Formwork(walls+connection existing foundation)			11,25 h														
Steel working conecction(existing foundation+walls)			5,62 h	8,38 h													
Removing formwork					10,5 h												
Plastic+Cleaning Concret	1 h																
Stremaform+steel link walls		2 h															
Formwork(zone columns)	3 h																
Mounting manholes		3 h															
Stell working floor (+conecction with walls and columns)					0,27 h	5,23 h											
Steel working lift cases						12,57 h	3,18 h										
Prop up for the pedallen						9,82 h	14,18 h										
Concret working floor									11,75 h								
Backhoe loader	6,75 h				2,93 h												
Cleaning and clearin	2,25 h																
Excavation(-3,00 m.Tower Crane)	3 h																
Excavation(-1,90 m.Lift Cases)	1,5 h																
Fill the spaces with sand (recycled from broken concrete).					2,93 h												
Jonh	39 h	19,75 h	11,25 h	13,3 h	2,1 h	15,05 h	24,68 h										
Fenced and signaling	5 h																
Provisional houses	2,5 h																
Water, electricity and sanitar Phase2	3 h																
Take out the water of the foundation	11 h																
Cleaning foundations	14,5 h	19,75 h															
Formwork(walls+connection existing foundation)			11,25 h														
Concret workin until -0,28 m.				9,3 h													
Formwork(zone columns)	3 h																
Fill the spaces with sand (recycled from broken concrete).					1,83 h												
Stell working floor (+conecction with walls and columns)					0,27 h	5,23 h											
Mounting tower crane				4 h													
Inside Formwork walls lift cases							10,5 h										
Prop up for the pedallen						9,82 h	14,18 h										
Marc	26,75 h	38,92 h	24 h	12,38 h	12,6 h	15,05 h	24,68 h										
Cleaning and clearin	2,25 h																
Water, electricity and sanitar Phase1	2 h																
Cleaning foundations	14,5 h	19,75 h															
Foundation demolition(lifts and stairs cases)	1 h																
Stremaform waterproof+steel link walls		2,5 h															
Concrete filling until -1'50 m		2,17 h	7,13 h														
Formwork(walls+connection existing foundation)			11,25 h														
Steel working conecction(existing foundation+walls)			5,62 h	8,38 h													
Removing formwork					10,5 h												



Resource Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13
Steel working floor Formwork(zone columns) Fill the spaces with sand (recycled from broken concrete). Stell working floor (+conecction with walls and columns) Mounting tower crane Inside Formwork walls lift cases Prop up for the pedallen	4 h 3 h	14,5 h				1,83 h 0,27 h	5,23 h										
Tony Cleaning and clearin Water, electricity and sanitar Phase1 Cleaning foundations Stremaform waterproof+steel link walls Concrete filling until -1'50 m Steel working conecction(existing foundation+walls) Steel working floor Steel working (connection columns with existing foundation) Consolidating ground Outside Formwork walls lift cases Prop up for the pedallen Formwork perimeter and holes	27,18 h 2,25 h 2 h 14,5 h	39,23 h 19,75 h 2,5 h 2,17 h	12,75 h 7,13 h 5,62 h	8,38 h	11,8 h	23,07 h	14,18 h		14 h								
Josh Steel working (connection columns with existing foundation) Waterproof Outside Formwork walls lift cases Prop up for the pedallen Formwork perimeter and holes	4,43 h 4,43 h	0,32 h 0,32 h			4 h	23,07 h	14,18 h		14 h								
Jan Steel working (connection columns with existing foundation) Waterproof Outside Formwork walls lift cases Mounting beams with the connectors of the column Mounting predallen	4,43 h 4,43 h	0,32 h 0,32 h			4 h	13,25 h		14,32 h	29,35 h								
Ronny Steel working (connection columns with existing foundation) Waterproof Outside Formwork walls lift cases Concret high strength and fast setting inside the column Mounting predallen	4,43 h 4,43 h	0,32 h 0,32 h			4 h	13,25 h	3,82 h	6 h	29,35 h								
Lee Site planning-Topography Plastic+Cleaning Concret Steel working for the tower crane Concrete working until - 0'16 m. Inside Formwork walls lift cases Mounting predallen Concret working floor	15,5 h 5 h 1 h 9,5 h	34,83 h 34,83 h				8,95 h	10,5 h	2,32 h	41,1 h								
Dave Excavation(-3,00 m.Tower Crane) Excavation(-1,90 m.Lift Cases) Concrete working until - 0'16 m. Concret high strength and fast setting inside the column Ventilation sistem Concret working floor	4,5 h 3 h 1,5 h					8,95 h	3,82 h	3,68 h	23,25 h								
Werner Concrete working until - 0'16 m. Mounting beams with the connectors of the column Ventilation sistem						8,95 h 8,95 h		12 h	11,5 h								
Tom Stragier Concrete working until - 0'16 m. Concret working cases stairs and lifts Steel working conecction						8,95 h 8,95 h	8 h		7,25 h								
Tom Daems Steel working lift cases Mounting Prefabricated columns(+prop up+formwork base)						12,57 h 12,57 h	13 h 3,18 h	2,18 h	7,25 h								

Resource Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvyneck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13
Steel working conection									7,25 h								
Michel						12,57 h	13 h	2,18 h	7,25 h								
Steel working lift cases						12,57 h	3,18 h										
Mounting Prefabricated columns(+prop up+formwork base)							9,82 h	2,18 h									
Steel working conection									7,25 h								
Bob						12,57 h	11,18 h		7,25 h								
Steel working lift cases						12,57 h	3,18 h										
Concret working cases stairs and lifts							8 h										
Steel working conection									7,25 h								
Tower crane																	
Vibrator needle 50 mm diam. gasoline		2,17 h	7,13 h			8,95 h	8 h		11,75 h								
Concrete filling until -1'50 m		2,17 h	7,13 h														
Concrete working until - 0'16 m.						8,95 h											
Concret working cases stairs and lifts							8 h										
Concret working floor									11,75 h								
Vibrator needle 30 mm diam.gasoline				9,3 h		8,95 h			11,75 h								
Concret workin until -0,28 m.				9,3 h													
Concrete working until - 0'16 m.						8,95 h											
Concret working floor									11,75 h								
Consolidation machine					11,8 h												
Consolidating ground					11,8 h												
Backhoe jackhammer	1 h																
Foundation demolition(lifts and stairs cases)	1 h																
Drain pump																	
Concrete (m3)		9,78	32,22	26,67		104	40,75		136								
Concrete filling until -1'50 m		9,78	32,22														
Concret workin until -0,28 m.				26,67													
Concrete working until - 0'16 m.						104											
Concret working cases stairs and lifts							40,75										
Concret working floor									136								
Steel (kg)	2.752,4	7.205,6	749,02	1.117,98	352,97	9.202,59	576,44		9.530								
Steel working for the tower crane	1.235,36	4.529,64															
Steel working conection(existing foundation+walls)			749,02	1.117,98													
Steel working floor	722,81	2.620,19															
Steel working (connection columns with existing foundation)	794,23	55,77															
Stell working floor (+conection with walls and columns)					352,97	6.927,03											
Steel working lift cases						2.275,56	576,44										
Steel working conection									9.530								
Formwork 2 sides (m2)	74		82			165	140		127								
Formwork(walls+connection existing foundation)			82														
Formwork(zone columns)	74																
Outside Formwork walls lift cases						165											
Inside Formwork walls lift cases							140										
Formwork perimeter and holes									127								
Total	202,23 h	236,27 h	83,25 h	61,05 h	65,27 h	236,8 h	191,1 h	42,68 h	238,55 h								

	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13	Total
<b>Steve</b>						132,38 h
Cleaning and clearin						2,25 h
Topography foundation						3 h
Foundation demolition(lifts and stairs cases)						1 h
Steel working for the tower crane						44,33 h
Put the first part of the tower crane						0,5 h
Formwork(walls+connection existing foundation)						11,25 h
Concret workin until -0,28 m.						9,3 h
Stremaform+steel link walls						2 h
Formwork(zone columns)						3 h
Mounting manholes						3 h
Topography+Formwork perimetres						1 h
Stell working floor (+conecction with walls and columns)						5,5 h
Inside Formwork walls lift cases						10,5 h
Prop up for the pedallen						24 h
Concret working floor						11,75 h
<b>Paul</b>						202,33 h
Fenced and signaling						5 h
Provisional houses						2,5 h
Water, electricity and sanitar Phase2						3 h
Take out the water of the foundation						11 h
Cleaning foundations						34,25 h
Steel working for the tower crane						44,33 h
Put the first part of the tower crane						0,5 h
Formwork(walls+connection existing foundation)						11,25 h
Steel working conecction(existing foundation+walls)						14 h
Removing formwork						10,5 h
Plastic+Cleaning Concret						1 h
Stremaform+steel link walls						2 h
Formwork(zone columns)						3 h
Mounting manholes						3 h
Stell working floor (+conecction with walls and columns)						5,5 h
Steel working lift cases						15,75 h
Prop up for the pedallen						24 h
Concret working floor						11,75 h
<b>Backhoe loader</b>						9,68 h
Cleaning and clearin						2,25 h
Excavation(-3,00 m.Tower Crane)						3 h
Excavation(-1,90 m.Lift Cases)						1,5 h
Fill the spaces with sand (recycled from broken concrete).						2,93 h
<b>Jonh</b>						125,13 h
Fenced and signaling						5 h
Provisional houses						2,5 h
Water, electricity and sanitar Phase2						3 h
Take out the water of the foundation						11 h
Cleaning foundations						34,25 h
Formwork(walls+connection existing foundation)						11,25 h
Concret workin until -0,28 m.						9,3 h
Formwork(zone columns)						3 h
Fill the spaces with sand (recycled from broken concrete).						1,83 h
Stell working floor (+conecction with walls and columns)						5,5 h
Mounting tower crane						4 h
Inside Formwork walls lift cases						10,5 h
Prop up for the pedallen						24 h
<b>Marc</b>						154,38 h
Cleaning and clearin						2,25 h
Water, electricity and sanitar Phase1						2 h
Cleaning foundations						34,25 h
Foundation demolition(lifts and stairs cases)						1 h
Stremaform waterproof+steel link walls						2,5 h
Concrete filling until -1'50 m						9,3 h
Formwork(walls+connection existing foundation)						11,25 h
Steel working conecction(existing foundation+walls)						14 h
Removing formwork						10,5 h




	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13	Total
Steel working floor						18,5 h
Formwork(zone columns)						3 h
Fill the spaces with sand (recycled from broken concrete).						1,83 h
Stell working floor (+conecction with walls and columns)						5,5 h
Mounting tower crane						4 h
Inside Formwork walls lift cases						10,5 h
Prop up for the pedallen						24 h
<b>Tony</b>						150,6 h
Cleaning and clearin						2,25 h
Water, electricity and sanitar Phase1						2 h
Cleaning foundations						34,25 h
Stremaform waterproof+steel link walls						2,5 h
Concrete filling until -1'50 m						9,3 h
Steel working conecction(existing foundation+walls)						14 h
Steel working floor						18,5 h
Steel working (connection columns with existing foundation)						4,75 h
Consolidating ground						11,8 h
Outside Formwork walls lift cases						13,25 h
Prop up for the pedallen						24 h
Formwork perimeter and holes						14 h
<b>Josh</b>						60 h
Steel working (connection columns with existing foundation)						4,75 h
Waterproof						4 h
Outside Formwork walls lift cases						13,25 h
Prop up for the pedallen						24 h
Formwork perimeter and holes						14 h
<b>Jan</b>						65,67 h
Steel working (connection columns with existing foundation)						4,75 h
Waterproof						4 h
Outside Formwork walls lift cases						13,25 h
Mounting beams with the connectors of the column						12 h
Mounting predallen						31,67 h
<b>Ronny</b>						61,17 h
Steel working (connection columns with existing foundation)						4,75 h
Waterproof						4 h
Outside Formwork walls lift cases						13,25 h
Concret high strength and fast setting inside the column						7,5 h
Mounting predallen						31,67 h
<b>Lee</b>						113,2 h
Site planning-Topography						5 h
Plastic+Cleaning Concret						1 h
Steel working for the tower crane						44,33 h
Concrete working until - 0'16 m.						8,95 h
Inside Formwork walls lift cases						10,5 h
Mounting predallen						31,67 h
Concret working floor						11,75 h
<b>Dave</b>						44,2 h
Excavation(-3,00 m.Tower Crane)						3 h
Excavation(-1,90 m.Lift Cases)						1,5 h
Concrete working until - 0'16 m.						8,95 h
Concret high strength and fast setting inside the column						7,5 h
Ventilation sistem						11,5 h
Concret working floor						11,75 h
<b>Werner</b>						32,45 h
Concrete working until - 0'16 m.						8,95 h
Mounting beams with the connectors of the column						12 h
Ventilation sistem						11,5 h
<b>Tom Stragier</b>						24,2 h
Concrete working until - 0'16 m.						8,95 h
Concret working cases stairs and lifts						8 h
Steel working conecction						7,25 h
<b>Tom Daems</b>						35 h
Steel working lift cases						15,75 h
Mounting Prefabricated columns(+prop up+formwork base)						12 h

	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13	Total
Steel working conection						7,25 h
Michel						35 h
Steel working lift cases						15,75 h
Mounting Prefabricated columns(+prop up+formwork base)						12 h
Steel working conection						7,25 h
Bob						31 h
Steel working lift cases						15,75 h
Concret working cases stairs and lifts						8 h
Steel working conection						7,25 h
Tower crane						
Vibrator needle 50 mm diam. gasoline						38 h
Concrete filling until -1'50 m						9,3 h
Concrete working until - 0'16 m.						8,95 h
Concret working cases stairs and lifts						8 h
Concret working floor						11,75 h
Vibrator needle 30 mm diam.gasoline						30 h
Concret workin until -0,28 m.						9,3 h
Concrete working until - 0'16 m.						8,95 h
Concret working floor						11,75 h
Consolidation machine						11,8 h
Consolidating ground						11,8 h
Backhoe jackhammer						1 h
Foundation demolition(lifts and stairs cases)						1 h
Drain pump						
Concrete (m3)						
Concrete filling until -1'50 m						
Concret workin until -0,28 m.						
Concrete working until - 0'16 m.						
Concret working cases stairs and lifts						
Concret working floor						
Steel (kg)						
Steel working for the tower crane						
Steel working conection(existing foundation+walls)						
Steel working floor						
Steel working (connection columns with existing foundation)						
Stell working floor (+conection with walls and columns)						
Steel working lift cases						
Steel working conection						
Formwork 2 sides (m2)						
Formwork(walls+connection existing foundation)						
Formwork(zone columns)						
Outside Formwork walls lift cases						
Inside Formwork walls lift cases						
Formwork perimeter and holes						
Total						1.357,2 h






# De Mouterij











Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	1
Start												
Fenced and signaling	10 h											
Paul	5 h											
Jonh	5 h											
Cleaning and clearin	9 h											
Steve	2,25 h											
Backhoe loader	2,25 h											
Marc	2,25 h											
Tony	2,25 h											
Site planning-Topography	5 h											
Lee	5 h											
Provisional houses	5 h											
Paul	2,5 h											
Jonh	2,5 h											
Water, electricity and sanitar Phase1	4 h											
Marc	2 h											
Tony	2 h											
Water, electricity and sanitar Phase2	6 h											
Paul	3 h											
Jonh	3 h											
Take out the water of the foundation	22 h											
Paul	11 h											
Jonh	11 h											
Topography foundation	3 h											
Steve	3 h											
Cleaning foundations	58 h	79 h										
Paul	14,5 h	19,75 h										
Jonh	14,5 h	19,75 h										
Marc	14,5 h	19,75 h										
Tony	14,5 h	19,75 h										
Foundation demolition(lifts and stairs cases)	3 h											
Steve	1 h											
Marc	1 h											
Backhoe jackhammer	1 h											
Excavation(-3,00 m.Tower Crane)	6 h											
Backhoe loader	3 h											
Dave	3 h											
Excavation(-1,90 m.Lift Cases)	3 h											
Backhoe loader	1,5 h											
Dave	1,5 h											
Plastic+Cleaning Concret	1 h											

Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	1
Lee	1 h											
Steel working for the tower crane	28,5 h	104,5 h										
Steve	9,5 h	34,83 h										
Paul	9,5 h	34,83 h										
Lee	9,5 h	34,83 h										
Steel (kg)	1.235,36	4.529,64										
Put the first part of the tower crane		1 h										
Steve		0,5 h										
Paul		0,5 h										
Stremaform waterproof+steel link walls		5 h										
Marc		2,5 h										
Tony		2,5 h										
Concrete filling until -1'50 m		6,5 h	21,4 h									
Marc		2,17 h	7,13 h									
Tony		2,17 h	7,13 h									
Vibrator needle 50 mm diam. gasoline		2,17 h	7,13 h									
Concrete (m3)		9,78	32,22									
Formwork(walls+connection existing foundation)			45 h									
Steve			11,25 h									
Paul			11,25 h									
Jonh			11,25 h									
Marc			11,25 h									
Formwork 2 sides (m2)			82									
Steel working conecction(existing foundation+walls)			16,85 h	25,15 h								
Paul			5,62 h	8,38 h								
Marc			5,62 h	8,38 h								
Tony			5,62 h	8,38 h								
Steel (kg)			749,02	1.117,98								
Concret workin until -0,28 m.				27,9 h								
Steve				9,3 h								
Jonh				9,3 h								
Vibrator needle 30 mm diam.gasoline				9,3 h								
Concrete (m3)				26,67								
Removing formwork					21 h							
Paul					10,5 h							
Marc					10,5 h							
Plastic+Cleaning Concret	1 h											
Paul	1 h											
Steel working floor	8 h	29 h										
Marc	4 h	14,5 h										
Tony	4 h	14,5 h										



Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	1
Steel (kg)	722,81	2.620,19										
Stremaform+steel link walls		4 h										
Steve		2 h										
Paul		2 h										
Formwork(zone columns)	12 h											
Steve	3 h											
Paul	3 h											
Jonh	3 h											
Marc	3 h											
Formwork 2 sides (m2)	74											
Steel working (connection columns with existing foundation)	17,75 h	1,25 h										
Tony	4,43 h	0,32 h										
Josh	4,43 h	0,32 h										
Jan	4,43 h	0,32 h										
Ronny	4,43 h	0,32 h										
Steel (kg)	794,23	55,77										
Mounting manholes		6 h										
Steve		3 h										
Paul		3 h										
Fill the spaces with sand (recycled from broken concrete).					6,6 h							
Backhoe loader					2,93 h							
Jonh					1,83 h							
Marc					1,83 h							
Consolidating ground					23,6 h							
Tony					11,8 h							
Consolidation machine					11,8 h							
Topography+Formwork perimetres					1 h							
Steve					1 h							
Waterproof					12 h							
Josh					4 h							
Jan					4 h							
Ronny					4 h							
Stell working floor (+conecction with walls and columns)					1,07 h	20,93 h						
Steve					0,27 h	5,23 h						
Paul					0,27 h	5,23 h						
Jonh					0,27 h	5,23 h						
Marc					0,27 h	5,23 h						
Steel (kg)					352,97	6.927,03						
Concrete working until - 0'16 m.						53,7 h						
Lee						8,95 h						
Dave						8,95 h						

Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	1
Werner						8,95 h						
Tom Stragier						8,95 h						
Vibrator needle 50 mm diam. gasoline						8,95 h						
Vibrator needle 30 mm diam.gasoline						8,95 h						
Concrete (m3)						104						
Mounting tower crane				8 h								
Jonh				4 h								
Marc				4 h								
Outside Formwork walls lift cases						53 h						
Tony						13,25 h						
Josh						13,25 h						
Jan						13,25 h						
Ronny						13,25 h						
Formwork 2 sides (m2)						165						
Steel working lift cases						50,27 h	12,73 h					
Paul						12,57 h	3,18 h					
Tom Daems						12,57 h	3,18 h					
Michel						12,57 h	3,18 h					
Bob						12,57 h	3,18 h					
Steel (kg)						2.275,56	576,44					
Inside Formwork walls lift cases							42 h					
Steve							10,5 h					
Jonh							10,5 h					
Marc							10,5 h					
Lee							10,5 h					
Formwork 2 sides (m2)							140					
Concret working cases stairs and lifts							24 h					
Tom Stragier							8 h					
Bob							8 h					
Vibrator needle 50 mm diam. gasoline							8 h					
Concrete (m3)							40,75					
Mounting Prefabricated columns(+prop up+formwork base)							19,63 h	4,37 h				
Tom Daems							9,82 h	2,18 h				
Michel							9,82 h	2,18 h				
Concret high strength and fast setting inside the column							7,63 h	7,37 h				
Ronny							3,82 h	3,68 h				
Dave							3,82 h	3,68 h				
Mounting beams with the connectors of the column								24 h				
Jan								12 h				
Werner								12 h				
Prop up for the pedallen						58,9 h	85,1 h					

Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	1
Steve						9,82 h	14,18 h					
Paul						9,82 h	14,18 h					
Jonh						9,82 h	14,18 h					
Marc						9,82 h	14,18 h					
Tony						9,82 h	14,18 h					
Josh						9,82 h	14,18 h					
Mounting predallen								6,95 h	88,05 h			
Jan								2,32 h	29,35 h			
Ronny								2,32 h	29,35 h			
Lee								2,32 h	29,35 h			
Ventilation sistem									23 h			
Dave									11,5 h			
Werner									11,5 h			
Steel working conecction									29 h			
Tom Stragier									7,25 h			
Tom Daems									7,25 h			
Michel									7,25 h			
Bob									7,25 h			
Steel (kg)									9.530			
Formwork perimeter and holes									28 h			
Tony									14 h			
Josh									14 h			
Formwork 2 sides (m2)									127			
Concret working floor									70,5 h			
Steve									11,75 h			
Paul									11,75 h			
Lee									11,75 h			
Dave									11,75 h			
Vibrator needle 50 mm diam. gasoline									11,75 h			
Vibrator needle 30 mm diam.gasoline									11,75 h			
Concrete (m3)									136			
Remove the prop of columns and pedallen.												
Outside of formwork walls FLOOR 1						53 h						
Steel working walls											63 h	
Inside of formwork walls											42 h	
Concret working walls											24 h	
Mounting Prefabricated columns(+prop up+formwork base)									2,2 h	21,8 h		
Concret high strength and fast setting inside the column										15 h		
Mounting beams with the connectors of the column										24 h		
Prop up for the pedallen											144 h	
Mounting predallen												



Task Usage as of 20/06/13 17:04  
 De Mousterij  
 Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13	28/01/13	04/02/13	11/02/13	1
Ventilation system												
Steel working conecction												
Formwork perimeter and holes												
Concret working floor												
Remove the prop of columns and pedallen.												
Take out the tower crane												
END												
Total	202,25 h	236,25 h	83,25 h	61,05 h	65,27 h	289,8 h	191,1 h	42,68 h	240,75 h	60,8 h	273 h	

Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13
Start											
Fenced and signaling Paul Jonh											
Cleaning and clearin Steve Backhoe loader Marc Tony											
Site planning-Topography Lee											
Provisional houses Paul Jonh											
Water, electricity and sanitar Phase1 Marc Tony											
Water, electricity and sanitar Phase2 Paul Jonh											
Take out the water of the foundation Paul Jonh											
Topography foundation Steve											
Cleaning foundations Paul Jonh Marc Tony											
Foundation demolition(lifts and stairs cases) Steve Marc Backhoe jackhammer											
Excavation(-3,00 m.Tower Crane) Backhoe loader Dave											
Excavation(-1,90 m.Lift Cases) Backhoe loader Dave											
Plastic+Cleaning Concret											

Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13
Lee											
Steel working for the tower crane Steve Paul Lee Steel (kg)											
Put the first part of the tower crane Steve Paul											
Stremaform waterproof+steel link walls Marc Tony											
Concrete filling until -1'50 m Marc Tony Vibrator needle 50 mm diam. gasoline Concrete (m3)											
Formwork(walls+connection existing foundation) Steve Paul Jonh Marc Formwork 2 sides (m2)											
Steel working coneccion(existing foundation+walls) Paul Marc Tony Steel (kg)											
Concret workin until -0,28 m. Steve Jonh Vibrator needle 30 mm diam.gasoline Concrete (m3)											
Removing formwork Paul Marc											
Plastic+Cleaning Concret Paul											
Steel working floor Marc Tony											



Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13
Steel (kg)											
Stremaform+steel link walls Steve Paul											
Formwork(zone columns) Steve Paul Jonh Marc Formwork 2 sides (m2)											
Steel working (connection columns with existing foundation) Tony Josh Jan Ronny Steel (kg)											
Mounting manholes Steve Paul											
Fill the spaces with sand (recycled from broken concrete). Backhoe loader Jonh Marc											
Consolidating ground Tony Consolidation machine											
Topography+Formwork perimetres Steve											
Waterproof Josh Jan Ronny											
Stell working floor (+conecction with walls and columns) Steve Paul Jonh Marc Steel (kg)											
Concrete working until - 0'16 m. Lee Dave											

Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13
Werner Tom Stragier Vibrator needle 50 mm diam. gasoline Vibrator needle 30 mm diam.gasoline Concrete (m3)											
Mounting tower crane Jonh Marc											
Outside Formwork walls lift cases Tony Josh Jan Ronny Formwork 2 sides (m2)											
Steel working lift cases Paul Tom Daems Michel Bob Steel (kg)											
Inside Formwork walls lift cases Steve Jonh Marc Lee Formwork 2 sides (m2)											
Concret working cases stairs and lifts Tom Stragier Bob Vibrator needle 50 mm diam. gasoline Concrete (m3)											
Mounting Prefabricated columns(+prop up+formwork base) Tom Daems Michel											
Concret high strength and fast setting inside the column Ronny Dave											
Mounting beams with the connectors of the column Jan Werner											
Prop up for the pedallen											

Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13
Steve Paul Jonh Marc Tony Josh											
Mounting predallen Jan Ronny Lee											
Ventilation sistem Dave Werner											
Steel working conecction Tom Stragier Tom Daems Michel Bob Steel (kg)											
Formwork perimeter and holes Tony Josh Formwork 2 sides (m2)											
Concret working floor Steve Paul Lee Dave Vibrator needle 50 mm diam. gasoline Vibrator needle 30 mm diam.gasoline Concrete (m3)											
Remove the prop of columns and pedallen.											
Outside of formwork walls FLOOR 1											
Steel working walls											
Inside of formwork walls											
Concret working walls											
Mounting Prefabricated columns(+prop up+formwork base)											
Concret high strength and fast setting inside the column											
Mounting beams with the connectors of the column											
Prop up for the pedallen											
Mounting predallen			95 h								



Task Usage as of 20/06/13 17:04  
 De Mousterij  
 Steven Schyvynck

	18/02/13	25/02/13	04/03/13	11/03/13	18/03/13	25/03/13	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13
Ventilation system		23 h									
Steel working conecction		29 h									
Formwork perimeter and holes		28 h									
Concret working floor		37,4 h	33,1 h								
Remove the prop of columns and pedallen.											
Take out the tower crane											
END											
Total		212,4 h	33,1 h								

	<b>Total</b>
Start	
Fenced and signaling	10 h
Paul	5 h
Jonh	5 h
Cleaning and clearin	9 h
Steve	2,25 h
Backhoe loader	2,25 h
Marc	2,25 h
Tony	2,25 h
Site planning-Topography	5 h
Lee	5 h
Provisional houses	5 h
Paul	2,5 h
Jonh	2,5 h
Water, electricity and sanitar Phase1	4 h
Marc	2 h
Tony	2 h
Water, electricity and sanitar Phase2	6 h
Paul	3 h
Jonh	3 h
Take out the water of the foundation	22 h
Paul	11 h
Jonh	11 h
Topography foundation	3 h
Steve	3 h
Cleaning foundations	137 h
Paul	34,25 h
Jonh	34,25 h
Marc	34,25 h
Tony	34,25 h
Foundation demolition(lifts and stairs cases)	3 h
Steve	1 h
Marc	1 h
Backhoe jackhammer	1 h
Excavation(-3,00 m.Tower Crane)	6 h
Backhoe loader	3 h
Dave	3 h
Excavation(-1,90 m.Lift Cases)	3 h
Backhoe loader	1,5 h
Dave	1,5 h
Plastic+Cleaning Concret	1 h

	<b>Total</b>
Lee	1 h
Steel working for the tower crane	133 h
Steve	44,33 h
Paul	44,33 h
Lee	44,33 h
Steel (kg)	5.765
Put the first part of the tower crane	1 h
Steve	0,5 h
Paul	0,5 h
Stremaform waterproof+steel link walls	5 h
Marc	2,5 h
Tony	2,5 h
Concrete filling until -1'50 m	27,9 h
Marc	9,3 h
Tony	9,3 h
Vibrator needle 50 mm diam. gasoline	9,3 h
Concrete (m3)	42
Formwork(walls+connection existing foundation)	45 h
Steve	11,25 h
Paul	11,25 h
Jonh	11,25 h
Marc	11,25 h
Formwork 2 sides (m2)	82
Steel working conecction(existing foundation+walls)	42 h
Paul	14 h
Marc	14 h
Tony	14 h
Steel (kg)	1.867
Concret workin until -0,28 m.	27,9 h
Steve	9,3 h
Jonh	9,3 h
Vibrator needle 30 mm diam.gasoline	9,3 h
Concrete (m3)	26,67
Removing formwork	21 h
Paul	10,5 h
Marc	10,5 h
Plastic+Cleaning Concret	1 h
Paul	1 h
Steel working floor	37 h
Marc	18,5 h
Tony	18,5 h



	<b>Total</b>
Steel (kg)	3.343
Stremaform+steel link walls	4 h
Steve	2 h
Paul	2 h
Formwork(zone columns)	12 h
Steve	3 h
Paul	3 h
Jonh	3 h
Marc	3 h
Formwork 2 sides (m2)	74
Steel working (connection columns with existing foundation)	19 h
Tony	4,75 h
Josh	4,75 h
Jan	4,75 h
Ronny	4,75 h
Steel (kg)	850
Mounting manholes	6 h
Steve	3 h
Paul	3 h
Fill the spaces with sand (recycled from broken concrete).	6,6 h
Backhoe loader	2,93 h
Jonh	1,83 h
Marc	1,83 h
Consolidating ground	23,6 h
Tony	11,8 h
Consolidation machine	11,8 h
Topography+Formwork perimetres	1 h
Steve	1 h
Waterproof	12 h
Josh	4 h
Jan	4 h
Ronny	4 h
Stell working floor (+conecction with walls and columns)	22 h
Steve	5,5 h
Paul	5,5 h
Jonh	5,5 h
Marc	5,5 h
Steel (kg)	7.280
Concrete working until - 0'16 m.	53,7 h
Lee	8,95 h
Dave	8,95 h

	<b>Total</b>
Werner	8,95 h
Tom Stragier	8,95 h
Vibrator needle 50 mm diam. gasoline	8,95 h
Vibrator needle 30 mm diam.gasoline	8,95 h
Concrete (m3)	104
Mounting tower crane	8 h
Jonh	4 h
Marc	4 h
Outside Formwork walls lift cases	53 h
Tony	13,25 h
Josh	13,25 h
Jan	13,25 h
Ronny	13,25 h
Formwork 2 sides (m2)	165
Steel working lift cases	63 h
Paul	15,75 h
Tom Daems	15,75 h
Michel	15,75 h
Bob	15,75 h
Steel (kg)	2.852
Inside Formwork walls lift cases	42 h
Steve	10,5 h
Jonh	10,5 h
Marc	10,5 h
Lee	10,5 h
Formwork 2 sides (m2)	140
Concret working cases stairs and lifts	24 h
Tom Stragier	8 h
Bob	8 h
Vibrator needle 50 mm diam. gasoline	8 h
Concrete (m3)	40,75
Mounting Prefabricated columns(+prop up+formwork base)	24 h
Tom Daems	12 h
Michel	12 h
Concret high strength and fast setting inside the column	15 h
Ronny	7,5 h
Dave	7,5 h
Mounting beams with the connectors of the column	24 h
Jan	12 h
Werner	12 h
Prop up for the pedallen	144 h

	<b>Total</b>
Steve	24 h
Paul	24 h
Jonh	24 h
Marc	24 h
Tony	24 h
Josh	24 h
Mounting predallen	95 h
Jan	31,67 h
Ronny	31,67 h
Lee	31,67 h
Ventilation sistem	23 h
Dave	11,5 h
Werner	11,5 h
Steel working conecction	29 h
Tom Stragier	7,25 h
Tom Daems	7,25 h
Michel	7,25 h
Bob	7,25 h
Steel (kg)	9.530
Formwork perimeter and holes	28 h
Tony	14 h
Josh	14 h
Formwork 2 sides (m2)	127
Concret working floor	70,5 h
Steve	11,75 h
Paul	11,75 h
Lee	11,75 h
Dave	11,75 h
Vibrator needle 50 mm diam. gasoline	11,75 h
Vibrator needle 30 mm diam.gasoline	11,75 h
Concrete (m3)	136
Remove the prop of columns and pedallen.	
Outside of formwork walls FLOOR 1	53 h
Steel working walls	63 h
Inside of formwork walls	42 h
Concret working walls	24 h
Mounting Prefabricated columns(+prop up+formwork base)	24 h
Concret high strength and fast setting inside the column	15 h
Mounting beams with the connectors of the column	24 h
Prop up for the pedallen	144 h
Mounting predallen	95 h

Task Usage as of 20/06/13 17:04  
De Mouterij  
Steven Schyvynck

	<b>Total</b>
Ventilation system	23 h
Steel working conecction	29 h
Formwork perimeter and holes	28 h
Concret working floor	70,5 h
Remove the prop of columns and pedallen.	
Take out the tower crane	
END	
<b>Total</b>	<b>1.991,7 h</b>



ID



Resource Name

Work

ID	Task Name	Units	Work	Delay	Start	Finish
1	Steve		132,38 h			
16	Put the first part of the tower crane	1	0,5 h	0 d	14/12/12 9:50	14/12/12 10:20
9	Topography foundation	1	3 h	0 d	05/12/12 14:00	06/12/12 8:30
11	Foundation demolition(lifts and stairs cases)	1	1 h	0 d	06/12/12 8:30	06/12/12 9:30
3	Cleaning and clearin	1	2,25 h	0 d	03/12/12 7:00	03/12/12 9:15
15	Steel working for the tower crane	1	44,33 h	0 d	06/12/12 14:00	14/12/12 9:50
19	Formwork(walls+connection existing foundation)	1	11,25 h	0 d	19/12/12 14:38	21/12/12 9:23
21	Concret workin until -0,28 m.	1	9,3 h	0 d	26/12/12 7:23	27/12/12 8:41
25	Stremaform+steel link walls	1	2 h	0 d	14/12/12 10:24	14/12/12 12:54
26	Formwork(zone columns)	1	3 h	0 d	07/12/12 9:04	07/12/12 12:34
28	Mounting manholes	1	3 h	0 d	10/12/12 9:38	10/12/12 13:08
31	Topography+Formwork perimetres	1	1 h	0 d	04/01/13 9:44	04/01/13 10:44
33	Stell working floor (+conecction with walls and columns)	1	5,5 h	0 d	04/01/13 15:14	07/01/13 12:44
38	Inside Formwork walls lift cases	1	10,5 h	0 d	14/01/13 10:11	15/01/13 13:11
43	Prop up for the pedallen	1	24 h	0 d	10/01/13 13:41	15/01/13 13:41
48	Concret working floor	1	11,75 h	0 d	31/01/13 10:31	01/02/13 14:46
2	Paul		202,33 h			
8	Take out the water of the foundation	1	11 h	0 d	05/12/12 8:00	06/12/12 11:00
16	Put the first part of the tower crane	1	0,5 h	0 d	14/12/12 9:50	14/12/12 10:20
10	Cleaning foundations	1	34,25 h	0 d	06/12/12 8:30	12/12/12 10:45
2	Fenced and signaling	1	5 h	0 d	03/12/12 7:00	03/12/12 12:30
5	Provisional houses	1	2,5 h	0 d	04/12/12 14:30	05/12/12 8:30
7	Water, electricity and sanitar Phase2	1	3 h	0 d	05/12/12 8:30	05/12/12 11:30
15	Steel working for the tower crane	1	44,33 h	0 d	06/12/12 14:00	14/12/12 9:50
19	Formwork(walls+connection existing foundation)	1	11,25 h	0 d	19/12/12 14:38	21/12/12 9:23
20	Steel working conecction(existing foundation+walls)	1	14 h	0 d	21/12/12 9:23	26/12/12 7:23
22	Removing formwork	1	10,5 h	0 d	31/12/12 8:41	02/01/13 11:11
23	Plastic+Cleaning Concret	1	1 h	0 d	07/12/12 10:00	07/12/12 11:00
25	Stremaform+steel link walls	1	2 h	0 d	14/12/12 10:24	14/12/12 12:54
26	Formwork(zone columns)	1	3 h	0 d	07/12/12 9:04	07/12/12 12:34
28	Mounting manholes	1	3 h	0 d	10/12/12 9:38	10/12/12 13:08
33	Stell working floor (+conecction with walls and columns)	1	5,5 h	0 d	04/01/13 15:14	07/01/13 12:44
37	Steel working lift cases	1	15,75 h	0 d	10/01/13 10:26	14/01/13 10:11
43	Prop up for the pedallen	1	24 h	0 d	10/01/13 13:41	15/01/13 13:41
48	Concret working floor	1	11,75 h	0 d	31/01/13 10:31	01/02/13 14:46
3	Backhoe loader		9,68 h			
12	Excavation(-3,00 m.Tower Crane)	1	3 h	0 d	06/12/12 9:30	06/12/12 13:00
13	Excavation(-1,90 m.Lift Cases)	1	1,5 h	0 d	07/12/12 8:30	07/12/12 10:00
3	Cleaning and clearin	1	2,25 h	0 d	03/12/12 7:00	03/12/12 9:15
29	Fill the spaces with sand (recycled from broken concrete).	1	2,93 h	0 d	31/12/12 14:26	02/01/13 8:52
4	Jonh		125,13 h			
8	Take out the water of the foundation	1	11 h	0 d	05/12/12 8:00	06/12/12 11:00
10	Cleaning foundations	1	34,25 h	0 d	06/12/12 8:30	12/12/12 10:45
2	Fenced and signaling	1	5 h	0 d	03/12/12 7:00	03/12/12 12:30
5	Provisional houses	1	2,5 h	0 d	04/12/12 14:30	05/12/12 8:30
7	Water, electricity and sanitar Phase2	1	3 h	0 d	05/12/12 8:30	05/12/12 11:30

ID



Resource Name

Work

"Jonh" continued

ID	Task Name	Units	Work	Delay	Start	Finish
19	Formwork(walls+connection existing foundation)	1	11,25 h	0 d	19/12/12 14:38	21/12/12 9:23
21	Concret workin until -0,28 m.	1	9,3 h	0 d	26/12/12 7:23	27/12/12 8:41
26	Formwork(zone columns)	1	3 h	0 d	07/12/12 9:04	07/12/12 12:34
29	Fill the spaces with sand (recycled from broken concrete).	1	1,83 h	0 d	31/12/12 14:26	02/01/13 7:46
33	Stell working floor (+conecction with walls and columns)	1	5,5 h	0 d	04/01/13 15:14	07/01/13 12:44
35	Mounting tower crane	1	4 h	0 d	27/12/12 14:38	28/12/12 10:08
38	Inside Formwork walls lift cases	1	10,5 h	0 d	14/01/13 10:11	15/01/13 13:11
43	Prop up for the pedallen	1	24 h	0 d	10/01/13 13:41	15/01/13 13:41

5



Marc

154,38 h

ID	Task Name	Units	Work	Delay	Start	Finish
10	Cleaning foundations	1	34,25 h	0 d	06/12/12 8:30	12/12/12 10:45
11	Foundation demolition(lifts and stairs cases)	1	1 h	0 d	06/12/12 8:30	06/12/12 9:30
3	Cleaning and clearin	1	2,25 h	0 d	03/12/12 7:00	03/12/12 9:15
6	Water, electricity and sanitar Phase1	1	2 h	0 d	04/12/12 12:30	04/12/12 14:30
17	Stremaform waterproof+steel link walls	1	2,5 h	0 d	14/12/12 10:20	14/12/12 13:20
18	Concrete filling until -1 50 m	1	9,3 h	0 d	14/12/12 13:20	17/12/12 14:38
19	Formwork(walls+connection existing foundation)	1	11,25 h	0 d	19/12/12 14:38	21/12/12 9:23
20	Steel working conecction(existing foundation+walls)	1	14 h	0 d	21/12/12 9:23	26/12/12 7:23
22	Removing formwork	1	10,5 h	0 d	31/12/12 8:41	02/01/13 11:11
24	Steel working floor	1	18,5 h	0 d	07/12/12 11:00	11/12/12 14:00
26	Formwork(zone columns)	1	3 h	0 d	07/12/12 9:04	07/12/12 12:34
29	Fill the spaces with sand (recycled from broken concrete).	1	1,83 h	0 d	31/12/12 14:26	02/01/13 7:46
33	Stell working floor (+conecction with walls and columns)	1	5,5 h	0 d	04/01/13 15:14	07/01/13 12:44
35	Mounting tower crane	1	4 h	0 d	27/12/12 14:38	28/12/12 10:08
38	Inside Formwork walls lift cases	1	10,5 h	0 d	14/01/13 10:11	15/01/13 13:11
43	Prop up for the pedallen	1	24 h	0 d	10/01/13 13:41	15/01/13 13:41

6



Tony

150,6 h

ID	Task Name	Units	Work	Delay	Start	Finish
3	Cleaning and clearin	1	2,25 h	0 d	03/12/12 7:00	03/12/12 9:15
6	Water, electricity and sanitar Phase1	1	2 h	0 d	04/12/12 12:30	04/12/12 14:30
10	Cleaning foundations	1	34,25 h	0 d	06/12/12 8:30	12/12/12 10:45
17	Stremaform waterproof+steel link walls	1	2,5 h	0 d	14/12/12 10:20	14/12/12 13:20
18	Concrete filling until -1 50 m	1	9,3 h	0 d	14/12/12 13:20	17/12/12 14:38
20	Steel working conecction(existing foundation+walls)	1	14 h	0 d	21/12/12 9:23	26/12/12 7:23
24	Steel working floor	1	18,5 h	0 d	07/12/12 11:00	11/12/12 14:00
27	Steel working (connection columns with existing foundation)	1	4,75 h	0 d	07/12/12 10:34	10/12/12 7:19
30	Consolidating ground	1	11,8 h	0 d	02/01/13 14:26	04/01/13 9:44
36	Outside Formwork walls lift cases	1	13,25 h	0 d	08/01/13 13:41	10/01/13 10:26
43	Prop up for the pedallen	1	24 h	0 d	10/01/13 13:41	15/01/13 13:41
47	Formwork perimeter and holes	1	14 h	0 d	29/01/13 13:01	31/01/13 10:31

7

Josh

60 h

ID	Task Name	Units	Work	Delay	Start	Finish
27	Steel working (connection columns with existing foundation)	1	4,75 h	0 d	07/12/12 10:34	10/12/12 7:19
32	Waterproof	1	4 h	0 d	04/01/13 10:44	04/01/13 15:14
36	Outside Formwork walls lift cases	1	13,25 h	0 d	08/01/13 13:41	10/01/13 10:26
43	Prop up for the pedallen	1	24 h	0 d	10/01/13 13:41	15/01/13 13:41
47	Formwork perimeter and holes	1	14 h	0 d	29/01/13 13:01	31/01/13 10:31

ID



Resource Name

Work

8

Jan

65,67 h

ID	Task Name	Units	Work	Delay	Start	Finish
27	Steel working (connection columns with existing foundation)	1	4,75 h	0 d	07/12/12 10:34	10/12/12 7:19
32	Waterproof	1	4 h	0 d	04/01/13 10:44	04/01/13 15:14
36	Outside Formwork walls lift cases	1	13,25 h	0 d	08/01/13 13:41	10/01/13 10:26
42	Mounting beams with the connectors of the column	1	12 h	0 d	22/01/13 10:41	23/01/13 15:11
44	Mounting predallen	1	31,67 h	0 d	25/01/13 13:11	31/01/13 12:51

9

Ronny

61,17 h

ID	Task Name	Units	Work	Delay	Start	Finish
27	Steel working (connection columns with existing foundation)	1	4,75 h	0 d	07/12/12 10:34	10/12/12 7:19
32	Waterproof	1	4 h	0 d	04/01/13 10:44	04/01/13 15:14
36	Outside Formwork walls lift cases	1	13,25 h	0 d	08/01/13 13:41	10/01/13 10:26
41	Concret high strength and fast setting inside the column	1	7,5 h	0 d	18/01/13 11:11	21/01/13 10:41
44	Mounting predallen	1	31,67 h	0 d	25/01/13 13:11	31/01/13 12:51

10



Lee

113,2 h

ID	Task Name	Units	Work	Delay	Start	Finish
48	Concret working floor	1	11,75 h	0 d	31/01/13 10:31	01/02/13 14:46
4	Site planning-Topography	1	5 h	0 d	04/12/12 7:00	04/12/12 12:30
14	Plastic+Cleaning Concret	1	1 h	0 d	06/12/12 13:00	06/12/12 14:00
15	Steel working for the tower crane	1	44,33 h	0 d	06/12/12 14:00	14/12/12 9:50
34	Concrete working until - 0'16 m.	1	8,95 h	0 d	07/01/13 12:44	08/01/13 13:41
38	Inside Formwork walls lift cases	1	10,5 h	0 d	14/01/13 10:11	15/01/13 13:11
44	Mounting predallen	1	31,67 h	0 d	25/01/13 13:11	31/01/13 12:51

11

Dave

44,2 h

ID	Task Name	Units	Work	Delay	Start	Finish
45	Ventilation sistem	1	11,5 h	0 d	29/01/13 13:01	31/01/13 8:01
48	Concret working floor	1	11,75 h	0 d	31/01/13 10:31	01/02/13 14:46
12	Excavation(-3,00 m.Tower Crane)	1	3 h	0 d	06/12/12 9:30	06/12/12 13:00
13	Excavation(-1,90 m.Lift Cases)	1	1,5 h	0 d	07/12/12 8:30	07/12/12 10:00
34	Concrete working until - 0'16 m.	1	8,95 h	0 d	07/01/13 12:44	08/01/13 13:41
41	Concret high strength and fast setting inside the column	1	7,5 h	0 d	18/01/13 11:11	21/01/13 10:41

12

Werner

32,45 h

ID	Task Name	Units	Work	Delay	Start	Finish
45	Ventilation sistem	1	11,5 h	0 d	29/01/13 13:01	31/01/13 8:01
34	Concrete working until - 0'16 m.	1	8,95 h	0 d	07/01/13 12:44	08/01/13 13:41
42	Mounting beams with the connectors of the column	1	12 h	0 d	22/01/13 10:41	23/01/13 15:11

13

Tom Stragier

24,2 h

ID	Task Name	Units	Work	Delay	Start	Finish
34	Concrete working until - 0'16 m.	1	8,95 h	0 d	07/01/13 12:44	08/01/13 13:41
39	Concret working cases stairs and lifts	1	8 h	0 d	15/01/13 13:11	16/01/13 13:11
46	Steel working conecction	1	7,25 h	0 d	28/01/13 11:01	29/01/13 10:16

14

Tom Daems

35 h

ID	Task Name	Units	Work	Delay	Start	Finish
37	Steel working lift cases	1	15,75 h	0 d	10/01/13 10:26	14/01/13 10:11
40	Mounting Prefabricated columns(+prop up+formwork base)	1	12 h	0 d	17/01/13 13:41	21/01/13 9:11
46	Steel working conecction	1	7,25 h	0 d	28/01/13 11:01	29/01/13 10:16

Who Does What as of 20/06/13 17:03  
De Mouterij  
Steven Schyvynck

ID



Resource Name

Work

ID	Resource Name	Work
15	Michel	35 h
	<i>ID</i>	<i>Task Name</i>
		<i>Units</i> <i>Work</i> <i>Delay</i> <i>Start</i> <i>Finish</i>
	37	Steel working lift cases   1   15,75 h   0 d   10/01/13 10:26   14/01/13 10:11
	40	Mounting Prefabricated columns(+prop up+formwork base)   1   12 h   0 d   17/01/13 13:41   21/01/13 9:11
	46	Steel working conecction   1   7,25 h   0 d   28/01/13 11:01   29/01/13 10:16
16	Bob	31 h
	<i>ID</i>	<i>Task Name</i>
		<i>Units</i> <i>Work</i> <i>Delay</i> <i>Start</i> <i>Finish</i>
	37	Steel working lift cases   1   15,75 h   0 d   10/01/13 10:26   14/01/13 10:11
	39	Concret working cases stairs and lifts   1   8 h   0 d   15/01/13 13:11   16/01/13 13:11
	46	Steel working conecction   1   7,25 h   0 d   28/01/13 11:01   29/01/13 10:16
17	Tower crane	0 h
18	Vibrator needle 50 mm diam. gasoline	38 h
	<i>ID</i>	<i>Task Name</i>
		<i>Units</i> <i>Work</i> <i>Delay</i> <i>Start</i> <i>Finish</i>
	48	Concret working floor   1   11,75 h   0 d   31/01/13 10:31   01/02/13 14:46
	18	Concrete filling until -1'50 m   1   9,3 h   0 d   14/12/12 13:20   17/12/12 14:38
	34	Concrete working until - 0'16 m.   1   8,95 h   0 d   07/01/13 12:44   08/01/13 13:41
	39	Concret working cases stairs and lifts   1   8 h   0 d   15/01/13 13:11   16/01/13 13:11
19	Vibrator needle 30 mm diam.gasoline	30 h
	<i>ID</i>	<i>Task Name</i>
		<i>Units</i> <i>Work</i> <i>Delay</i> <i>Start</i> <i>Finish</i>
	48	Concret working floor   1   11,75 h   0 d   31/01/13 10:31   01/02/13 14:46
	21	Concret workin until -0,28 m.   1   9,3 h   0 d   26/12/12 7:23   27/12/12 8:41
	34	Concrete working until - 0'16 m.   1   8,95 h   0 d   07/01/13 12:44   08/01/13 13:41
20	Consolidation machine	11,8 h
	<i>ID</i>	<i>Task Name</i>
		<i>Units</i> <i>Work</i> <i>Delay</i> <i>Start</i> <i>Finish</i>
	30	Consolidating ground   1   11,8 h   0 d   02/01/13 14:26   04/01/13 9:44
21	Backhoe jackhammer	1 h
	<i>ID</i>	<i>Task Name</i>
		<i>Units</i> <i>Work</i> <i>Delay</i> <i>Start</i> <i>Finish</i>
	11	Foundation demolition(lifts and stairs cases)   1   1 h   0 d   06/12/12 8:30   06/12/12 9:30
22	Drain pump	0 h



Cash Flow as of 20/06/13 17:02  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13
Start								
Fenced and signaling	315,70 €							
Cleaning and clearin	394,22 €							
Site planning-Topography	164,20 €							
Provisional houses	157,85 €							
Water, electricity and sanitar Phase1	109,52 €							
Water, electricity and sanitar Phase2	189,42 €							
Take out the water of the foundation	694,54 €							
Topography foundation	118,35 €							
Cleaning foundations	1.709,55 €	2.328,53 €						
Foundation demolition(lifts and stairs cases)	169,94 €							
Excavation(-3,00 m.Tower Crane)	333,90 €							
Excavation(-1,90 m.Lift Cases)	166,95 €							
Plastic+Cleaning Concret	32,84 €							
Steel working for the tower crane	2.357,63 €	8.644,64 €						
Put the first part of the tower crane		36,15 €						
Stremaform waterproof+steel link walls		136,90 €						
Concrete filling until -1'50 m		1.048,64 €	3.452,43 €					
Formwork(walls+connection existing foundation)			5.738,65 €					
Steel working conecction(existing foundation+walls)			1.315,94 €	1.964,16 €				
Concret workin until -0,28 m.				3.190,26 €				
Removing formwork					643,97 €			
Plastic+Cleaning Concret	32,84 €							
Steel working floor	1.014,13 €	3.676,23 €						
Stremaform+steel link walls		144,58 €						
Formwork(zone columns)	4.241,24 €							
Steel working (connection columns with existing foundation)	1.367,77 €	96,05 €						
Mounting manholes		216,87 €						
Fill the spaces with sand (recycled from broken concrete).					345,38 €			
Consolidating ground					1.348,39 €			
Topography+Formwork perimetres					39,45 €			
Waterproof					340,24 €			
Stell working floor (+conecction with walls and columns)					423,22 €	8.305,72 €		
Concrete working until - 0'16 m.						10.965,47 €		
Mounting tower crane				235,16 €				
Outside Formwork walls lift cases						10.055,12 €		
Steel working lift cases						4.039,40 €	1.023,24 €	
Inside Formwork walls lift cases							8.656,34 €	
Concret working cases stairs and lifts							4.341,27 €	

Cash Flow as of 20/06/13 17:02  
De Mouterij  
Steven Schyvynck

	03/12/12	10/12/12	17/12/12	24/12/12	31/12/12	07/01/13	14/01/13	21/01/13
Mounting Prefabricated columns(+prop up+formwork base)							580,26 €	
Concret high strength and fast setting inside the column							215,91 €	
Mounting beams with the connectors of the column								
Prop up for the pedallen						1.842,10 €	2.661,50 €	
Mounting predallen								
Ventilation sistem								
Steel working conecction								
Formwork perimeter and holes								
Concret working floor								
Remove the prop of columns and pedallen.								
Outside of formwork walls FLOOR 1								
Steel working walls								
Inside of formwork walls								
Concret working walls								
Mounting Prefabricated columns(+prop up+formwork base)								
Concret high strength and fast setting inside the column								
Mounting beams with the connectors of the column								
Prop up for the pedallen								
Mounting predallen								
Ventilation system								
Steel working conecction								
Formwork perimeter and holes								
Concret working floor								
Remove the prop of columns and pedallen.								
Take out the tower crane								
END								
<b>Total</b>	<b>13.570,59 €</b>	<b>16.328,57 €</b>	<b>10.507,03 €</b>	<b>5.389,57 €</b>	<b>3.140,64€</b>	<b>35.207,81 €</b>	<b>17.478,53 €</b>	

Cash Flow as of 20/06/13 17:02  
De Mouterij  
Steven Schyvynck

	21/01/13	28/01/13	04/02/13	11/02/13	18/02/13	25/02/13	04/03/13	11/03/13
Start								
Fenced and signaling								
Cleaning and clearin								
Site planning-Topography								
Provisional houses								
Water, electricity and sanitar Phase1								
Water, electricity and sanitar Phase2								
Take out the water of the foundation								
Topography foundation								
Cleaning foundations								
Foundation demolition(lifts and stairs cases)								
Excavation(-3,00 m.Tower Crane)								
Excavation(-1,90 m.Lift Cases)								
Plastic+Cleaning Concret								
Steel working for the tower crane								
Put the first part of the tower crane								
Stremaform waterproof+steel link walls								
Concrete filling until -1'50 m								
Formwork(walls+connection existing foundation)								
Steel working conecction(existing foundation+walls)								
Concret workin until -0,28 m.								
Removing formwork								
Plastic+Cleaning Concret								
Steel working floor								
Stremaform+steel link walls								
Formwork(zone columns)								
Steel working (connection columns with existing foundation)								
Mounting manholes								
Fill the spaces with sand (recycled from broken concrete).								
Consolidating ground								
Topography+Formwork perimetres								
Waterproof								
Stell working floor (+conecction with walls and columns)								
Concrete working until - 0'16 m.								
Mounting tower crane								
Outside Formwork walls lift cases								
Steel working lift cases								
Inside Formwork walls lift cases								
Concret working cases stairs and lifts								

Cash Flow as of 20/06/13 17:02  
De Mouterij  
Steven Schyvynck

	21/01/13	28/01/13	04/02/13	11/02/13	18/02/13	25/02/13	04/03/13	11/03/13
Mounting Prefabricated columns(+prop up+formwork base)	129,06 €							
Concret high strength and fast setting inside the column	208,37 €							
Mounting beams with the connectors of the column	705,48 €							
Prop up for the pedallen								
Mounting predallen	202,94 €	2.571,06 €						
Ventilation sistem		696,90 €						
Steel working conecction		11.337,78 €						
Formwork perimeter and holes		7.395,98 €						
Concret working floor		14.503,90 €						
Remove the prop of columns and pedallen.								
Outside of formwork walls FLOOR 1								
Steel working walls								
Inside of formwork walls								
Concret working walls								
Mounting Prefabricated columns(+prop up+formwork base)								
Concret high strength and fast setting inside the column								
Mounting beams with the connectors of the column								
Prop up for the pedallen								
Mounting predallen								
Ventilation system								
Steel working conecction								
Formwork perimeter and holes								
Concret working floor								
Remove the prop of columns and pedallen.								
Take out the tower crane								
END								
<b>Total</b>	<b>1.245,84 €</b>	<b>36.505,62 €</b>						



Cash Flow as of 20/06/13 17:02  
De Mouterij  
Steven Schyvynck

	11/03/13	18/03/13	25/03/13	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13
Start								
Fenced and signaling								
Cleaning and clearin								
Site planning-Topography								
Provisional houses								
Water, electricity and sanitar Phase1								
Water, electricity and sanitar Phase2								
Take out the water of the foundation								
Topography foundation								
Cleaning foundations								
Foundation demolition(lifts and stairs cases)								
Excavation(-3,00 m.Tower Crane)								
Excavation(-1,90 m.Lift Cases)								
Plastic+Cleaning Concret								
Steel working for the tower crane								
Put the first part of the tower crane								
Stremaform waterproof+steel link walls								
Concrete filling until -1'50 m								
Formwork(walls+connection existing foundation)								
Steel working conecction(existing foundation+walls)								
Concret workin until -0,28 m.								
Removing formwork								
Plastic+Cleaning Concret								
Steel working floor								
Stremaform+steel link walls								
Formwork(zone columns)								
Steel working (connection columns with existing foundation)								
Mounting manholes								
Fill the spaces with sand (recycled from broken concrete).								
Consolidating ground								
Topography+Formwork perimetres								
Waterproof								
Stell working floor (+conecction with walls and columns)								
Concrete working until - 0'16 m.								
Mounting tower crane								
Outside Formwork walls lift cases								
Steel working lift cases								
Inside Formwork walls lift cases								
Concret working cases stairs and lifts								

Cash Flow as of 20/06/13 17:02  
De Mouterij  
Steven Schyvynck

	11/03/13	18/03/13	25/03/13	01/04/13	08/04/13	15/04/13	22/04/13	29/04/13
Mounting Prefabricated columns(+prop up+formwork base)								
Concret high strength and fast setting inside the column								
Mounting beams with the connectors of the column								
Prop up for the pedallen								
Mounting predallen								
Ventilation sistem								
Steel working conecction								
Formwork perimeter and holes								
Concret working floor								
Remove the prop of columns and pedallen.								
Outside of formwork walls FLOOR 1								
Steel working walls								
Inside of formwork walls								
Concret working walls								
Mounting Prefabricated columns(+prop up+formwork base)								
Concret high strength and fast setting inside the column								
Mounting beams with the connectors of the column								
Prop up for the pedallen								
Mounting predallen								
Ventilation system								
Steel working conecction								
Formwork perimeter and holes								
Concret working floor								
Remove the prop of columns and pedallen.								
Take out the tower crane								
END								
<b>Total</b>								


Cash Flow as of 20/06/13 17:02  
De Mouterij  
Steven Schyvynck


	<b>Total</b>
Start	
Fenced and signaling	315,70 €
Cleaning and clearin	394,22 €
Site planning-Topography	164,20 €
Provisional houses	157,85 €
Water, electricity and sanitar Phase1	109,52 €
Water, electricity and sanitar Phase2	189,42 €
Take out the water of the foundation	694,54 €
Topography foundation	118,35 €
Cleaning foundations	4.038,08 €
Foundation demolition(lifts and stairs cases)	169,94 €
Excavation(-3,00 m.Tower Crane)	333,90 €
Excavation(-1,90 m.Lift Cases)	166,95 €
Plastic+Cleaning Concret	32,84 €
Steel working for the tower crane	11.002,26 €
Put the first part of the tower crane	36,15 €
Stremaform waterproof+steel link walls	136,90 €
Concrete filling until -1'50 m	4.501,07 €
Formwork(walls+connection existing foundation)	5.738,65 €
Steel working conecction(existing foundation+walls)	3.280,10 €
Concret workin until -0,28 m.	3.190,26 €
Removing formwork	643,97 €
Plastic+Cleaning Concret	32,84 €
Steel working floor	4.690,36 €
Stremaform+steel link walls	144,58 €
Formwork(zone columns)	4.241,24 €
Steel working (connection columns with existing foundation)	1.463,82 €
Mounting manholes	216,87 €
Fill the spaces with sand (recycled from broken concrete).	345,38 €
Consolidating ground	1.348,39 €
Topography+Formwork perimetres	39,45 €
Waterproof	340,24 €
Stell working floor (+conecction with walls and columns)	8.728,94 €
Concrete working until - 0'16 m.	10.965,47 €
Mounting tower crane	235,16 €
Outside Formwork walls lift cases	10.055,12 €
Steel working lift cases	5.062,64 €
Inside Formwork walls lift cases	8.656,34 €
Concret working cases stairs and lifts	4.341,27 €


Cash Flow as of 20/06/13 17:02  
De Mouterij  
Steven Schyvynck


	<b>Total</b>
Mounting Prefabricated columns(+prop up+formwork base)	709,32 €
Concret high strength and fast setting inside the column	424,28 €
Mounting beams with the connectors of the column	705,48 €
Prop up for the pedallen	4.503,60 €
Mounting predallen	2.774,00 €
Ventilation sistem	696,90 €
Steel working conecction	11.337,78 €
Formwork perimeter and holes	7.395,98 €
Concret working floor	14.503,90 €
Remove the prop of columns and pedallen.	
Outside of formwork walls FLOOR 1	
Steel working walls	
Inside of formwork walls	
Concret working walls	
Mounting Prefabricated columns(+prop up+formwork base)	
Concret high strength and fast setting inside the column	
Mounting beams with the connectors of the column	
Prop up for the pedallen	
Mounting predallen	
Ventilation system	
Steel working conecction	
Formwork perimeter and holes	
Concret working floor	
Remove the prop of columns and pedallen.	
Take out the tower crane	
END	
<b>Total</b>	<b>139.374,20 €</b>















Project: De Mouterij Date: 20/06/13 17:06	Critical		Critical Summary		Critical Marked		Project Summary	
	Noncritical		Summary		Marked		Highlighted Critical	
	Critical Milestone		Critical Inserted		Critical External		Highlighted Noncritical	
	Milestone		Inserted		External			

**PART 7: TECHNICAL DOCUMENTS**

## **7.1. TOWER CRANE LIEBHERR 154 EC H6 LITRONIC**



POWERED BY PEOPLE

INDUSTRIELAAN 10 – 1740 TERNAT


☎ 02 / 582 29 79

☎ 02 / 582 48 28

Klant:	<b>DE NUL</b>
Contact:	<b>Dirk Hautekeete</b>
Werk:	<b>Rusthuis Mouterij - Aalst</b>

<b>LIEBHERR</b>	<b>154 EC-H6 Litronic</b>
Wn :	<b>47806</b>
HH	<b>36,3 m</b>
Gieklengte:	<b>40 m</b>
Uitvoering :	<b>betonsokkel</b>

TF ref. **KVL 856 /2012**



Tegengewicht:		
<b>12,30 ton</b>		
	gewicht (kg)	#
A	2500	3
B	1600	3
Hijsslier 37 kW		
WIW250MZ401		
Radius Tegengiek 14,1 m		
zonder looppad i/d giek		
waarvan 1blok B onder de hijsslier		

Samenstelling TK ( van boven naar onder)			
a	3	Element(en) van	2,50 m 132 HC
b	2	Element(en) van	10,00 m 132 HC
c	1	Basisel. van	6,85 m 132 HC
d	1	Fundamentanker C026.001-372.111	132 HC
(de) montage zonder telescoopkader			

Elementverbindingen		
M36x390-12.9	a-a	a-b
M36x390-12.9	b-b	b-c
M36x390-12.9	c-d	

Belastingswaarden	
In Bedrijf	
M (kNm)	1977
H (kN)	23
V (kN)	489
Md (kNm)	191
Uit Bedrijf	
M (kNm)	2312
H (kN)	51
V (kN)	441
Md (kNm)	-

Berekening Betonsokkel	
Mb (kNm)	= 2383 = (2312 +1,4 x51)
e (m)	= 1,68 = 2383 / (441 +980)
c (m)	= 1,02 = (5,4 / 2 -1,68)
Grondruk(kg/cm2)	= 1,72 = 2/3 (142078/(102 x540)

**Opmerkingen:**

1. De samenstelling van deze kraan is overeenkomstig met de eisen van de constructeur.
2. De vermelde belastingswaarden hebben geen eigenlast- en hijslastbijwaarde.
3. De aannemer is volledig verantwoordelijk voor de funderingen alsook voor de bodemweerstand. De fundering dient volledig horizontaal te liggen en moet op regelmatige tijdstippen gecontroleerd worden.  
In het geval van een mobiele kraan valt de juiste aanleg van het spoor eveneens onder zijn verantwoordelijkheid.
4. De aarding van deze kraan dient door de aannemer te gebeuren
5. Opgegeven belastingen zonder bijkomende panelen en/of verlichting op deze kraan.
6. Onze plannen, berekeningsnota's en andere documenten blijven ons eigendom en mogen, zonder onze toelating, niet aan derden worden doorgegeven.
7. Berekening stabiliteit volgens EN 14439:2009 - Windzone **C.25**

Afm. betonsokkel: 5,4 m x 5,4 m x 1,4 m

6/09/2012

J. EECKHOUT

K. VAN LOO

E. VAN AUDENRODE

Vak bestemd voor de montageploeg:

a. Kraan gemonteerd volgens de gegevens van deze technische fiche, zonder aansprakelijkheid m.b.t. de samenstelling.  
b. Wijziging van technische fiche: na telefonisch onderhoud met Dhr. ....

De chef-monteur (Naam, handtekening + datum):FORM09.01/19ed.d

## Montage

## Pieds de scellement 120 HC / 132 HC




Préparer le massif de scellement (dimension et ferrailage) d'après le calcul du massif de scellement et des plans d'armature.

Les réactions sur les semelles sont indiqués dans les tableaux «Réactions sur les semelles».




120hc\_fa\_standard.dsf



### Mise en place des pieds de scellement



(1) Boulonner les pieds de scellement au mât de base ou à l'élément de mât et arrêter les boulons.



(2) Positionner l'ensemble pieds de scellement et mât de base dans la fouille de fondation. Nivelier l'ensemble. Vérifier la verticalité de l'ensemble. Inclinaison maximale  $\pm 2\%$ .



Placer le côté de télescopage de l'élément de mât à  $90^\circ$  par rapport au mur du bâtiment, afin que la flèche soit parallèle au mur du bâtiment lors du télescopage de la grue.

(3) Caler les pieds de scellement. Poser les fers d'armature autour des pieds de scellement. Couler du béton dans la fouille de fondation. A respecter impérativement : la profondeur de prise des pieds de scellement (1125 mm) et la distance des têtes par rapport au sol (220 mm) !




Pour les dommages pouvant être imputés à une exécution inadéquate du massif de scellement ou au non-respect des conditions du sol, l'entrepreneur en assume toute la responsabilité.




## 7.2. STREMAFORM WATERPROOF (TYPE 3077)

### Stremaform type 3077



Waterdichtingssysteem voor vloerplaat / Wand

2 varianten :



Realisatie van een hoek op de werf:



Doorslijpen van de STREMAFORM



Te snijden lengte = 2 x breedte tand (voor hoek van 90° )

### 7.3. PREDAL GSS (GILBERT STEEL SOLUTIONS)

<http://www.gssbvba.be>




## 7.4. STABOX (TYPE S)

<http://www.plakagroup.com>

### Cajas de esperas para hormigón armado

Gracias a su perfil exclusivo especialmente concebido para anclarse en el hormigón, el Stabox es la única caja de esperas que realiza por si misma un anclaje capaz de soportar los elevados esfuerzos que tienen lugar en las juntas de construcción.




### Ventajas Stabox



- La **cola de milano exterior** asegura un anclaje machihembrado entre las dos fases de hormigonado. **1**
- La **doble cola de milano** ancla el perfil en el hormigón, sin que pueda salirse o moverse. El Stabox es la única caja capaz de mejorar la estanqueidad de la junta de construcción. **2**
- Las **puntas de diamante** al dorso de la caja en acero bruto mejoran la rugosidad de la superficie y permiten así la transmisión de esfuerzos rasantes y de cizallamiento. **3**
- Las **pestañas de anclaje** garantizan que los bordes de la caja no se despeguen del hormigón en el momento de retirar la tapa y aseguran una alta calidad de anclaje. **4**
- Gracias a las perforaciones longitudinales a lo largo de la **tapa de tetrapack**, su extracción es sencilla bajo cualquier circunstancia. **5**
- Los **tapones en poliestireno**, perfectamente adaptados al perfil de la caja evitan que la lechada penetre por las extremos de la caja. **6**


### Características técnicas



- Longitudes comerciales estándar de: 1,25 m y 2,45 m\*
- La anchura de la caja queda definida según el modelo.
- La altura H del perfil es de 30 mm.

**Estribos:** Acero corrugado BE 500s certificado AFCAB - BENOR - KWA.

- Ø 6 mm estirado en frío.
- Ø 8, 10 y 12 mm plegable - desplegable una sola vez.



Dimensiones de los estribos:

- Altura: A = 120 mm
- Anchura: B = 40 x Ø mm
- Ø = 85 mm
- Z = ancho de caja - 10 mm

\* La longitud del perfil es de 1,20 m y 2,40 m. Las dimensiones estándar de los estribos son según se muestran en los detalles. Otras dimensiones (A y B) a consultar.



## Puesta en obra



- 1 Comprobar que las dimensiones del Stabox elegido son compatibles con los recubrimientos exigidos en la segunda fase de hormigonado.
- 2 Comprobar la correcta ubicación de los tapones de poliestireno en los dos extremos de la caja.
- 3 Fijar el Stabox al encofrado y/o eventualmente a las armaduras.
- 4 Hormigonar la primera fase.
- 5 Después del desencofrado, quitar la tapa y los tapones de poliestireno del Stabox.
- 6 Desplegar las armaduras en espera con la ayuda de una herramienta adaptada para no crear "bayonetas".




## Stabox en curva

La caja Stabox se puede curvar serrando los cantos de la caja.



**Se tendrá especial cuidado en no cortar o estropear las armaduras plegadas en el interior.**

Los cortes se debeán que tapar antes de hormigonar para impedir que entre de lechada de hormigón.



**Es la única caja de esperas que realiza un anclaje machihembrado estanco eficaz entre dos fases de hormigonado.**

## Tipo S



45 S	
E (mm)	
Ø 6	- 200 240 300
Ø 8	150 200 240 -
Ø 10	150 200 - -

60 S	
E (mm)	
Ø 6	- - - -
Ø 8	150 200 - -
Ø 10	150 200 - -

90 S	
E (mm)	
Ø 8	- - - -
Ø 10	100 150 - -
Ø 12	100 150 200 -

## 7.5. QUEMICAL ANCHOR HILTI (HIT-HY 200-A)

### Injection mortar Hilti HIT-HY 200-A with sleeve HIS-N for anchoring in cracked and non cracked concrete

#### Presentation



Foil pack HIT-HY 200-A (urthane methacrylate)




Sleeve HIS-N

#### Characteristics


- Urethane methacrylate adhesive
- Suitable for cracked concrete
- The best bond strength of the market

#### Intended use



#### Setting instructions


Manual cleaning (Hole diameter  $d_0 \leq 20$  mm and hole depth  $h_0 \leq 10$  d)




Drill hole



Blow out at least 4 times




Brush 4 times with steel brush HIT-RB




Blow out at least 4 times


Compressed air cleaning (all diameter and length of hole)



Drill hole




Blow 2 times with compressed air (mini 6 bars)




Brush 2 times with steel brush HIT-RB



Blow 2 times with compressed air (mini 6 bars)




Attach the mixer and insert the cartridge in the holder and twist the holder in the dispenser.




Discard initial adhesive.



Inject the adhesive starting at the back of the hole.




Slowly withdraw the mixer at each trigger pull.



Fill holes approximately 2/3 for pre-setting and 100% full for through setting.



Insert the element before the end of the working time  $t_{work}$ .



After curing time  $t_{cure}$ , apply the torque moment.

#### Concrete temperature during installation

Temperature of base material	Working time "t <sub>work</sub> "	Curing time "t <sub>cure</sub> "
-10 °C to -5 °C	1,5 hour	7 hour
-4 °C to 0 °C	50 min	4 hour
1 °C to 5 °C	25 min	2 hour
6 °C to 10 °C	15 min	1 hour
11 °C to 20 °C	7 min	30 min
21 °C to 30 °C	4 min	30 min
31 °C to 40 °C	3 min	30 min


#### Concrete temperature during life time of the building

Plage de température	Température du matériau support	Température à long terme	Température à court terme
I	- 40 °C to + 40 °C	+ 24 °C	+ 40 °C
II	- 40 °C to + 80 °C	+ 50 °C	+ 80 °C
III	- 40 °C to + 120 °C	+ 72 °C	+ 120 °C

Discard quantities :  
 2 strokes for 330 ml foil pack  
 3 strokes for 500 ml foil pack  
 4 strokes for 500 ml foil pack  $\leq 5^\circ\text{C}$



**Design in accordance with European design method  
(chemical anchors with variable embedment depth EOTA TR 029)**



dated 06/02/2012 – Option 1  
Valid until 23/12/2016

**Material**

HIS-N	Steel	Protection	HIS-RN	Steel	Protection
Sleeve	Class 5.8	Galvanised 5 µm	Sleeve	A4-70	Stainless
Rec. screw	Mini class 8.8	Dependent on the application	Rec. screw	A4-70	Stainless
Rec. washer		Dependent on the application	Rec. washer	A4	Stainless

Material characteristics		M8	M10	M12	M16	M20	
$f_{u,k}$ (N/mm <sup>2</sup> )	Nominal tensile strength	HIS-N	510	510	460	460	460
		HIS-RN	700	700	700	700	700
$f_{y,k}$ (N/mm <sup>2</sup> )	Yield strength	HIS-N	410	410	375	375	375
		HIS-RN	350	350	350	350	350
$A_S$ (mm <sup>2</sup> )	Stressed cross-section	Sleeve	53,6	110	170	255	229
		Rod / bolt	36,6	58	84,3	157	245
$M_f$ (N.m)	Moment of resistance (ELU)	Rod / bolt steel 8.8	24,0	48,0	84,0	212,8	415,2
		Rod / bolt steel A4-70	16,7	33,3	59,0	149,4	291,0

**Setting details**

Sleeve HIS-N	Diameter of hole $d_0$ (mm)	Drill hole depth $h_1$ (mm)	Effective embedment depth $h_{ef}$ (mm)	Minimum base material thickness $h_{min}$ (mm)	Torque moment $T_{max}$ (N.m)	Diameter of clearance hole in the fixture $d_f$ (mm)	Screwing length $h_s$ (mm)		Sleeve length L (mm)	External diameter of the sleeve d (mm)
							min	max		
							M8x90	14		
M10x110	18	110	110	150	20	12	10	25	110	16,5
M12x125	22	125	125	170	40	14	12	30	125	20,5
M16x170	28	170	170	230	80	18	16	40	170	25,4
M20x205	32	205	205	270	150	22	20	50	205	27,6

**Article numbers**


	HIS-N	HIS-RN
M8X90	258 015	258 024
M10X110	258 016	258 025
M12X125	258 017	258 026
M16X170	258 018	258 027
M20X205	258 019	258 028

Designation	Volume	Article number
Cartridge HIT-HY 200-A	330 ml	2022696
Cartridge HIT-HY 200-A	500 ml	2022697

**Pre-calculated values | Temperatures range 1 (+ 24°C | + 40°C)**

**Full load - Cracked concrete - Galvanised and stainless versions (kN)**

One isolated anchor, full load, non reinforced C20/25 concrete, cracked (without edge distance nor spacing influence)



HIT-HY 200-A and sleeve HIS-N			Tension		Shear	
Size	$h_{nom}$ (mm)	$h_{min}$ (mm)	Resistance values		Resistance values	
			Design $N_{rd}$	Rec. $N_{rec}$	Design $V_{rd}$	Rec. $V_{rec}$
<b>Galvanised version HIS-N</b>						
M 8	90	120	16,5	11,8	10,4	7,4
M 10	110	150	26,6	19,0	18,4	13,1
M 12	125	170	33,5	24,0	26,0	18,6
M 16	170	230	53,2	38,0	39,3	28,1
M 20	205	270	70,4	50,3	36,7	26,2
<b>Stainless steel version HIS-RN</b>						
M 8	90	120	13,9	9,9	8,3	6,0
M 10	110	150	21,9	15,7	12,8	9,2
M 12	125	170	31,6	22,5	19,2	13,7
M 16	170	230	53,2	38,0	35,3	25,2
M 20	205	270	69,1	49,4	41,5	29,6

**7.6. VANDERSANDEN MORVAN (ZWART)/ RIJSWAARD ENGELS  
BONT (ROOD)**

# Specificatieformulier metselbaksteen

NEN-EN 771-1



HD, categorie I, groep 1, brandgedrag A1

Producttype			Vol	Met "frog"	Geperforeerd	KOMO-Logo (BRL 1007 en CI)
		Vormbak				
		Strengpers				
		Handvorm		X		
						Certificaatnummer: Kiwa, K53304
Visuele Kenmerken	Kleur	Volgens monster				Logo producent: <b>RIJSWAARD BAKSTEEN</b>
		Omschrijving (vlgs koopovereenkomst)				
	Oppervlakte zichtvlak	Onbezand		Gestructureerd		
		Bezand	X	Geglazuurd		
Glad		Geëngobeerd				
						Datum aanvraag: n.b.
Afmetingen (mm)		Lengte x Breedte x Hoogte: ...214...x...102...x...66.....				Productsoort:
Maattolerantie gemiddelde maat		T1, T2 of Tm <sup>2)</sup>			T2	Engels-Bont HV EF   DR1B
		2) .....x.....x..... mm voor resp. l, b en h				
Maatspreiding		R1, R2 of Rm <sup>3)</sup>			R1	Aantal: ± 58.032 st
		3) .....x.....x..... mm voor resp. l, b en h				Leveringsdatum: n.b.
Initiële wateropzuiging <sup>1)</sup> (kg/m <sup>2</sup> .min)	Zeer weinig zuigend		(<0.5)			Bouwwerk: Mouterij te Aalst (B)
	Matig zuigend		(0.5 – 1.5)			
	Normaal zuigend		(1.5 – 4.0)		X	
	Sterk zuigend		(>4.0)			
Wateropneming <sup>1)</sup>		Vrijwillige wateropneming (massa %)			≤ 15% m/md	Architect: n.b.
Volumieke massa <sup>1)</sup>		Bruto volumieke massa (kg/m <sup>3</sup> )			1650	Aannemer: De Nul
Tolerantie volumieke massa <sup>1)</sup>		D1, D2 of Dm <sup>4)</sup>			D2	Opdrachtgever: n.b.
		4) ..... %				
Actieve oplosbare zouten <sup>1)</sup>		Wateroplosbaar Na + K en Mg	S0			Aanvrager: Verhelst Bouwmaterialen
			S1			
			S2	X		
Vorst-dooi weerstand		F0				Naam, datum en handtekening:
		F2, vorstklasse C, BRL 1007				Mw M. Lataire
		F2, vorstklasse D, BRL 1007			X	Leverancier: Steenfabriek De Rijswaard BV
Warmtegeleidbaarheid <sup>1)</sup> λ (W/mK)					0.43 W/mk	De Rijswaard 2, 5308 LV AALST
Waterdampdoorlatendheid <sup>1)</sup> μ					5/10	Naam, datum, handtekening: A. Josemanders, 19 februari 2013
Bouwstoffenbesluit		Ja / Nee			Ja/1B	Aanvullende informatie van de producent:
Specifieke toepassingen		Precisiemetselwerk / kromheid vlgs BRL 1007			X	<b>Steenfabriek De Rijswaard B.V.</b> De Rijswaard 2 5308 LV AALST Tel 0418 - 55 22 21   Fax 0418 - 55 29 00 E-mail: info@rijswaard.nl
		Product voor schilderwerk (SO <sub>4</sub> ≤ 0.10 %)			X	
Genormaliseerde druksterkte <sup>1)</sup> (N/mm <sup>2</sup> )		5.0 / 7.5 / 10.0 / 12.5 / 15.0 / 20.0 / 25.0 / 30.0 / 35.0 / 40.0, etc.			≥ 15 N/mm <sup>2</sup>	

Vakken met een grijsarcering (evt.) aan te kruisen. 1) De cursief gedrukte declaraties zijn op basis van gemiddelde waarden.



WF  
206 x 98 x 51 mm

NL	FR	DE	IT	PL	RU	UK
<p>Een mengsel van verschillende, uitgelezen kleisoorten vormt de basis voor deze gevelsteen. Dit mengsel is uitermate geschikt voor de productie van handvormgevelsteen. Door gebruik te maken van speciale zandsoorten voor de oppervlaktebehandeling wordt de gewenste kleur bekomen.</p>	<p>Un mélange de différentes types d'argile forme la base de ces briques de parement. Ce mélange est idéal pour la production de briques faites-main. La couleur finale est obtenue en utilisant des types de sables spécifiques pour le sablage de surface.</p>	<p>Eine Mischung von unterschiedlichen Lehmarten bildet die Basis dieser Verblender. Diese Mischung ist besonders geeignet für die Produktion von handgeformter Verblender. Durch die Verwendung und Verteilung über die Oberfläche von angemessenen Sandsorten wird der gewünschte Farbton erzielt.</p>	<p>A mix of different kinds of clay forms the basis for this facing brick. This special mix of clays is ideally suited for the manufacturing of hand formed bricks. By using specific sand types for surface covering, the desired colour is achieved.</p>	<p>Syngomani do wurobu tuch segiel elewacyjnej sa mieszanki glinych rodzajow gliny. Ta specjalna mieszanka do rozlujow rodzajow gliny jest idealna dostozowana do produkcji segiel rezalne formowaluch. Różne kolory ilica, otrzymani sie poprzez zastosowanie roznych segiel gatu-ków rózku.</p>	<p>Средняя нормированная прочность при сжатии</p> <p>Допустимые отклонения от номинальных размеров</p> <p>Категория допустимых отклонений от номинальных размеров</p> <p>Стабильность формы</p> <p>Содержание цементных растворов</p> <p>Содержание активных растворимых солей</p> <p>Огнеустойчивость: Еврокласс</p> <p>Водопоглощение</p> <p>Капиллярное водопоглощение</p> <p>Паропроницаемость</p> <p>Масса нетто</p> <p>Масса брутто</p> <p>Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math></p> <p>Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math></p> <p>Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math></p> <p>Морозоустойчивость</p>	<p>Основной цвет: черный</p> <p>Описание: одноцветный, антрацит</p> <p>Между различными партиями возможны незначительные различия.</p> <p>В зависимости от объема продукции возможны некоторые отклонения в размерах.</p>
<p><b>Kleur</b> Hoofdkleur: zwart Beschrijving: uniform antraciet-zwart</p>	<p><b>Couleur principale: noir</b> Description: anthracite-noir uniforme</p>	<p><b>Farbe</b> Hauptfarbe: schwarz Beschreibung: unifarbener anthrazit-schwarz</p>	<p><b>Color</b> Main colour: black Description: unicoloured anthracite black</p>	<p><b>Barwa</b> Kolor podstawowy: czarny Opis: jednokolorowy antracytowo-czarny</p>	<p><b>Цвет</b> Основной цвет: черный Описание: одноцветный, антрацит</p>	<p><b>Color</b> Main colour: black Description: unicoloured anthracite black</p>
<p><b>Formaat</b> Naargelang de bakserie kunnen deze schommelingen in de kleuruance mogelijk.</p>	<p><b>Les différentes cuissons peuvent présenter des légères variations de couleur.</b></p>	<p><b>Je nach Serie können die Durchschichtliche Maße leicht abweichen.</b></p>	<p><b>Slight differences from one series to another are possible.</b></p>	<p><b>Различия в размерах возможны в зависимости от партии.</b></p>	<p><b>В зависимости от объема продукции возможны некоторые отклонения в размерах.</b></p>	<p><b>Slight differences from one series to another are possible.</b></p>
<p><b>CE NBN EN 771-1 CAT1 - HD</b></p>	<p><b>Speifieke eigenschappen</b> Gemiddelde druksterkte T2 Maatolerantiecategorie R1 Maatspreiding Vormstabiliteit O,04 mm/m O,15 N/mm2 52. A1 ≤ 7% (m/m) 1,5 - 4 kg/m2.min ; IW3 50/100 2090 kg/m3 (D1) 1940 kg/m3 (D1) 0,62 W/mk 0,65 W/mk 1,38 W/mk F2</p>	<p><b>Druckfestigkeit</b> Abmessungen: Tolernzkat. Abmessungen: Maßspanne Übliche Feuchtedehnung Verbindfestigkeit (Mauerwerk) Geh. an akt. löslichen Salzen Brandverhalten: Euroklasse Wasserdampfrate Anfängliche Wasseraufnahme Wasserzähpfähigkeit Netto-Trockendichte Brutto-Trockendichte Wärmeleitfähigkeit <math>\lambda_{\text{ср}}(90/90)</math> Wärmeleitfähigkeit <math>\lambda_{\text{ср}}(90/90)</math> Wärmeleitfähigkeit <math>\lambda_{\text{ср}}(90/90)</math> Frostwiderstand</p>	<p><b>Свойства продукции</b> Выступают на сжатие Категория толеранци (умтарowej) Рóżnica rozmiarow Stabilność formy Przyzwerność (zaprawa spoinowa) Zawartość aktywnych soli Odporność na ogień: Klasa Euro Nasiąkliwość Początkowe wchłanianie wody Przepuszczalność paru wodnej Masa netto suchych segiel Masa brutto suchych segiel Przewodność cieplna <math>\lambda_{\text{ср}}(90/90)</math> Przewodność cieplna <math>\lambda_{\text{ср}}(90/90)</math> Przewodność cieplna <math>\lambda_{\text{ср}}(90/90)</math> Mrozoodporność</p>	<p><b>Свойства продукции</b> Выступают на сжатие Категория толеранци (умтарowej) Рóżnica rozmiarow Stabilność formy Przyzwerność (zaprawa spoinowa) Zawartość aktywnych soli Odporność na ogień: Klasa Euro Nasiąkliwość Początkowe wchłanianie wody Przepuszczalność paru wodnej Masa netto suchych segiel Masa brutto suchych segiel Przewodność cieplna <math>\lambda_{\text{ср}}(90/90)</math> Przewodność cieplna <math>\lambda_{\text{ср}}(90/90)</math> Przewodność cieplna <math>\lambda_{\text{ср}}(90/90)</math> Mrozoodporność</p>	<p><b>Свойства продукции</b> Выступают на сжатие Категория толеранци (умтарowej) Рóżnica rozmiarow Stabilność formy Przyzwerność (zaprawa spoinowa) Zawartość активных растворимых солей Огнеустойчивость: Еврокласс Водопоглощение Капиллярное водопоглощение Паропроницаемость Масса нетто Масса брутто Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math> Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math> Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math> Морозоустойчивость</p>	<p><b>Свойства продукции</b> Выступают на сжатие Категория толеранци (умтарowej) Рóżnica rozmiarow Stabilność formy Przyzwerność (zaprawa spoinowa) Zawartość активных растворимых солей Огнеустойчивость: Еврокласс Водопоглощение Капиллярное водопоглощение Паропроницаемость Масса нетто Масса брутто Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math> Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math> Темперопроводность <math>\lambda_{\text{ср}}(90/90)</math> Морозоустойчивость</p>

