


SINTRUPVEJ

LEYEND

SHED AREA AND STORAGE AREA:



DRESSING ROOM



DINNING ROOM



OFFICES



CONTAINERS FOR MATERIALS



CONTAINERS FOR SEPARATED GARBAGES
A. Recyclingable
B. Inflammable
C. Flammable

WORKING AREA:



FENCE



SIGNBOARDS



LIGHT IN COMMON
WORKING AREA



STORAGE AREA FOR
EQUIPMENT AND MATERIALS



PARKING AREA DURING CONSTRUCTION

TECHNICAL APPLIANCES




CRANE TOWER

SERVICES



ELECTRICITY



COLD WATER




TELEPHON/TV



SEWER


AFTER CONSTRUCTION



PARKING PLACE



ENTRANCE ROAD



NOTE:

EXTERNAL ACCESS WAYS:
ALL CARS HAVE TO BE ON
PUBLIC STREET

TRANSPORT ROADS:
MATERIALS AND EQUIPMENTS
ARE PLACED ON THE PARKING
ZONE
THERE ARE LIFTED UP FROM
THERE TO EACH FLOOR
NO DEPOTS ON PUBLIC ROADS
OUTSIDE THE SCAFFOLDING.

ACCESS ON THE BUILDING SITE:
FROM THE PERPENDICULAR TO
SINTRUPVEJ

CLEANING UP:
ALL THE BUILDING SITE MUST BE
CLEANED OUT AFTER A
WORKING

DAY, SPECIALLY THE ACCESS
ROAD AREA (ACCES ROAD,
OUTSIDE
AND OUTSIDE THE BUILDING).
EVERY FRIDAY THERE WILL BE A
GENERAL CLEARANCE.

LIGHTING:
ALL THE CONTRACTOR ARE
RESPONSIBLE TO PUT UP SOME
TEMPORARY LIGHT INSIDE AND
OUTSIDE THE BUILDING TO
ENSURE
GOOD VISIBILITY AT ANY TIME IN
THE DAY

CABINS:
THE MAIN CONTRACTOR IS
RESPONSIBLE FOR THE SET UP
OF
SANITARY CABIN, OFFICES ON
THE BUILDING SITE. THE CABINS,

OFFICES, SANITARY CABINS WILL
BE CONNECTED TO THE SEWER,
ELECTRICITY AND WATER.

WATER AND ELECTRICITY ON
THE BUILDING SITE:
MAIN CONTRACTOR MUST
ENSURE THE STABLISHMENT
OF
WATER AND ELECTRICITY ON
THE BUILDING SITE

LOCKING OFF ON THE BUILDING
SITE:
THE MAIN CONTRACTOR WILL
STABLISH FENCES AROUND THE
BUILDING SITE (MIN 2M HEIGHT)
THE BUILDING SITE MUST BE
CLOSED AND LOCKED AFTER A
WORKING DAY.
THERE WILL BE ALSO COME
WARNING SIGNS WHICH ARE PUT
UP

SAFETY PROVISION:
MAIN CONTRACTOR HAS FULL
RESPONSABILITY FOR THE
ESTABLISHMENT OF THE
TEMPORARY SUPPORT.

THERE WILL BE A TELEPHONE,
FIRST AID KIT, EXTINGUISHER

INTHE OFFICE CABIN
(COURTYARD SIDE)

WINTER PRECAUTIONS:
PERIOD: 1/11 - 31/03

SEASON RELATED:
(RESPONSABILITY OF THE MAIN
CONTRACTOR)
- OUTDOOR LIGHT
- INDOOR LIGHT
- COVERING OF MATERIALS
- TOTAL COVERING (BUILDING)

- PROTECTION OF
TEMPORARY WATER
- PIPES AGAINST FROST

WEATHER RELATED:
- CLEANING OF SNOW
- PROTECTION OF MATERIALS
AGAINST FROST
- HOT CONCRETE
- INSULATION OF CONCRETE
FORM WORK

VIA

UNIVERSITY COLLEGE
SCHOOL OF TECHNOLOGY AND BUSINESS - Horsens

PROJECT: New Administration Building for NIELS NISSEN A/S

SCALE:1:200

SUBJECT: SITE PLAN

CREATED BY: Cristina Miret Román

CLASS:
CAHS 72

BDe_SP_1