

**PROCESCONTROLPLAN:**

Case: Vejlevej 19 ..... Nr.: ..... 1 ..... Rev.: .....

Activity	Controlled by	Control frequency	Control ds482 p 39	Control method	Accepting-criteria	Documentation of control	Remarks
Formwork control	Maria Garcia	Formwork must be controlled before each pour is implemented.	Geometry/appearance Stability/anchorage Tightness/ Cleanliness. oil. placement $\pm 10$ mm	Visual/measurement/ photo	DS 482	Process control document	
Reinforcement control	Maria Garcia	Reinforcement works must be controlled before each pour.	Right type,dimensions/Clean, right bent & fixed. tension. $\pm 10$ mm for each, then $\pm 20$ for secondary	Visual/measurement/ Photo/physical movement	DS 482	Process control document	
Casting concrete control	Maria Garcia	Correct level/ Vibration every 300mm/right type of concrete/casting first and per 10th repetition/curing first and per 5th repetition	Separation and compression, Casting & floating process, temperature conditions, after care. concrete placement & correct vibration.	Visual/measure/ photo	DS 482	Process control document	