



BUILDING SITE PLAN




C 2: Cabin 2 OFFICE (2 rooms + bathroom)



Lightning on wooden pole

C 1: Cabin 1 (Bathroom facilities + changing room + dining room)



NOTE:

EXTERNAL ACCESS WAYS: CARE ARE REFERRED TO PUBLIC ROADS.

INTERNAL ACCESS ROADS: THE MAIN STAIRCASE CAN BE USED FOR VERTICAL TRAFFIC BETWEEN FLOORS.

CLEANING UP: A GENERAL CLEARANCE IS MADE ONCE A WEEK. EACH CONTRACTOR SHALL CLEAN UP AFTER THEMSELVES.

WHEN THE CONTAINERS ARE FULL THE MAIN CONTRACTOR SHALL CHECK THAT THEY ARE TAKEN IMMEDIATELY AWAY.

LIGHT: THE HOLE BUILDINGSITE WILL BE LIGHT UP. THERE WILL BE PUTT UP LIGHT POLES SO THAT THERE SHOULD NOT BE ANY DARK SPOTS. AS THE BUILDING RISES LIGHTS WILL BE INSTALLED ON EVERY FLOOR AND EVERYWHERE NEEDED.

WELFARE PROVISION: THE MAIN CONTRACTOR IS RESPONSIBLE FOR ALL SECURITY AND MUST MAKE SURE THA ALL THE OTHERS CONTRACTORS FOLLOW THEM UP.

THE MAIN CONTRACTOR SHALL ALSO SEE TO THAT ALL CABINS MUST BEEN CLEAN ONCE A WEEK.

THE FIRST AID KIT WILL BE PLACED IN THE CABINS.

ELECTRICITY POWER: THE ELECTRICIAN CONTRACTOR ESTABLISHES AND MAINTAINS ELECTRICAL POWER AND SITE LIGHT.

WATER FOR THE BUILDING: THE PLUMBER CONTRACTOR ESTABLISHES AND MAINTAINS SITE WATER SUPPLY.

LOOKING AFTER THE BUILDING AND THE SITE: THE MAIN CONTRACTOR IS RESPONSIBLE FOR THE FUNCTION DURING THE PROJECT.

SAFETY PROVISIONS: THE MAIN CONTRACTOR IS RESPONSIBLE FOR SAFETY, SHORING AND CLOSING OFF ALL STORIES IN CONNECTION WHEN THE ARE PUT UP.

SEWER: THE CONNECTION FOR SEWER TO THE PORTABLE CABINS WILL BEE EXECUTED BY THE PLUMBER CONTRACTOR AFTER AGREEMENT WITH THE LOCAL COUNCIL.

Perimeter fence with galvanized mesh on concrete supports and woven mesh cladding for hiding views