

CONTENTS

Acknowledgements	XV
Abstract	XVII
1 Thesis Overview	1
1.1 Introduction	1
1.2 Offshore Wind Farms	3
1.2.1 Offshore wind turbine technologies	5
1.2.2 Offshore power transmission	8
1.2.3 Technical feasibility of diode based HVdc transmission	13
1.3 Research Approach	14
1.3.1 Thesis goal and objectives	15
1.4 Thesis Outline	15
2 System Modelling	17
2.1 Introduction	17
2.2 Wind Turbine Modelling	18
2.2.1 Aerodynamic model	19
2.2.2 Mechanical model	20
2.2.3 Electrical model	21

2.3	Offshore Wind Farm Modelling	25
2.3.1	Aggregated model of an offshore wind farm	25
2.3.2	Distributed model of an offshore wind farm	29
2.3.3	Clustered model of an offshore wind farm	31
2.4	Diode Based HVdc-Link Modelling	33
2.4.1	Offshore capacitor and filter bank	34
2.4.2	Offshore diode-based rectifier	36
2.4.3	HVdc link reactance and cable model	37
2.4.4	Onshore LCC-HVdc inverter	38
2.5	Summary	40
3	Overview of the Offshore Wind Farm Control Strategy	43
3.1	Introduction	43
3.2	Wind Turbine Control Tasks	44
3.2.1	Speed control	44
3.2.2	Back-to-back dc-link voltage control	47
3.3	Wind Turbine Grid Integration Tasks	48
3.3.1	Modes of operation	49
3.4	Summary	54
4	Control of the Aggregated Offshore Wind Farm	57
4.1	Introduction	57
4.2	Wind Turbine Control	58
4.2.1	Wind turbine speed control	59
4.2.2	PMSG current control	64
4.2.3	Back to back converter dc-link voltage control	67
4.2.4	Wind turbine control performance	69
4.3	Wind Turbine Grid Integration	71
4.3.1	Front-end converter current control	72
4.3.2	Offshore ac-grid voltage control	75
4.3.3	Offshore ac-grid frequency control	78
4.3.4	Protection Strategy and Fault Ride Through Capability	80

4.4	Stability Analysis	83
4.4.1	Stability analysis in connected operation mode	83
4.4.2	Stability analysis in islanded operation mode	106
4.5	Results	113
4.5.1	Offshore ac-grid and HVdc link start-up operation	114
4.5.2	Response to frequency changes at rated power	115
4.5.3	Wind farm power control	119
4.5.4	Fault-ride-through performance during onshore faults	122
4.5.5	Voltage and frequency control during rectifier ac-breaker operation	127
4.6	Summary	129
5	Distributed Control of the Offshore Wind Farm	131
5.1	Introduction	131
5.2	Grid Integration of the j^{th} cluster	133
5.2.1	Current control of the j^{th} cluster model	133
5.2.2	Distributed voltage and frequency control	136
5.3	Stability Analysis	140
5.4	Results	158
5.4.1	Islanded operation (operation mode A)	158
5.4.2	Connected operation	164
5.4.3	Transient performance	167
5.5	Summary	174
6	Conclusions and Future Works	177
6.1	Conclusions	177
6.1.1	More relevant information	177
6.1.2	More relevant contributions	179
6.2	Future Works	180
Bibliography		181