STUDY and CONSTRUCTIVE ANALYSIS of an OFFICE BUILDING



BACHELOR FINAL PROJECT

AUTOR: Paula Cort Azcárraga ACADEMIC TUTOR: Frank Verplanken

Home University: Universidad Politécnica de Valencia (Spain) Host University: Kaho Sint-Lieven (Belgium)



ACADEMIC YEAR 2013/2014



Introduction

My name is Paula Cort Azcárraga and I am from Valencia, Spain. For the last four years I have been studying buildingconstruction at the Universidad Politéctica, sited in Valencia. I chose to go with building construction because it is what I have a passion for. I grew up with my father as a construction worker, and I was always fascinated by it at a young age. Construction offers people the opportunity to see the fruits of their labor on a day to day basis. I also think of construction as a classical trade in that you constantly learn and improve your ability over time.

My school offered me the opportunity to study abroad through an Erasmus Exchange program and I didn't hesitate to accept it. I chose Belgium because of its gorgeous historic monuments, castles, cobblestone architecture and beautiful art work. I thought it is one of the best countries to learn about building construction. Moreover, the people here are very fluent in English and this could help me to improve this language. Belgium is widely known as the heart of Europe and a hub for international networking.

Studying in a different country has provided me a huge expertise and knowledge about a variety of subjects in more depth and from a different cultural perspective. The way of learning in Belgium varies considerably from the way I used to study in Spain. Here, practical learning is much more emphasized than theoretical. I personally think that the way used here is more useful and provides more knowledge that I will need in my future.

Moreover, I have learnt several ways to built, specifically the prefabricated technique, which is very used in Belgium, in Spain most of construction is made is situ and not usual to move from a different place.

Appreciation

First of all, I would like to thank Frank and Steve for their time and dedication on my project. I would not have been able to do it without their help and patience, not only at class but also at the work. Their knowledge and expertise is very much appreciated.

I also wish to thank all the members of the Kaho Sint-Lieven for being always willing to help and for making things easier.

It was a pleasant experience and without their support it wouldn't have been possible.

Index

PART 1. Site installation plan

- Present the building and its distribution
- Implanting.
 Crane characteristics.
 PLANE 1
 PLANE 2
- Facades. PLANE 3
 Structure. PLANE 4

PART 2. Principal section

- Longitudinal section. PLANE 5

PART 3. Detailed drawings

- Detail 1. PLANE 6
- Detail 2. PLANE 7
- Detail 3. PLANE 8
- Detail 4. PLANE 9
- Detail 5. PLANE 10
- Detail 6. PLANE 11
- Detail 7. PLANE 12
- Detail 8. PLANE 13
- Detail 9. PLANE 14
- Detail 10. PLANE 15

PART 4. Technical study.

- Precast stairs
- Stairs details PLANE 16
- Step by step. PLANE 17

PART 5. Comparative study

- Propos the comparative
- Comparative table
- Details PLANE 18, PLANE 19
- Step by step PLANE 20/21/22/24

PART 6. Scheduling and pricing

- Schedule work. GANTT

Part 1.

Site installation plan



This is a building for office use, has 4 level + basement. The structure is with prefabricated concrete, excluding the basement slab, this is in situ.








BASEMENT GROUND, FIRST AND SECOND FLOOR

The use of ceramic brick and concrete brick is also combined.



Concrete block has more resistance than ceramic, but the last is cheaper.



When I arrive at work, hollow core slab was placed. There are two types.

- 1 type: Thickness 0.15 m + 0.05
- 2 type: Thickness 0.24 m + 0.05
- 3 type: Thickness 0.40 m + 0.05

Hollow slab



Insulation: recticel, polyurethane.





Brick facade




Facane brick: 5 x 9 x 12 cm

Insulation: polyurethane, 8 cm (depends on the site of placement)

Ceramic brick: 11 x 12 x 24 cm



Prefabricated stairs



Windows







Cantilever








HEB 180 anchored floor using steel sheet.

When I get to the work they were completing the structure. I could see how the structure is finished, the facade was performed using a scaffold; placement of windows, electrical installation, sanitary and air conditioning. The cantilever construction and removal of the tower crane.





FINAL BACHELOR PROJECT

DESCRIPTION

PART 1 Site installation plan

IMPLANTATION

PLANE N° :

1



UNIVERSIDAD POLITECNICA DE VALENCIA



STUDENT

Paula Cort Azcárraga

SCALE

1 / 500

DATE



The tower crane is placed outside the future building. Just in the middle in front the principal facade.

In this way we need a radius of 50 meters to reach the stockpile area and the debris area. Secondly, we need at least 20 m hight, because

our building

have 16 m. since the foundation of the crane, to the most elevated pont of the building. We choise the model: Liebherr 1 80 EC-H 10. Finaly, we need to know the lifting capacity and the lift capacity, as we work with precast elements. So LM1=3150 kg. is enought for us./ About the adjacent buildings and their protection, there aren't any problem.

2200 kg 2600 kg

3150 kg

3800 kg 4750 kg


Radius and Capacity

Stockpiles area

DROGSESTEENWEG

hook reach m m		m/kg											LM1						
			24	8	18	ß	32	34	36	8	40	42	45	8	50	52	55	58	60
60	(61.6)	24-173	6020	6310	5790	\$340	4940	4660	4290	4030	3/60	3540	1240	2980	2820	2680	2450	2300	1200
55	(56.6)	24-179 10000	7190	6560	6020	5550	\$140	4790	4470	4180	3920	3500	1389	3110	2050	2800	2600		
50	(616)	24 18.8 10990	7600	6940	6370	5880	5450	5080	4740	4440	4170	3030	3600	3320	3150				
45	(46.6)	24-19.6	7570	7280	6690	6180	5730	5340	4990	4670	4390	4140	3800						
40	(41.6)	2.4-20.9 10006	8570	7830	720	6668	6180	5760	5390	5050	4750								

Debris area



R60,00 R55,00 R50,00 R45,00

STUDY and CONSTRUCTIVE ANALYSIS of an **OFFICE** BUILDING located in Ghent

FINAL BACHELOR PROJECT

DESCRIPTION

PART 1

Site installation plan

TOWER CRANE

PLANE N° :





UNIVERSID∆D POLITECNICA DE VALENCIA



STUDENT

Paula Cort Azcárraga

SCALE

1 / 500

DATE



FINAL BACHELOR PROJECT

DESCRIPTION

PART 1 Site installation plan

FACADES

PLANE N° :

3



UNIVERSIDAD POLITECNICA DE VALENCIA




STUDENT

Paula Cort Azcárraga

SCALE


1 / 250


DATE



Part 2.

Principal section





–Plant 5cm –Substrate 6cm

-Foil -Drainage 4cm

-Absorbent and mechanical protective cloth -EPDM


-Flameproof insulation 3*5cm -Drampscherm

-Concrete ramp 4cm, 1.5% -Hollow core slab 40+5+3cm

-Void 30cm -Ceiling5cm

00000{0000000{00000}	00000{000000	00000000000	00001000	000{00000000000000000000000000000000000	000{000000}00			
24	4,3		06	0,05				
-Raised floor 16cm -Hollow core slab 40+5+3 cm -Void 47 -Ceiling 5cm				2,75				
000000000000000000000000000000000000000	000000000000000000000000000000000000000	000000000000000000000000000000000000000	<u>000\$0000</u> 1 5	000{00000000000000000000000000000000000	000100000100	000000000000000000000000000000000000000		
4,6			0,05	10,79				
-Raised floor 16cm -Hollow core slab 40+5+3 cm -Void 47 -Ceiling 5cm			2,57			0		
000000000000000000000000000000000000000)00000{{00000}	00000000000000000000000000000000000000	0000{000	000{0000000}000	000{00000{00	000000000000000000000000000000000000000		
+5+3 cm		3,55 500	2,57		7,17			
	7,15		2,97 0,05	3,55		3,52		
	010000000000000000000000000000000000000					4,23		
ickwork wall 3,65	3,65		3,26	4,07	- Concrete po - Workplace g	rayed 6cm at + uitvulling 10cm oured in situ 30cm granular concrete 7cm		

42,32



	Insolate	<u>{000000}</u>	Hollow core slab
	Plant		Rebar
	Concrete		Gravel
	Brickwok (11x12x24 cm)		- EPDM
4	Prefabricated concrete	日	Brickwok (5x9x24 cm)
	Dranaige		Carpet

STUDY and CONSTRUCTIV **ANALYSIS** of an OFFICE BUILDING located in Ghent **FINAL BACHELOR** PROJECT DESCRIPTION PART 2 PRINCIPAL SECTION P-P' PLANE N° : UNIVERSIDAD POLITECNICA DE VALENCIA KAHO KAHO Sint-Liever


STUDENT Paula Cort Azcárraga

SCALE 1 / 50

DATE 16 / JUNE / 2014

Part 3.

Details



FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 1

PLANE N° :





UNIVERSIDAD Politecnica de Valencia




STUDENT

Paula Cort Azcárraga

SCALE

1/10

DATE



FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 2

PLANE N° :





UNIVERSIDAD Politecnica de Valencia




STUDENT

Paula Cort Azcárraga

SCALE

1 / 10

DATE



FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 3

PLANE N° :

8



UNIVERSIDAD Politecnica de Valencia




STUDENT

Paula Cort Azcárraga

SCALE

1/10

DATE



FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 4

PLANE N° :

9



UNIVERSIDAD Politecnica de Valencia




STUDENT

Paula Cort Azcárraga

SCALE

1/10

DATE



FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 5

PLANE N° :

10



UNIVERSIDAD POLITECNICA DE VALENCIA




STUDENT

Paula Cort Azcárraga

SCALE

1/10

DATE



FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 6

PLANE N° :

11



UNIVERSIDAD Politecnica de Valencia




STUDENT

Paula Cort Azcárraga

SCALE

1 / 10

DATE



Carpet 1cm Raised floor 12 cm Raised floor support Hollow core slab 40+5 cm

STUDY and CONSTRUCTIVE ANALYSIS of an OFFICE BUILDING located in Ghent

FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 7

PLANE N° :

12



UNIVERSIDAD Politecnica de Valencia




STUDENT

Paula Cort Azcárraga

SCALE

1/10

DATE



Flameproof insulation 5 cm Concrete ramp. < 4 cm Hollow core slab 40+5 cm

STUDY and CONSTRUCTIVE ANALYSIS of an OFFICE BUILDING located in Ghent

FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 8

PLANE N° :

13



UNIVERSIDAD Politecnica de Valencia




STUDENT

Paula Cort Azcárraga

SCALE

1/10

DATE



FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 9

PLANE N° :

14



UNIVERSIDAD Politecnica de Valencia




STUDENT


Paula Cort Azcárraga

SCALE

1/10

DATE





FINAL BACHELOR PROJECT

DESCRIPTION

PART 3 Detailed drawings

DETAIL 10

PLANE N° :

15



UNIVERSIDAD Politecnica de Valencia



STUDENT

Paula Cort Azcárraga

SCALE

1 / 10

DATE

Part 4.

Technical study

1 PRECAST STAIRS

The prefabricated concrete stairs are custom manufactured for each project.


Prefabricated stairs can be designed to adapt at the structural, dimensional and esthetics characteristics, for each type of building.

In this way, it possible to reduce the problems that affects with the time and the cost.

2 INSTALLATION AND NECESSARY EQUIPMENTS

Indications to install precast elements:

- 1. Location plan
- 2. Structural plan
- 3. Ground plan, sections and levels.
- 4. Relationship and specifications for precast



Also, must to know:

- To analyze the characteristics and peculiarities of work.
- To know all spaces and facilities available.
- Check the access, maneuvering areas and slopes.

Choose the correct crane and equipment, it's the most important thing, so it is decisive for the good ending work.

Should be analyzed, height, weight, dimensions, etc.. For this work will be use a Tower Crane: LIEBHERR, 180 E-CH-10. (More information in plane 2)



To transport:


In general, precast elements, small and slightly weighed, as the stairs, are move with very basic equipment: conventional truck, trailer...



Should be avoid restock the material at the work, so there are actions than increase the total cost and complicate the ejecution.


To acces:

Supply of the precast elements must be continuous and safe, for that reason, ways and access must be positioned parallel to the stock area.



The auxiliary resources more common in the lifting to mounting prefabricated elements, are:

- 1. Lifting hook
- 2. Pins
- 3. Stirrup
- 4. Brands and steel wire



To install:

Should not beginning to do the mounting without these conditions:

- a) Concrete must have enough resistance.
- b) Prepare all areas necessary for ease of assembly
- c) Ensure a supply of items, continuous and completely to prevent the execution stops for lack of precast.
- d) Check the features and suitability of auxiliary resources and equipment so as to ensure maximum safety of assembly.

2.1 Assembly sequence:

Assembly should be do, when be possible, for levels, avoiding crane movements.

Will be a good view between laborers at stockpiles and collocation area.

When the sight is not possible, a code will be established among laborers.

Stockpile prefabricated elements it is recommended to do inside the building, when the building only have one level, and outside the building, when this have more levels. For this way is easier not disrupting at others activities.

3 ADVANTAGES AND DISADVANTAGES

Advantages

Easy to install: It is not necessary use formwork.

<u>Stockpiles:</u> Stairs normally come from the factory to truck and are placed directly from this.

<u>Quick access:</u> Instant access between levels, increasing efficiency and security.

<u>Cost reduction:</u> Because is faster to install, need less laborer and without formwork.

Maintenance: Low maintenance cost


<u>Quality:</u> Stairs with industrial quality. The surfaces have a high quality finish.

Disadvantages


The only disadvantage is the cost. Prefabricated elements are designed specifically for this work and are industrial build so always is necessary to move them until the work. So these reasons can be increase the total cost, but in almost occasions, these costs are counteracted with others, and is better choose precast


4 CONSTRUCTION METHOD: STEP BY STEP

Bachelor final Project. Paula Cort Azcárraga Kaho Sint-Lieven; Universidad Politécnica de Valencia









1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 -

STUDY and CONSTRUCTIVE ANALYSIS of an OFFICE BUILDING located in Ghent

FINAL BACHELOR PROJECT

DESCRIPTION

PART 4

Technical study.

Details about precast stairs

PLANE N° :

18



UNIVERSIDAD POLITECNICA DE VALENCIA



KAHO Sint-Lieven

STUDENT

Paula Cort Azcárraga

SCALE

1 / 70

DATE


Part 5.

Comparative study

The topic chosen for comparative study is the different between two ways to build a very interesting element at the work: the cantilever.

It proposes a new way to build, comparing time, cost and performance.

When the architect designed this structure, he thought to move the first floor 5 metres to the right. And became these level a very diaphanous place, to get more light, space and, of course, beauty.



The purpose is to change the mechanical anchorage by a spatial structure. It work as a single structure, also reduced material and cost, increasing the strength and safety.

Now, beams are put with the floor through steel sheet. It are anchored with screw and the beams are welded at sheets. Thus, the welding is working perpendicular at the floor direction, a really dangerous situation. Because the direction about the welding must be the same at its work.

To improve this situation could add a metal plate over the existing ones. welding them to these, so that for welding this in the same direction as the work.

The new construction is to replace every HEB 180, place from 70 cm, by HEB 240.

Just 5 beams this time, combined with another diagonal beam, which will be anchored to the upper beam is placed. Created a work triangle.

COMPARATIVE STUDY

				SPAT	ĪAL				
MATERIAL AND EQUIPMENT	21 HEB 4 IPE 18 21 HEA 2 HEA	80 \ 140	Crane Lifting platfor	EQUIPMENT			Rel Stru Ce 15 5 S 8 H (1x 8 H		Cro Lift Tru Cc
SCHEDULLING AND PRICING	№º 1.01 1.02 1.03 1.04 1.05 	MATER HEB 180 (kg) IPE 180 (kg) HEA 140 (kg) HEA 140 (kg) Steel hollow		QUANTITY 3978,24 6,64 2968,98 49,4 72	UNIT PRICE 1,67€ 1,66 1,71 1,71 1,64	11,02 € 5.076,96 € 84,47 €	№ 2.01 2.02 2.03 2.04	MATERIALS HEB 240 (kg) Steel hollow profile (Ceramic block Floor hollow core sla concrete + rebar	ab +
PROS AND CONS	PROS: - Less tir CONS: - Dange	me of ejecution erous structure repairs	PROS - Save s - Increa - The str CONS:	teel profiles sed security ucture works better ime of ejecution					
CONCLUSION		-		price or time to execute nd a most security optior					


STRUCTURE

EQUIPMENT

rane fting platform uck mixer oncrete cupola

QUANTITY	UNIT PRICE	TOTAL PRICE
4534,4	1,67	7.572,45€
142,35	1,81	257,65€
200	0,1	20,00€
57,72	62,35	3.598,84€
<u>.</u>		11.448,94

t, studying the structure, how it works, and



STUDY and CONSTRUCTIVE ANALYSIS of an OFFICE BUILDING located in Ghent

FINAL BACHELOR PROJECT

DESCRIPTION

PART 5

Comparative study.

New construction for the cantilever. Spatial structure

PLANE N° :

18



UNIVERSIDAD POLITECNICA DE VALENCIA




STUDENT

Paula Cort Azcárraga

SCALE

1 / 20

DATE



The metal structure soars with crane. Another laborer, placed on the lifting platform, guide the structure and fixed.

Then, still on the platform placed end profiles

STUDY and CONSTRUCTIVE ANALYSIS of an **OFFICE BUILDING** located in Ghent

FINAL BACHELOR PROJECT

DESCRIPTION

PART 5

Comparative study.

STEP BY STEP Spatial structure

PLANE N° :

19



UNIVERSIDAD POLITECNICA DE VALENCIA



KAHO Sint-Lieven


STUDENT

Paula Cort Azcárraga

SCALE


1 / 50

DATE



Put wooden boards on the steel profile, on them, the operator can move and place the hollow core. It shall be protected with a lifeline

When they are placed all hollow core slabs, the slab is concreted



FINAL BACHELOR PROJECT

DESCRIPTION

PART 5

Comparative study.

STEP BY STEP Spatial structure

PLANE N° :

20



UNIVERSIDAD POLITECNICA DE VALENCIA



KAHO Sint-Lieven


STUDENT


Paula Cort Azcárraga

SCALE

1 / 50

DATE





With the same procedure, the operator places the window

Raised floor, and ceilings.

STUDY and CONSTRUCTIVE ANALYSIS of an **OFFICE BUILDING** located in Ghent

FINAL BACHELOR PROJECT

DESCRIPTION

PART 5

Comparative study.

STEP BY STEP Spatial structure

PLANE N° :

21



UNIVERSIDAD POLITECNICA DE VALENCIA



KAHO Sint-Lieven


STUDENT

Paula Cort Azcárraga

SCALE

1 / 50

DATE



After, the laborer finish the roof.

All structure are finish

STUDY and CONSTRUCTIVE ANALYSIS of an OFFICE BUILDING located in Ghent

FINAL BACHELOR PROJECT

DESCRIPTION

PART 5 Comparative study

> STEP BY STEP Spatial structure

PLANE N° :

22



UNIVERSIDAD POLITECNICA DE VALENCIA




STUDENT

Paula Cort Azcárraga

SCALE

1 / 50


DATE



Part 6.

Scheduling and pricing

D	0	Task Name	Duration	Start	Finish	r '13 F	08 Jul '13 S	3 23 S S M	Sep '13 т	09 Dec '13 W T	24 Feb '14 F S		May '14 M
1	-	OFFICE BUILDING	375 days	Mon 05/08/13	Fri 09/01/15	F	<u> </u>	ט iVi		vv I	г 5	<u>з</u>	
2		START	0 days	Mon 05/08/13			•	05/08					
3		1 Implanting	7 days	Mon 12/08/13									
4		1.1 Cleaning surface	1 day	Mon 12/08/13		-	,						
5		1.2 Fenced and signaling	0,5 days	Tue 13/08/13				Б					
6			0,5 days	Tue 13/08/13				h h					
7		1.4 Placement of temporary facilities in site huts	0,5 days		Wed 14/08/13	-		к Г					
8		1.5 Electrical, plumbling and sanitation installation of the site huts	0,5 days	Wed	Wed 14/08/13			ĥ					
9		1.6 Placement of the crane	4 days	Thu 15/08/13	Tue 20/08/13								
10		2 Earthwork	34 days	Wed 21/08/13		-			J				
11		2.1 Installation of temporary	2 days		Tue 27/08/13	-		*					
		retaining wall	,	26/08/13									
12		2.2 Dig to -2m	2 days	Wed 28/08/13	Thu 29/08/13			Б,					
13		2.3 Drainage installation	2 days	Fri 30/08/13	Mon 02/09/13	3		T					
14		2.4 Installing dewatering pumps	4 days	Tue 03/09/13	Fri 06/09/13			T					
15		2.5 Dig to -4m	4 days	Wed 02/10/13	Mon 07/10/13	3		_	ו				
16		2.6 Dig elevator pit	2 days	Mon 09/09/13	Tue 10/09/13			T I					
17		3 Framework	25 days	Wed 11/09/13	Tue 15/10/13								
18		3.1 Temporary foundation with rocks approx 50cm thickness	3 days	Wed 11/09/13	Fri 13/09/13								
19		3.2 Installing 115 poles to -2m	12 days	Mon 16/09/13	Tue 01/10/13								
20		3.3 Cut piles to break free the rebar that's inside. Sonar test	2 days	Tue 08/10/13	Wed 09/10/13	-		ì					
21		3.4 Ground leveling in the pits, foundation plate + walls	1 day	Thu 10/10/13	Thu 10/10/13								
22		3.5 Foundation plate building	3 days	Fri 11/10/13	Tue 15/10/13				۲, The second				
23		4 Basement	32 days	Wed 16/10/13	Thu 28/11/13								
24		 4.1 Formwork slab + rebar + sewage pipes + concrete found slab + formwork panels 	6 days		Wed 23/10/13								
25		4.2 Final plans basement walls, columns and cover	9 days	Thu 24/10/13	Tue 05/11/13								
26		4.3 Foundation walls	11 days	Wed 06/11/13	Wed 20/11/13	2				1			
27	İ	4.4 Place the scaffold	1 day	Thu 21/11/13	Thu 21/11/13					Laborer			
28	ŧ	4.5 Brickwork facade BASEMENT	2 days	Fri 22/11/13	Mon 25/11/13					Brickwork[1 kg];Scaffold;Façade r	nortar[1 m	n3];Labore
29	ŧ	4.6 Interior walls of concrete	3 days	Thu 21/11/13	Mon 25/11/13	2				ĕ _			
30		4.7 Prefabricated beams	2 days	Tue 26/11/13	Wed 27/11/13					5			
31		4.8 Prefabricated stairs	1 day	Thu 28/11/13	Thu 28/11/13	~				ĥ			
32		5 Ground Floor	14 days	Fri 29/11/13	Wed 18/12/1								
		Task		Group By	y Summary			xternal Milesto	ne	<u></u>	Duration-only		
		Split					Ir	nactive Task	p		Manual Summary	Rollun 💻	
Projec	t: GANT	OBRA			•	~			no -		-	-	
	Fri 13/0		▼		p Milestone	\diamond		nactive Milesto		×	Manual Summary	_	
-		Summary		Rolled U	p Progress		lr	nactive Summa	ry 🦷	$\overline{}$	Start-only	Ľ	
											-		
		Project Summary		External			N	/lanual Task	Ĩ]	Finish-only	2	




D	6	Task Name	Duration	Start	Finish	r '13 F	08 Ju S	l '13 S	23 Sep '13 M T	09 Dec W T	с '13 т	24 Feb '14 F S S	12 May M	<u>''14</u>	28 Jul '14 W T	13 Oct '14	4 29 De S S	ec '14 M
33	<u> </u>	5.1 Concrete and prefabricated walls	7 days	Fri 29/11/13	Mon 09/12/1		3	 	IVI		I	<u> </u>	IVI		vv I			
34	ŧ	5.2 Place the scaffold	, 1 day		Tue 10/12/13	-				Laboi	rer							
35		5.3 Brickwork facade GF	3 days	Wed 11/12/1	Fri 13/12/13					Scaff	fold;Bric	kwork[1 kg];Façade	mortar[1 m	3]				
36	ŧ	5.4 Prefabricated stairs + platforms stabbing	1 day	Tue 10/12/13	Tue 10/12/13	-				Ť								
37		5.5 Cover GF	4 days	Wed 11/12/1	Mon 16/12/13	3				i								
38		5.6 Electrical installation, plumbing and sanitation	2 days	Tue 17/12/13	Wed 18/12/13													
39		6 First Floor	15 days	Thu 19/12/13	Wed 08/01/1	(
40		6.1 Final reinforcement plans and cover	2 days	Thu 19/12/13	Fri 20/12/13					ľ								
41	ŧ	6.2 Concrete and prefabricated walls	7 days	Mon 23/12/1	Tue 31/12/13					1	ŋ							
42	ŧ	6.3 Prefabricated stairs + platforms	t 1 day	Mon 23/12/1	Mon 23/12/1	3				Ĭ -Ţo	ower cra	ne;Machine operato	or;Laborer;P	refabricate	d stairs[1 m2]			
43		6.4 Cover F1	4 days	Wed 01/01/1	4 Mon 06/01/14	1												
44		6.5 Electrical installation, plumbing and sanitation	2 days	Tue 07/01/14	Wed 08/01/14													
45 46		7 Second Floor 7.1 Final reinforcement plans and cover	15 days 2 days	Thu 09/01/14 Thu 09/01/14	Wed 29/01/1 Fri 10/01/14					ţ								
47	ŧ	7.2 Concrete and prefabricated walls	7 days	Mon 13/01/1	4Tue 21/01/14													
48	ŧ	7.3 Place the scaffold	1 day	Wed 22/01/1	4Wed 22/01/14	1						borer						
49	ŧ	7.4 Brickwork facade 2F	3 days	Thu 23/01/14	Mon 27/01/14	1						rickwork[1 kg];Scaf						
50	•	7.5 Prefabricated stairs + platforms	t 1 day	Mon 13/01/1	4Mon 13/01/14	1					Towe	er crane;Machine or	perator;Labo	orer;Prefabr	icated stairs[1 r	n2]		
51	Ť	7.6 Cover F2	4 days	Wed 22/01/1	4Mon 27/01/14	1												
52		7.7 Electrical installation, plumbing	2 days	Tue 28/01/14							ĥ							
		and sanitation			29/01/14	-												
53		8 Third Floor	15 days		Wed 19/02/1	<u> </u>												
54		8.1 Final reinforcement plans and cover	2 days	Thu 30/01/14		_												
55	!	8.2 Concrete and prefabricated walls	-		4Tue 11/02/14	-					Í	.						
56	!	8.3 Place the scaffold	1 day		4Wed 12/02/14	-						Laborer						
57	•	8.4 Brickwork facade 3F	3 days		Mon 17/02/14	-					↓	Brickwork[1 kg]						
58	!	8.5 Prefabricated stairs + platforms	-		4Mon 03/02/14	-					F	Tower crane;Machi	ine operato	;Laborer;Pr	efabricated stai	irs[1 m2]		
59	•	8.6 Cover 3F	4 days		4Mon 17/02/14	1												
60		8.7 Electrical installation, plumbing and sanitation	2 days	Tue 18/02/14	19/02/14	-												
61		9. Roof	25 days		Wed 26/03/1	2												
62		9.1 Formwork cover	2 days	Thu 20/02/14								\						
63 64		9.2 Eaves bricklaying 9.3 Prefabricated architectural	3 days 6 days		4Wed 26/02/14 Thu 06/03/14	-												
		concrete				-						\downarrow						
65		9.4 Waterproofing and tests	4 days		Wed 12/03/14	-												
66		9.5 Finishing cover	10 days	Thu 13/03/14	Wed 26/03/14	1												
		Task		Group B	y Summary	-		Externa	al Milestone	\$	[Duration-only			Deadline	۵		
		Split		Rolled L	Ip Task			Inactive	e Task			Manual Summary Ro	llup		Critical			1
-		TOBRA Milestone	•	Rolled L	Ip Milestone	\diamond		Inactive	e Milestone	\diamond	ſ	Manual Summary			Critical Split			
vate: I	Fri 13/0	56/14 Summary	_		Ip Progress)		e Summary	∇		Start-only	C		Progress			
		Project Summary	-	Externa				Manua	•	C		Finish-only	2		0			
		1						Pag										

D 🚺	Task Name	Duration	Start	Finish	r '13 F	lut 80			ер '13 т	09 09	Dec '13	F	24 Feb '14	·
67	10 Projection structure	9 days	Thu 27/03/14	1 Tue 08/04/14	· · ·	S	S	M	I	VV	I	F	S	S
68	10.1 Support steel beams, anchoring to concrete	-		Fri 28/03/14									Ť	
69	10.2 Envolvent glass	4 days	Mon 31/03/1	4Thu 03/04/14										
70	10.3 Installations	3 days	Fri 04/04/14	Tue 08/04/14										
71	11 Remove Crane	1 day	Wed 09/04/1	4Wed 09/04/14	l									ĥ
72	12 Interior finish	185 days	Thu 10/04/14	4 Wed 24/12/14									,	-
73	12.1 Remove scaffol	1 day	Thu 10/04/14	Thu 10/04/14										Б
74	12.2 Suspended ceilings	7 days	Fri 11/04/14	Mon 21/04/14	1									Δ.
75	12.3 Raised floors	12 days	Tue 22/04/14	Wed 07/05/14	1									
76	12.4 Installation of air conditioning	15 days	Thu 08/05/14	Wed 28/05/14	1									
77	12.5 Air tightness test	6 days	Thu 29/05/14	Thu 05/06/14										
78	12.6 Insulation	15 days	Fri 06/06/14	Thu 26/06/14										
79	12.7 Carpentry	25 days	Fri 27/06/14	Thu 31/07/14										
80	12.8 Fixed partitions	20 days	Fri 01/08/14	Thu 28/08/14										
81	12.9 Pavement stairs and rug	20 days	Fri 29/08/14	Thu 25/09/14										
82	12.10 Carpet	20 days	Fri 26/09/14	Thu 23/10/14										
83	12.11 Paint	20 days	Fri 24/10/14	Thu 20/11/14										
84	12.12 Furniture	20 days	Fri 21/11/14	Thu 18/12/14										
85	12.13 Cleaning	4 days	Fri 19/12/14	Wed 24/12/14	l									
86	13 Environment construction	10 days	Mon 29/12/1	4Fri 09/01/15	-									
87	13.1 Outdoor railings and mailboxes	2 days	Mon 29/12/1	4Tue 30/12/14										
88	13.2 Outdoor construction, outside	6 days	Wed	Wed										
	pavement and street furniture		31/12/14	07/01/15										
89	13.3 Remove site huts	0,5 days		5 Thu 08/01/15										
90	13.4 Remove temporary installations	0,5 days	Thu 08/01/15	5 Thu 08/01/15										
91	13.5 Remove fenced	0,5 days	Fri 09/01/15	Fri 09/01/15										
92	13.6 Cleaning	0,5 days	Fri 09/01/15	Fri 09/01/15										
93	END	0 days	Fri 09/01/15	Fri 09/01/15										

Project: GANT OBRA Date: Fri 13/06/14

Task		Group By Summary	— ——	External Milestone		Duration-only	
Split		Rolled Up Task		Inactive Task		Manual Summary Rollup	
Milestone	♦	Rolled Up Milestone	\diamond	Inactive Milestone	\diamond	Manual Summary	-
Summary	~	Rolled Up Progress		Inactive Summary	$\bigtriangledown \qquad \bigtriangledown$	Start-only	Ľ
Project Summary	$\overline{}$	External Tasks		Manual Task	C 3	Finish-only	
				Page 3			



Some photos of the current state of the work:









Bachelor final Project. Paula Cort Azcárraga Kaho Sint-Lieven; Universidad Politécnica de Valencia





Bachelor final Project. Paula Cort Azcárraga Kaho Sint-Lieven; Universidad Politécnica de Valencia