

Bachelor Final Project

Study and Constructive Analysis of Deinze's New City Hall





Autor: Luis Latorre Zaplana

Academic tutor at UPV: María José Vidal Lucas

Academic tutor at Odisee: David Peters

2015

INDEX

- Personal introduction
- Introduction to project
- Part 1. Organisation of the building site
- > Part 2. General section of the building 1/50
- > Part 3. Details 1/10
- Part 4. Technical study
- Part 5. Comparative study
- Part 6. Scheduling. Gantt chart
- Pictures taken in the site
- Bibliography



PERSONAL INTRODUCTION

Hello, my name is Luis Latorre Zaplana, I'm 23 years old, I live in Puerto de Sagunto (Valencia) and I'm student of the last course in Degree in Technical Architecture at the "Universitat Politècnica de València" (UPV).

I decided to study technical architecture because since my childhood I've been influenced by my parents who are both technical architects and are currently in the profession. I had access to many working places with my father at an early age and that's what sparked my interest in building.



I'm currently in Belgium enjoying an Erasmus scholarship of 5 months (from early February to late June) for my FP and various subjects but while I'm taking the opportunity to improve my English and I have obtained a certificate of Dutch (basic level).

While performing my FP, I realized how different the construction of Belgium regarding Spain. The great importance given to thermal insulation of buildings, greater use of precast concrete or building of no more than 3 floors are some of the main differences I have observed.

Thanks to the aid of Mr.David Peters (my Odisee tutor) and Mr.Filip Vertongen and Mr.Mario Bourgois (project leader and construction leader of the construction from the company Strabag) with numerous corrections and explanations, I have been able to understand 100% the execution and organization of the building and to develop my FP successfully.

To sum up, I advise all students of technical architecture of the UPV to perform their TFG here because the construction is booming right now in Belgium and we have much to learn from them.



INTRODUCTION TO PROJECT

As for my TFG, which is discussed below, is the study and constructive analysis of the new city hall of the town of Deinze. The work involves (as seen in the index) in developing a organization plan of the work, the preparation of a general section, the development of construction details of the building, a technical study *step by step* of a concrete subject of the building, a comparative study of two different types of construction, scheduling tasks represented in a Gantt chart, bibliography and photos.

The city hall of Deinze, is a set of two buildings, a larger main building which is the town hall, a community building and a service center (included the services of OCMW) and a smaller building with a board room and wedding room for the community.

Architecturally, the main building has a rectangular ground and section and it's a 5-storey building and 1 basement common to both buildings, two modules ladder, one with 2 elevators and the other with one, a corridor connecting the two buildings by ground and first floors and installation cabins in the fifth floor. It has several entrances through the basement and the ground floor but the main entrance is in the small building. The facade is modular on the pillars and glazing.

Constructively, the main building consists of foundation slab and concrete piles, perimeter containment walls of *mixed soil* and concrete walls in the basement, brickwork and concrete block partitions, *in situ* and precast concrete columns and beams, composite slabs, precast concrete platforms and prefabricated concrete walls filled with liquid concrete, PUR and PIR as the main insulation, floor and ceiling technical, prefabricated stairs, glass facade with aluminium carpentry and natural stone facing, flat and accessible roof.

Architecturally, the small building has a rectangular ground and section and it's a 2-storey building and 1 basement common to both buildings, and a module ground floor staircase to first. It has two main entrances with revolving door. The facade is modular on the pillars and glazing.


Constructively, the small building consists of foundation slab and concrete piles, perimeter containment walls of *mixed soil* and concrete walls in the basement, brickwork and concrete block partitions, *in situ* and precast concrete columns and beams, composite slabs, precast concrete platforms, metal containment structure housing, PUR and PIR as the main insulation, floor and ceiling technical, prefabricated stairs, glass facade with aluminium carpentry natural stone facing, flat and vegetal roof.



PART 1. ORGANISATION OF THE BUILDING SITE



ORGANISATION OF THE BUILDING SITE



LEGEND


BUILDING EMPLACEMENT LOADING ZONE STORAGE (steel and precasts) STORAGE (rest) ELECTRIC METER WATER METER WATER SUPPLYING POINTS LIGHT BEACON (each 10m, entrances and corners) ELECTRICAL INSTALLATION WATER INSTALLATION FENCED (2m) FENCED (1m)		
STORAGE (steel and precasts) STORAGE (rest) ELECTRIC METER WATER METER WATER SUPPLYING POINTS LIGHT BEACON (each 10m, entrances and corners) ELECTRICAL INSTALLATION WATER INSTALLATION FENCED (2m)	BUILDING EMPLACEMENT	
STORAGE (rest)ELECTRIC METERWATER METERWATER SUPPLYING POINTSLIGHT BEACON (each 10m, entrances and corners)ELECTRICAL INSTALLATIONWATER INSTALLATIONFENCED (2m)	LOADING ZONE	
ELECTRIC METER WATER METER WATER SUPPLYING POINTS LIGHT BEACON (each 10m, entrances and corners) ELECTRICAL INSTALLATION WATER INSTALLATION FENCED (2m)	STORAGE (steel and precasts)	
WATER METER WATER SUPPLYING POINTS LIGHT BEACON (each 10m, entrances and corners) ELECTRICAL INSTALLATION WATER INSTALLATION FENCED (2m)	STORAGE (rest)	
WATER SUPPLYING POINTS	ELECTRIC METER	
LIGHT BEACON (each 10m, entrances and corners) ELECTRICAL INSTALLATION WATER INSTALLATION FENCED (2m)	WATER METER	
and corners) ELECTRICAL INSTALLATION WATER INSTALLATION FENCED (2m)	WATER SUPPLYING POINTS	\bigcirc
WATER INSTALLATION FENCED (2m)		nces 😑
FENCED (2m)	ELECTRICAL INSTALLATION	
	WATER INSTALLATION	
FENCED (1m)	FENCED (2m)	00
	FENCED (1m)	


USEFUL TELEPHONE NUMBERS


- European SOS: 112 - Deinze hospital Sint-Vincentiusziekenhuis (Schutterijstraat 34): 09/387 71 11 - Deinze fire department (Stadionlaan 24): 09/381 81 11 - Deinze police station (Stadionlaan 22): 09/381 41 00


SIGNALING OF THE CONSTRUCTION SITE













MAP OF THE LOCATION

ACCES FROM E-17




DATA SHEET OF THE CRANE TOWER



PART 2. GENERAL SECTION OF THE BUILDING (1:50)



		-Plaster coat -Brickwork (29x -PIR insulation -Polyethylene m -Concrete wall -HEA 200 (8m l -Mixed soil 55cr	5cm nembrane 1cm "in situ" 30cm long)every 1m	15,73	-Skirting 5cm -Polished concrete -PIR insulation 15ct -Polyethylene mem -Foundation slab 50 -Pile cap -Cleaning concrete -Soil
					A 21 A
PIR and	d PUR insulation		XPS		
Rockwo	ool insulation		Lightweight concrete		
Precast	concrete		Hidden elements		
"In situ"	concrete		Projections		
Cleaning	g concrete		Soil LEGEND		
	Rockwa Precast		Rockwool insulation Precast concrete "In situ" concrete	Rockwool insulation Lightweight concrete Precast concrete Hidden elements "In situ" concrete Projections Cleaning concrete Soil	Rockwool insulation Precast concrete In situ" concrete Cleaning concrete



-Cleaning concrete 10cm -Soil


FINAL BACHELOR PROJECT: STUDY AND CONSTRUCTIVE ANALYSIS OF DEINZE'S NEW CITY HALL


DRAWING: General section of the building STUDENT: LUIS LATORRE ZAPLANA SCALE: 1/50 PLANE No. 2

DATE: 17/06/2015

PART 3. DETAILS (1:10)










FINAL BACHELOR PROJECT: S DEINZE'S NEW CITY HALL
DRAWING: Detail 1
STUDENT: LUIS LATORRE ZAPLANA
PLANE No. 3







SCALE: 1/10
DATE: 17/06/2015






FINAL BACHELOR PROJECT: STUDY DEINZE'S NEW CITY HALL	AND CONSTRUCTIVE ANALYSIS OF
DRAWING: Detail 3	
STUDENT: LUIS LATORRE ZAPLANA	SCALE: 1/10
PLANE No. 5	DATE: 17/06/2015






FINAL BACHELOR PROJECT: S DEINZE'S NEW CITY HALL
DRAWING: Detail 4
STUDENT: LUIS LATORRE ZAPLANA
PLANE No. 6










	NAL BACHELOR PROJECT: ST EINZE'S NEW CITY HALL
DF	RAWING: Detail 5
ST	UDENT: LUIS LATORRE ZAPLANA
PL	ANE No.7


STUDY AND CONSTRUCTIVE ANALYSIS OF ESCUELA TÉCNICA SUPERIOR UNIVERSITAT POLITÈCNICA DE VALÈNCIA $\langle \hat{A} \rangle$ **STRABAG** SCALE: 1/10 DATE: 17/06/2015






FINAL BACHELOR PROJECT: STUDY DEINZE'S NEW CITY HALL	AND CONSTRUCTIVE ANALYSIS OF
DRAWING: Detail 6	
STUDENT: LUIS LATORRE ZAPLANA	SCALE: 1/10
PLANE No. 8	DATE: 17/06/2015









PART 4. TECHNICAL STUDY







1) Firstly, the entire space of the plot is backfilled with crushed stones to a height of 50cm so that the machines can move, as the soil cannot bear much weight. With the aid of a backhoe a deep trench is executed (23m deep and 0,55m wide), adding liquid concrete at the same time, and it's mixed with the soil. That's called mixed soil. Before the concrete hardens, with the help of the tower crane, eight meters long steel profiles (HEA 200) are introduced every single meter as a reinforcement to the mixed soil wall and they serve as union of the set.




4) Coming up next, a 50cm deep **foundation slab** is made, placing on the future joint with the inside wall a metallic element (Plaka Nederland) to prevent water from passing into the building.



7 & 8) To isolate internally the building there's one step left: the addition of the insulating elements. A polyethylene membrane and PIR insulation panels (IKO Enetherm) are placed both vertically and horizontally. Besides, two rows of **concrete blocks** are placed as a base for a **brickwork**, and in the joint between them there is dpc (**damp proof course**) to prevent intrusion of soil moisture. The floor is ended with a layer of polished concrete and with an aluminium skirting.




2) Secondly, when the concrete has already hardened and with the aid of a regular backhoe, it's made a first excavation of approximately 2m deep. Then, a hydraulic drilling makes separated holes at 45 degrees and insert steel bars or ground anchors inside them, in order to hold the mixed soil wall when the excavation goes on.





5) Once the foundation slab is done, the next step is the formworking, reinforcement and concrete **pouring** of the inside wall (30cm) and the coronation beam which is located above it. During the assembly of the formwork, several steel bars are inserted into the hard concrete to hold the formwork when the pouring of the concrete is being carried out.


Concrete wall "in situ" 30cm




-16.00m







6) After the inside wall and the mixed soil wall are made, it starts the execution of the first slab of the building which is made from 9cm precast concrete panels supported by the inside wall and a 15cm layer of "in situ" concrete laid over the panels. To execute the 1st slab, the concrete is poured so that the coronation beam is completely filled, and the slab as well.





3) After that, a second 2m deep excavation is made reaching the level +3'00 according to the **implementation project**. A longitudinal groove is made at the lower part of the M.S. wall that keeps visible, to introduce the future reinforcement in.


FINAL BACHELOR PROJECT: STUDY DEINZE'S NEW CITY HALL	AND CONSTRUCTIVE ANALYSIS OF UNIVERSITAT POLITÈCNICA DE VALÈNCIA
DRAWING: Step by step - Retaining walls	
STUDENT: LUIS LATORRE ZAPLANA	SCALE: 1/50
PLANE No. 10	DATE: 17/06/2015

PART 5. COMPARATIVE STUDY











Holes in the columns to pour the concrete



Precast columns and platforms

1) Firstly, the precast column is laied on the ground.

2) Then, a worker attaches a double leg sling from the tower crane to a front groove of the precast column.

2) The operator of the tower crane starts incorporating the column, following the instructions of the operator. This step is necessari because the column wouldn't be able to hold its own weight if it were lifted up for the top and it'd split in the middle part.


3,4,5,6) When the column has been incorporated, the operator attaches the double leg sling to the other groove on the top and the crane operator place the column above a precast element. Every column has four waiting bars on the top to be nailed with the precastplatform and the colum of the next floor. When the column is placed, with the aid of a concrete pump, the operator pours liquid concrete in the holes where the bars have been nailed and here's how column-platform-column get fixed together.




Waiting bars



DEINZE'S NEW CITY HALL DRAWING: Implementation of a precast column STUDENT: LUIS LATORRE ZAPLANA PLANE No. 12








n situ concrete column in the basement

 \triangleleft

Δ

4





Column-beam union

/ · ·	/\ /\	 · · · /	
		<u>_</u>	
		<u>adar da da compo</u>	

 \triangleleft

Λ

 \triangleleft

. . Д.,


. *Δ*

FINAL BACHELOR PROJECT: STUDY AND CONSTRUCTIVE ANALYSIS OF DEINZE'S NEW CITY HALL Image: Constructive Analysis of Ingenier (A action of the constructive Analysis of Deinze's New City Hall DRAWING: "In situ" concrete column Student: Luis Latorre Zaplana Scale: 1/20 PLANE No. 13 DATE: 17/06/2015

600

. I

Δ




1) When the workers execute the foundation slab, they put four waiting bars for the future column.

2) Once the slab has hardened the steelfixers place the reinforcement of the column and fix it to the wainting bars. After that, the workers put some rings pacers


before assembling the formwork.

3) Then, with the aid of a scaffolding, the workers assemble the whole formwork of the column. Coming up next, one of the workers pours the concrete with a concrete pump from the top of the scaffold and vibrates it to avoid segregation.

FINAL BACHELOR PROJEC DEINZE'S NEW CITY HALI
DRAWING: Implementation of
STUDENT: LUIS LATORRE ZAPL
PLANE No. 14



4) Finally, they remove the formwork from top to bottom and after that the scaffold. The bars of the column will be showed on the top to fix the column to a future concrete beam.



	"In situ"	column	Precast column		
Material and equipment	Material: -Structural concrete -Metal bars -Spacers -Wire	Equipment: -Tower crane -Truck mixer -Vibrator -Formwork -Scaffold -Concrete pump -Plumb -Pliers -Hose (curing) -Slings	Material: -Precast column	Equipment: -Tower crane -Concrete pump -Slings	
Pricing (1 column)	"In situ" column (1column-0,389m³) Buy concrete (€/m³) Pouring concrete+reinforcement(€/m³) Transport concrete(€/m³) Renting formwork (€/m²) Transport formwork (€/kg) Placing formwork(€/m²) Buy metal bars (incl.transp) (€/kg) *Dimensions of the in situ column: 0,5x0,5x4,33	UnitsUnit priceTotal1,08m³58 (\notin /m³)62,641,08m³30 (\notin /m³)32,41,08m³18,2(\notin /m³)19,6568,66m²10(\notin /m²)86,6260kg0,01(\notin /kg)2,62,60m²25(\notin /m²)6586,40kg0,55(\notin /kg)47,52 Σ =316,416m=1,08m³ / =8,66m²	Pecast column (1piece) Buy columns (€/piece) Transport (€/piece) Placing (€/piece) Fill holes (€/piece)	UnitsUnit price (€/u)Total1450450,00 €112,512,50 €1125125,00 €14545,00 €Σ=587,50 €	
Pros & Cons	Pros: -Rigidity of the system -Joints better solved -Adaptation to more complex forms -Great structural strength	Cons: -Necessary formwork -It depend on weather conditions -Large amount of waste generated -Timeout during setting and curing	Pros: -Construction industrialized -Geometric accuracy -Good quality tested and steady -Reductions in deadlines -Not necessary formworks -Great structural strength -Reduction of spenses for hours/man -No depend on weather conditions -Fairly accurate cost control -More ecological (minimize waste, energy) -Possibility of delivery in 24h -Unskilled labour to be an assembly line	Cons: -Troubles at the joints -Low stiffness to the horizontal forces (wind) -Collection, handling, transport and erection may affect structural strength -Availability of heavy equipment for handling and maneuvering space -It requires transport to work	
Conclusions	As shown in the pricing, purchase, transportation and placement of precast columns is more expensive than a concrete column made "in situ". However, the execution of prefabricated pillars is much faster and requires less manpower, therefore lowering costs. Being a construction in which 90% of the columns are prefabricated, this option is more viable respect of the "in situ" columns, in addition to difficulty that would be (in terms of formwork and form) doing that columns prefabricated.				

PART 6. SCHEDULING. GANTT CHART



		Duration	Start	Finish	11 October 21 March 01 September 11 February 21 July 01 January 11 June 23/09 09/12 24/02 12/05 28/07 13/10 29/12 16/03 01/06 17/08 02/11 18/01 04/04 20/06 05/02
1 Deinz	ze's new city hall	437,88 day	rs Mon 03/03/14	Thu 11/02/16	
2 STA	ART	0 days	Mon 03/03/14	Mon 03/03/14	• 03/03
3 1 lr	mplanting	5 days	Mon 03/03/14	Mon 10/03/14	
4 1	1.1 Fenced and signaling	1 day	Mon 03/03/14	Tue 04/03/14	Strabag labourer[2]
5 1	1.2 Cleaning surface	1 day	Tue 04/03/14	Wed 05/03/14	Strabag labourer[4]
	1.3 Electrical installation, plumbing,and sanitation of temporary facilities	2 days	Wed 05/03/14	Fri 07/03/14	Strabag labourer[4]
	1.4 Placement of temporary facilities in site huts	1 day	Fri 07/03/14	Mon 10/03/14	Strabag labourer[3,2];Crane truck[0,8]
		174 days	Mon 10/03/14	Mon 15/12/14	
9 2	2.1 Water pumping	200 days	Mon 10/03/14	Mon 15/12/14	Water pump machine
0 2	2.2 Crushed stones backfill	3 days	Mon 10/03/14	Thu 13/03/14	Loader;Road roller;Main construction labourers[10]
1 2	2.3 Tower crane installation	1 day	Thu 13/03/14	Fri 14/03/14	Crane truck;Main construction labourers[3];Tower crane installer[3]
2 2	2.4 Retaining walls (mixed soil)	23 days	Fri 14/03/14	Wed 16/04/14	Main construction labourers[10];Mixed soil backhoe;Tower crane
3 2	2.5 Digging Lv.1 (+5,30m)	7 days	Wed 16/04/14	Fri 25/04/14	Main construction labourers[10];Backhoe;Loader
4 2	2.6 Drilling ground anchors	8 days	Fri 25/04/14	Wed 07/05/14	Hydraulic drilling;Main construction labourers[10]
5 2	2.7 Digging Lv.2 (+3,00m)	15 days	Wed 07/05/14	Wed 28/05/14	Backhoe;Loader;Main construction labourers[10]
6 2	2.8 Digging lift pit	1 day	Wed 28/05/14	Thu 29/05/14	Backhoe;Main construction labourers[2]
3 F	oundation	72 days	Wed 28/05/14	Thu 02/10/14	
	3.1 Foundation piles(drilling, reinforcement	18 days	Wed 28/05/14	Mon 23/06/14	Rotary blasthole drills;Tower crane;Main construction labourers[7]
	and concreting) 3.2 Cleaning concrete 10cm	7 days	Wed 28/05/14	Fri 06/06/14	Main construction labourers[5];Concrete pump;Tower crane
0 3	3.3 Digging of the pile heads	4 days	Mon 30/06/14	Fri 04/07/14	Backhoe;Main construction labourers[5]
1 3	3.4 Breackage of the head of piles	5 days	Fri 04/07/14	Fri 11/07/14	Main construction labourers[5];Breacking hammer
2 3	3.5 Impedance test	1 day	Fri 11/07/14	Mon 04/08/14	
3 3	3.6 Pits and pipes	7 days	Fri 06/06/14	Wed 18/06/14	Main construction labourers[5]
4 3	3.7 Foundation slab 50cm	3 days	Mon 04/08/14	Thu 07/08/14	Main construction labourers[10];Tower crane;Concrete pump
5 3	3.8 Earth connection	1 day	Tue 05/08/14	Wed 06/08/14	Main construction labourers
	· · · · · · · · · · · · · · · · · · ·	15 days	Thu 14/08/14	Thu 04/09/14	Main construction labourers[10];Tower crane
7 3	walls) 3.10 "In situ" concrete retaining walls (insulation, reinforcement and concreting)	10 days	Thu 04/09/14	Thu 18/09/14	Main construction labourers[10];Tower crane;Concrete pump
	-	5 days	Thu 25/09/14	Thu 02/10/14	Main construction labourers[5];Tower crane;Concrete pump
	reinforcement and concreting) Basement	62 days	Thu 18/09/14	Wed 17/12/14	
	4.1 "In situ" columns (reinforcement, formwork and concreting)	8 days	Thu 18/09/14	Tue 30/09/14	Tower crane;Concrete pump;Main construction labourers[10];Scaffold[5]
	4.2 "In situ" concrete beams (formwork, reinforcement and concreting)	10 days	Tue 07/10/14	Tue 21/10/14	Main construction labourers[7];Tower crane;Concrete pump;Scaffold[5]
	4.3 Sm-"In situ" concrete columns (reinforcement, formwork and concreting)	2 days	Thu 18/09/14	Mon 22/09/14	Main construction labourers[2];Concrete pump;Tower crane;Scaffold[2]
3 4	4.4 Cavity walls (placing and concreting)	5 days	Tue 07/10/14	Tue 14/10/14	Main construction labourers[10];Concrete pump;Tower crane
	Task		Summary		Inactive Milestone A Duration-only Start-only C External Milestone A Critical Split
oject: Stral	bag Split		Project Summar	y 📕	Inactive Summary Manual Summary Rollup Finish-only Deadline Progress

	Milestone	•	Inactive Task		Manual Task		Manual Summary	Ext
Frojeci. Sirabay	Split		Project Summary	I1	Inactive Summary	0	Manual Summary Rollup	Fin
Project: Strabag	Task		Summary	—	Inactive Milestone	\diamond	Duration-only	Sta


ID Task	Name	Duration	Start	Finish	11 October 23/09 09/12	21 March 01 Septer 24/02 12/05 28/07	
34	4.5 Precast stairs	1 day	Tue 21/10/14	Wed 22/10/14	23/09 09/12	24/02 12/05 28/07	13/10 29/12 Main construction labourers[!
35	4.6 Concrete masonry	10 days	Tue 21/10/14	Tue 04/11/14			Main construction laboure
36	4.7 Brick work	10 days	Tue 21/10/14	Tue 04/11/14			Main construction laboure
37	4.8 Precast walls	12 days	Tue 04/11/14	Mon 24/11/14			Main construction labo
38	4.9 Septic 15.000L	1 day	Mon 24/11/14	Tue 25/11/14			Main construction labo
39	4.10 Acces ramp	7 days	Tue 25/11/14	Thu 04/12/14			Main construction la
40	4.11 Precast columns	1 day	Tue 04/11/14	Wed 05/11/14			Tower crane;Main construc
41	4.12 Placement of props	5 days	Thu 04/12/14	Thu 11/12/14			Main construction
42	4.13 Precast panels	3 days	Thu 11/12/14	Tue 16/12/14			Main construction
43	4.14 Precast platforms	2 days	Thu 11/12/14	Mon 15/12/14			Main construction
44	4.15 Universal beams (placement)	1 day	Tue 16/12/14	Wed 17/12/14			Main construction
45 5	Ground floor	22,88 days	Wed 17/12/14	Fri 30/01/15			r1
	5.1 Composite slab (reinforcement and concreting)	1 day	Wed 17/12/14	Thu 18/12/14			Tower crane;Conc
47		3 days	Wed 17/12/14	Mon 22/12/14			Main constructio
48	5,	11 days	Thu 25/12/14	Fri 09/01/15			Main constru
	0.	1 day	Mon 19/01/15	Mon 19/01/15			Main const
50	5.4 Precast columns	5 days	Mon 29/12/14	Mon 05/01/15			Main construc
51	5.5 Concrete masonry	10 days	Mon 05/01/15	Mon 19/01/15			Main const
52	5.6 Brickwork	10 days	Mon 05/01/15	Mon 19/01/15			Main const
53	5.7 Placement of props	5 days	Tue 20/01/15	Mon 26/01/15			Main con
54	5.8 Precast panels	3 days	Tue 27/01/15	Thu 29/01/15			Tower cr
55	5.9 Precast platforms	2 days	Tue 27/01/15	Wed 28/01/15			Main cor
56	5.10 Universal beams (placement)	1 day	Fri 30/01/15	Fri 30/01/15			Tower ci
57	5.12 Sm-"In situ" concrete columns (reinforcement, formwork and concreting)	4 days	Thu 25/12/14	Tue 06/01/15			Main constru
58	5.13 Placement of the formwork (corridor)	3 days	Tue 27/01/15	Thu 29/01/15			Main cor
59 6	First floor	33 days	Fri 30/01/15	Tue 17/03/15			r 1
	6.1 Composite slab (reinforcement and concreting)	1 day	Mon 02/02/15	Mon 02/02/15			Main co
61	-	3 days	Mon 02/02/15	Wed 04/02/15			Main co
	6.3 Corridor (reinforcement and concreting)	2 days	Fri 30/01/15	Mon 02/02/15			Main co
		5 days	Tue 10/02/15	Mon 16/02/15			Main
	concreting) 6.5 Precast stairs	1 day	Tue 24/02/15	Tue 24/02/15			Ma
65	6.6 Precast columns	5 days	Thu 12/02/15	Wed 18/02/15			Mair
66	6.7 Concrete masonry	10 days	Thu 19/02/15	Wed 04/03/15			
67	6.8 Brickwork	10 days	Thu 19/02/15	Wed 04/03/15			
	6.9 Placement of props		Thu 05/03/15				

Project: Strabag	Task		Summary	 1	Inactive Milestone	\diamond	Duration-only	Start-or
Troject. Strabug	Split		Project Summary	00	Inactive Summary	0	Manual Summary Rollup	Finish-c
	Milestone	♦	Inactive Task		Manual Task		Manual Summary	Externa

01 Septer	nber 11 Februa	IFY	21 July		01 January		11	June		
12/05 28/07	13/10 29/12 Main construction labourers[5	16/03 0	01/06 17/08	02/11		18/01	04/04	20/06	05/0	09
	Main construction labourer	5[5]								
	Main construction labourer	s[5]								
	Main construction labo	urers[10]								
	Main construction labo	ourers[10]								
	Main construction la	hourers[10]·Loader								
	Tower crane;Main construc	tion labourers[5]								
	Main construction I	abourers[17]								
	Main construction	labourers[10];Tower of	crane							
	Main construction	labourers[7];Tower cr	ane							
	Main construction	labourers[2];Tower cr	rane							
	1									
	Tower crane;Conc	rete pump;Main const	ruction labourers[7]							
	Main constructio	n labourers[10];Tower	crane;Concrete pump							
	Main constru	ction labourers[10];To	ower crane;Concrete pu	Imp						
	Main const	ruction labourers[2];T	ower crane							
	Main construc	tion labourers[5];Tow	er crane							
		ruction labourers[5]								
	Main const	ruction labourers[5]								
	🞽 Main con	struction labourers[17]							
	Tower cr	ane;Main construction	labourers[5]							
	Main con	struction labourers[5]	;Tower crane							
	Tower cr	ane;Main constructior	a labourers[2]							
	Main construc	tion labourers[2] Con	crete pump;Tower crar	ne:Scaffold[2]						
				,						
	Main cor	struction labourers[5]	;Scaffold							
	Main co	nstruction labourers[5	;];Tower crane;Concret	e pump						
			10];Tower crane;Concre							
	Main co	nstruction labourers[2];Tower crane;Concret	e pump;Scaffol	d					
	Main	construction labourer	rs[10];Tower crane;Con	crete pump						
	Ma	in construction labour	ers[2];Tower crane							
	Mair	construction laboure	rs[5];Tower crane;Cond	rete pump						
		ain construction labou	urers[5]							
		ain construction labor	urers[5]							
		Main construction lab								
			GGI GI 3[1 /]							
	Start-only C	External Milestone		ical Split						
Summary Rollup Summary	Finish-only External Tasks	Deadline Critical		gress nual Progress						

	Task Name	Duration	Start	Finish	11 October 23/09	09/12	21 March 24/02	12/05
	6.10 Precast panels	3 days	Thu 12/03/15	Mon 16/03/15				. 2, 00
	6.11 Precast platforms	2 days	Thu 12/03/15	Fri 13/03/15				
	6.12 Universal beams (placement)	1 day	Tue 17/03/15	Tue 17/03/15				
	6.13 Sm-Metallic structure (assembly and	10 days	Thu 12/02/15	Wed 25/02/15				
	fixation) 7 Second floor	46 days	Thu 26/02/15	Tue 05/05/15				
	7.1 Composite slab (reinforcement and	1 day	Wed 18/03/15	Wed 18/03/15				
	concreting) 7.2 Perimeter beam (formwork,	3 days	Wed 18/03/15	Fri 20/03/15				
5	reinforcement and concreting) 7.3 Cavity walls (insulation, placing and	5 days	Thu 26/03/15	Wed 01/04/15				
	concreting) 7.4 Precast stairs	1 day	Thu 09/04/15	Thu 09/04/15				
	7.5 Precast columns	5 days	Mon 30/03/15	Fri 03/04/15				
)	7.6 Concrete masonry	10 days	Mon 06/04/15	Tue 21/04/15				
0	7.7 Brickwork	10 days	Mon 06/04/15	Tue 21/04/15				
	7.8 Placement of props	5 days	Wed 22/04/15	Tue 28/04/15				
2	7.9 Precast panels	3 days	Wed 29/04/15	Mon 04/05/15				
3	7.10 Precast platforms	2 days	Wed 29/04/15					
4	7.11 Universal beams (placement)	1 day	Tue 05/05/15	Tue 05/05/15				
5	7.12 Corridor (roofing corrugated sheet)	2 days		Fri 27/02/15				
6	8 Third floor	76 days	Mon 02/03/15					
7				Wed 06/05/15				
	8.1 Composite slab (reinforcement and concreting)	1 day						
3	8.2 Perimeter beam (formwork, reinforcement and concreting)	3 days	Wed 06/05/15					
)	8.3 Cavity walls (insulation, placing and concreting)	5 days	Thu 14/05/15	Wed 20/05/15				
C	8.4 Precast stairs	1 day	Thu 28/05/15	Thu 28/05/15				
	8.5 Precast columns	5 days	Mon 18/05/15	Fri 22/05/15				
	8.6 Concrete masonry	10 days	Mon 25/05/15	Wed 10/06/15				
3	8.7 Brickwork	10 days	Mon 25/05/15	Wed 10/06/15				
4	8.8 Placement of props	5 days	Thu 11/06/15	Wed 17/06/15				
5	8.9 Precast panels	3 days	Thu 18/06/15	Mon 22/06/15				
6	8.10 Precast platforms	2 days	Thu 18/06/15	Fri 19/06/15				
7	8.11 Universal beams (placement)	1 day	Tue 23/06/15	Tue 23/06/15				
8	8.12 Sm-Roofing (corrugated sheet)	8 days	Mon 02/03/15	Wed 11/03/15				
9	9 Fourth floor	32 days	Wed 24/06/15	Mon 31/08/15				
0	9.1 Composite slab (reinforcement and	1 day	Wed 24/06/15	Wed 24/06/15				
1	concreting) 9.2 Perimeter beam (formwork, reinforcement and concreting)	3 days	Wed 24/06/15	Fri 26/06/15				
2	9.3 Cavity walls (insulation, placing and	5 days	Thu 02/07/15	Wed 08/07/15				
)3	concreting) 9.4 Precast stairs	1 day	Thu 16/07/15	Thu 16/07/15				
)4	9.5 Precast columns	5 days	Mon 06/07/15	Fri 10/07/15				

Project: Strabag	Task		Summary	1	Inactive Milestone	\diamond	Duration-only	Star
Troject. Strabag	Split		Project Summary		Inactive Summary	0	Manual Summary Rollup	Finis
	Milestone	♦	Inactive Task		Manual Task		Manual Summary	Exte



)	Task Name	Duration	Start	Finish	11 October 23/09	09/12	21 March 24/02	12/05	
05	9.6 Concrete masonry	10 days	Mon 13/07/15	Tue 18/08/15	23/09	09/12	24/02	12/05	
06	9.7 Brickwork	10 days	Mon 13/07/15	Tue 18/08/15					
07	9.8 Placement of props	5 days	Wed 19/08/15	Tue 25/08/15					
108	9.9 Precast panels	3 days	Wed 26/08/15	Fri 28/08/15					
109	9.10 Precast platforms	2 days	Wed 26/08/15	Thu 27/08/15					
10	9.11 Universal beams (placement)	1 day	Mon 31/08/15	Mon 31/08/15					
111	10 Fifth floor	29 days	Mon 31/08/15	Thu 08/10/15					
112	10.1 Composite slab (reinforcement and	1 day	Mon 31/08/15	Mon 31/08/15					
113	concreting) 10.2 Perimeter beam (formwork,	3 days	Mon 31/08/15	Wed 02/09/15					
114	reinforcement and concreting) 10.3 Industrial lift assembly	2 days	Thu 03/09/15	Fri 04/09/15					
115	10.4 Cavity walls (insulation, placing and	2 days	Tue 08/09/15	Wed 09/09/15					
116	concreting) 10.5 Utility room (assembly)	16 days	Thu 17/09/15	Thu 08/10/15					
110		-		Wed 21/10/15					
	11 Building envelope	56 days							
118	11.1 Glazing structure	30 days	Tue 08/09/15	Mon 19/10/15					
119	11.3 Stone facing	37 days	Mon 13/07/15	Tue 01/09/15					
120	11.5 Remove tower crane	2 days	Tue 20/10/15	Wed 21/10/15					
121	11.6 Roofs	20 days	Thu 10/09/15	Wed 07/10/15					
122	12 Interior finish	68 days	Thu 08/10/15	Wed 27/01/16					
123	12.1 Interior partitions	4 days	Thu 08/10/15	Tue 13/10/15					
124	12.2 Wooden carpentry	15 days	Wed 14/10/15	Tue 03/11/15					
125	12.3 Electrical installation	15 days	Wed 04/11/15	Wed 25/11/15					
126	12.4 Air conditioning + Water + Heating	17 days	Wed 04/11/15	Thu 26/11/15					
127	installation 12.5 Raised floors + carpet	12 days	Fri 27/11/15	Mon 14/12/15					
128	12.6 Suspended ceilings	7 days	Fri 27/11/15	Mon 07/12/15					
129	12.7 Telecoms	15 days	Fri 27/11/15	Thu 17/12/15					
130	12.8 Lift installation	37 days	Tue 08/12/15	Wed 27/01/16					
131	12.9 Paint	20 days	Tue 08/12/15	Tue 19/01/16					
132	12.10 Railings	5 days	Wed 20/01/16						
132	13 Others	11 days		Thu 11/02/16					
	13.1 Outdoor constructions		Thu 28/01/16						
134		5 days							
135	13.2 Remove site huts	1 day	Thu 04/02/16	Thu 04/02/16					
136	13.3 Remove industrial lift	1 day	Thu 04/02/16	Thu 04/02/16					
137	13.4 Remove temporary installations	1 day	Fri 05/02/16	Fri 05/02/16					
138	13.5 Remove fenced	1 day	Mon 08/02/16	Mon 08/02/16					
139	13.6 Cleaning	3 days	Tue 09/02/16	Thu 11/02/16					
140	END	0 days	Thu 11/02/16	Thu 11/02/16					

					Manual Summary						
Project: Strabag	Split	Project Summary	 Inactive Summary	0	Duration-only Manual Summary Rollup	Finish-only	3	Deadline	+	Progress	
	Task	Summary	Inactive Milestone		Duration-only	Start-only	L	External Milestone	\diamond	Critical Split	



PICTURES TAKEN IN THE SITE

-General view of the site and surroundings:



Main building



Small building



Canal next to the site



Corridor that connects both buildings



View from the roof of the main building



-Organisation of the site:



Vehicular Access 1 + Pedestrians Access 1



Vehicular Access 2



Worksite huts



Pedestrians Access 2



Tower crane



Stockpile



-Precast columns:



Metal bars to connect columns and prefabricated platforms



Concrete pouring holes

-In situ columns and beams:







Precast column with a tube to drain the roof





-Composite beams:





Boyd beam reinforced with metal bars and concrete

-Brickwork and concrete masonry:



Porotherm bricks



Brickwork





Concrete blocks



Concrete masonry



Precast/bearing walls in the lift and stairs module



Metal bars to connect cavity walls



Placement with the tower crane



Base of a cavity wall



Luis Latorre Zaplana – Degree in Technical Arquitecture

-Precast walls:

-Precast stairs:





Precast stairs in the small building



Precast stairs in the main building



Supporting of the precast stairs in a landing

-Metallic structure (small building):



Universal beams and rectangular hollow profiles that hold the roof





STUDY AND CONSTRUCTIVE ANALYSIS OF DEINZE'S NEW CITY HALL



Corridor



-Aluminium carpentry:



Carpentry in the light well





Fixation of the carpentry



-Roof:



Small building's roof



Main building's roof



Raised floor with cut to length spacers (main building)



Sheet metal panels and concrete base to place installations on it

-Insulation/waterproofing:



PIR insulation and polyethylene membrane (retaining walls)



PIR insulation and polyethylene membrane (retaining walls)





Rockwool in partitions



Acoustic and thermal insulation panels "stertekt" for ceilings in the basement



Bitumen membrane applied with torch



PUR insulation and PE sheet in the basement

-Other elements:



Ramp to access to the basement



Cantilever in one access of the small building





Air conditioning tubes





Heating



Industial lift (two of the in the site)



Columns with and without natural stone lining



MSL (mean sea level) – XIX century



BIBLIOGRAPHY

- Tower crane MDT268 A J12 <u>https://goo.gl/3JOhPA</u>
- PUR insulation Kingspan <u>http://www.kingspan.com/</u>
- PIR insulation IKO Enetherm <u>http://www.enertherm.eu/</u>
- Bitumen membrane De Boer DeboRek <u>http://goo.gl/EbQUch</u>
- Porotherm bricks Wienerberger <u>http://www.wienerberger.be/binnenmuur</u>
- Concrete blocks Coeck <u>http://www.coeck.be/</u>
- YONG blocks <u>http://www.ytong.es/#_sub1544</u>
- False ceiling tiles OWA <u>http://www.owa.de/nl/</u>
- Stremaform plate Plaka Nederland <u>http://plakagroup.com/nl-NL/PLAKA-Nederland/</u>
- Concrete connection Schock Isokorb <u>http://www.schock-us.com/en_us/solutions/isokorb--189</u>
- Precast concrete elements <u>http://prefaxis.be/</u>
- Rock wool KNAUF <u>http://www.knauf.be/</u>
- Glazing Mosa Glas <u>http://www.mosaglas.nl/</u>
- Containers Vindevogel (renting) <u>http://www.containers-vindevogel.be/</u>
- Fenced Sulmon <u>http://www.sulmon.com/</u>
- Working huts Rob Units <u>http://www.robunits.be/</u>
- Acoustic and thermal insulation Stertekt panels <u>http://www.stertekt.com/</u>

